

Finnish Railway Network Statement 2015



Finnish Railway Network Statement 2015

Transport infrastructure data of the
Finnish Transport Agency 3/2013

Finnish Transport Agency
Helsinki 2013

Photograph on the cover: Simo Toikkanen

Online publication pdf (www.liikennevirasto.fi)

ISSN-L 1798-8276

ISSN 1798-8284

ISBN 978-952-255-383-6

Finnish Transport Agency
P.O. Box 33
FI-00521 Helsinki, Finland
Tel. +358 (0)29 534 3000

Foreword

The Finnish Transport Agency (FTA) publishes the Finnish Railway Network Statement (hereinafter the Network Statement) for the timetable period 2015. This is the twelfth Network Statement prepared in Finland, in accordance with the Finnish Railway Act. The Network Statement describes the access conditions, the state-owned railway network, the allocation capacity, the services supplied to railway undertakings and the principles of determining the infrastructure charge. The Network Statement is published for applicants for capacity for each timetable period separately. The present Network Statement is intended for the timetable period 14.12.2014–12.12.2015.

The Network Statement 2015 has been prepared based on the previous Network Statement taking into account the feedback received from users and the Network Statements of other European Infrastructure Managers.

The structure of the Network Statement follows the common European structure and comprises the following chapters:

- 1 General
- 2 Access conditions
- 3 Railway network
- 4 Capacity allocation
- 5 Services supplied to railway undertakings
- 6 Infrastructure charge

This is the first Finnish Railway Network Statement which also includes information from the publication *Rataverkon kuvaus* (i.e. Description of the Railway Network). This has been done in order to improve user-friendliness, since users no longer have to search for information in two different publications. This reform entails two annual updates of the Network Statement, in June and at the beginning of the timetable period. If necessary, there may also be intermediate updates.

The railway statutes are being revised and will probably enter into force during the timetable period 2015. The amendments due to the revised statutes will be made in the Network Statement immediately upon entry into force.

Within the Finnish Transport Agency, the Network Statement is the responsibility of the Traffic Services Department. Several specialists inside and outside the Finnish Transport Agency have been involved in the preparation of the Network Statement.

Helsinki, 13 December 2013

Finnish Transport Agency
Traffic and Information, Traffic Services Department

Table of contents

| | | |
|-------|---|----|
| 1 | GENERAL INFORMATION | 7 |
| 1.1 | Introduction..... | 7 |
| 1.2 | Objective | 7 |
| 1.3 | Legal Framework | 7 |
| 1.4 | Legal Status..... | 8 |
| 1.4.1 | General Remarks..... | 8 |
| 1.4.2 | Liability | 8 |
| 1.4.3 | Appeals Procedure..... | 8 |
| 1.5 | Structure of the Network Statement..... | 9 |
| 1.6 | Validity and Updating..... | 9 |
| 1.6.1 | Validity Period | 9 |
| 1.6.2 | Updating Process | 9 |
| 1.7 | Publishing | 10 |
| 1.8 | Contacts | 10 |
| 1.9 | Co-operation between Infrastructure Managers | 12 |
| 1.10 | Glossary | 12 |
| 2 | ACCESS CONDITIONS | 15 |
| 2.1 | Introduction..... | 15 |
| 2.2 | General Access Requirements | 15 |
| 2.2.1 | General Requirements for Operating Railway Traffic | 15 |
| 2.2.2 | General Requirements for Access to the Railway Network..... | 17 |
| 2.2.3 | Operating Licence..... | 17 |
| 2.2.4 | Safety Certificate | 18 |
| 2.2.5 | Cover of Liabilities..... | 19 |
| 2.3 | General Business Conditions | 19 |
| 2.3.1 | Framework Agreement..... | 19 |
| 2.3.2 | Access Contract | 20 |
| 2.3.3 | Other Agreements Regarding Railway Network Usage..... | 20 |
| 2.4 | Operational Rules and Legislative Information..... | 21 |
| 2.5 | Exceptional Transport | 21 |
| 2.6 | Dangerous Goods..... | 22 |
| 2.7 | Rolling Stock Acceptance Process Guidelines..... | 22 |
| 2.8 | Staff Acceptance Process | 23 |
| 3 | INFRASTRUCTURE | 25 |
| 3.1 | Introduction..... | 25 |
| 3.2 | Extent of Network | 25 |
| 3.2.1 | Multi-Track Line Sections | 25 |
| 3.2.2 | Limits..... | 25 |
| 3.2.3 | Connected Railway Networks | 26 |
| 3.3 | Network Description | 26 |
| 3.3.1 | Geographic Identification | 26 |
| 3.3.2 | Capabilities | 30 |
| 3.3.3 | Traffic Control and Communications Systems | 32 |
| 3.4 | Traffic Restrictions..... | 35 |
| 3.4.1 | Specialised Infrastructure..... | 35 |
| 3.4.2 | Environmental Restrictions..... | 36 |
| 3.4.3 | Dangerous Goods | 36 |

| | | |
|-------|---|----|
| 3.4.4 | Tunnel Restrictions | 37 |
| 3.4.5 | Bridge Restrictions..... | 38 |
| 3.4.6 | Overweight Load Transport | 38 |
| 3.5 | Availability of the Infrastructure | 38 |
| 3.6 | Passenger Stations | 38 |
| 3.7 | Freight Terminals..... | 38 |
| 3.8 | Service Facilities | 39 |
| 3.8.1 | Train Formation Yards..... | 39 |
| 3.8.2 | Storage Sidings..... | 39 |
| 3.8.3 | Maintenance and Service Facilities..... | 39 |
| 3.8.4 | Refuelling Facilities..... | 39 |
| 3.8.5 | Technical Equipment | 39 |
| 3.9 | Infrastructure Development..... | 40 |
| 4 | CAPACITY ALLOCATION | 41 |
| 4.1 | Introduction | 41 |
| 4.2 | Description of Process | 41 |
| 4.3 | Schedule for Train Path Requests and Allocation Capacity Requests..... | 43 |
| 4.3.1 | Schedule for Working Timetable | 43 |
| 4.3.2 | Requesting Rail Capacity for Temporary Traffic | 44 |
| 4.4 | Allocation Process | 44 |
| 4.4.1 | Coordination Process..... | 44 |
| 4.4.2 | Dispute Resolution | 47 |
| 4.4.3 | Congested Infrastructure | 47 |
| 4.4.4 | Impact of the Framework Agreements | 48 |
| 4.5 | Allocation of Capacity for Maintenance, Renewal and Enhancements..... | 49 |
| 4.6 | Non-Usage Rules..... | 50 |
| 4.7 | Exceptional Transport and Dangerous Goods | 50 |
| 4.8 | Special Measures to be taken in the Event of Disturbance | 51 |
| 4.8.1 | Principles..... | 51 |
| 4.8.2 | Operational Regulation | 51 |
| 4.8.3 | Foreseen Problems..... | 51 |
| 4.8.4 | Unforeseen Problems..... | 51 |
| 5 | SERVICES | 53 |
| 5.1 | Introduction | 53 |
| 5.2 | Services Offered by the Finnish Transport Agency | 53 |
| 5.3 | Services Offered by Others | 54 |
| 6 | CHARGES | 55 |
| 6.1 | Charging Principles and Services Included in the Infrastructure Charge..... | 55 |
| 6.2 | Charging System..... | 55 |
| 6.3 | Tariffs | 56 |
| 6.4 | Performance Scheme..... | 56 |
| 6.5 | Changes to Charges..... | 56 |
| 6.6 | Billing Arrangements..... | 57 |

APPENDICES

| | |
|-------------|---|
| Appendix 1 | Basic Information on Line Sections |
| Appendix 2 | Rail Traffic Operating Points |
| Appendix 3 | Transport Operating Regulations for the Tornio–Haaparanta Line Section |
| Appendix 4 | Loading Gauge |
| Appendix 5 | Structure Gauge |
| Appendix 6 | Superstructure Categories, EN Categories Derived from the Superstructure Categories and Permitted Speeds for Different Axle Loads |
| Appendix 7 | Electrification |
| Appendix 8 | Signalling Systems |
| Appendix 9 | Vibration-Related Speed Restrictions |
| Appendix 10 | Speed Limits due to Track Conditions |
| Appendix 11 | Maximum Train Speeds in Tunnels |
| Appendix 12 | Bridge-Related Restrictions |
| Appendix 13 | Major Track Work and Other Track Works Affecting traffic in 2015 |
| Appendix 14 | Passenger Information at the Stations of the State-Owned Railway network |
| Appendix 15 | GSM-R (RAIL) Network |
| Appendix 16 | Rolling Stock Speed in the Railway Network |
| Appendix 17 | Monitoring of Rolling Stock |

1 General information

1.1 Introduction

The Network Statement is published in accordance with the Railway Act ([304/2011](#))¹ and [Directive 2012/34/EU](#)² of the European Parliament and of the Council on the allocation of railway infrastructure capacity and the levying of charges for the use of railway infrastructure and safety certification (hereinafter referred to as the "Capacity and Infrastructure Charge Directive"). The Network Statement for the timetable period 2015 is the twelfth Network Statement published in Finland.

1.2 Objective

The Network Statement is published for the use of applicants for capacity for each timetable period separately. The Network Statement describes the access conditions, state-owned railway network, capacity allocation, services supplied to railway undertakings and the basis on which the infrastructure charge is determined. The Network Statement specifies in detail the general rules, deadlines, procedures and grounds applicable to capacity allocation and the charging systems.

Railway undertakings can request capacity for international traffic within the European Economic Area, as well as for domestic freight traffic. Domestic passenger traffic may only be operated by VR Group in those rail lines which include in monopoly agreement between the Ministry of Transport and Communications and VR Group. Any railway undertaking can operate passenger traffic on the line sections which are not included in the agreement. VR Group has the exclusive right to operate railway transit traffic to and from Russia in the Finnish railway network, until the renewed agreement on transit traffic between Finland and Russia enters into force.

1.3 Legal Framework

Current Legislation

In accordance with the Railway Act, the Finnish Transport Agency publishes information on the provisions of the Railway Act, as well as on the provisions issued under this Act and other provisions, concerning

1. the right of access to the railway network;
2. the principles of determining the infrastructure charges;
3. applying for rail capacity and the related deadlines;
4. the requirements for and approval of railway rolling stock; as well as
5. other conditions concerning operating and starting the operation of railway traffic.

¹ <http://www.finlex.fi/fi/laki/ajantasa/2011/20110304>

² <http://eur-lex.europa.eu/LexUriServ/LexUriServ.do?uri=OJ:L:2001:075:0029:0046:EN:PDF>

The Finnish Transport Agency publishes information on the nature and extent of the railway network in the Network Statement for each timetable period. This information is contained in Chapter 3 of this Network Statement. The provisions issued by the Finnish Transport Agency on:

1. specialised infrastructure under the Railway Act (point 3.4.1)
2. the priority order to be applied to congested infrastructure under the Railway Act (point 4.4.3)
3. the threshold quota for the minimum use of railway infrastructure on each train path under the Railway Act (point 4.6) are also published in the Network Statement.

1.4 Legal Status

1.4.1 General Remarks

The Network Statement is not a regulation issued by the Finnish Transport Agency but a document providing information.

1.4.2 Liability

Information published in the Network Statement does not affect regulations issued by the Finnish Transport Agency or the Finnish Transport Safety Agency. Information on the third parties mentioned in the Network Statement may also change during the timetable period.

1.4.3 Appeals Procedure

A decision taken by the Finnish Transport Agency may be appealed against under the Railway Act by filing a claim for rectification with the Regulatory Body, which in Finland is the Finnish Transport Safety Agency. A claim for rectification may be filed if the decision taken by the Regulatory Body concerns:

1. priority order for allocating capacity in individual cases
2. levying of the infrastructure charge
3. capacity allocation
4. allocation of urgently needed capacity
5. issuance of a safety certificate or
6. the access contract.

The claim for rectification shall be filed with the Finnish Transport Safety Agency within 30 days of the date of receipt of notice of the decision. The Finnish Transport Safety Agency shall decide on the claim for rectification within two months of the date on which all relevant information for taking a decision has been delivered to it. The decision shall, however, be taken within ten days of the date on which all relevant information has been delivered if the claim concerns the priority order in individual cases, capacity allocation or a request for urgently needed capacity.

1.5 Structure of the Network Statement

This Network Statement follows the common structure set for Network Statements by RailNetEurope.

The Network Statement consists of five more chapters in addition to this one. The second chapter deals with the requirements for accessing the railway network, the third handles the railway network infrastructure, the fourth covers issues related to capacity allocation, the fifth chapter is about services offered to railway undertakings, and the sixth chapter deals with the infrastructure charge and charging principles. The Network Statement includes appendices that provide a more detailed description of the railway network features and other issues related to railway traffic operations.

1.6 Validity and Updating

1.6.1 Validity Period

The Network Statement is valid for one timetable period. It is published four months ahead of the expiry of the deadline for submission of capacity requests that is 12 months ahead of the timetable period. The Network Statement 2015 is intended for the timetable period 2015, that is, for the period 14.12.2014–12.12.2015. The Network Statement for the timetable period 2016 will be published by 12.12.2014 at the latest.

1.6.2 Updating Process

If information contained in item 1.3 changes, the Finnish Transport Agency will publish the changes on its website <http://www.liikennevirasto.fi>³.

The Appendix 13 of the Network Statement presents an estimate of the track work that is to be done during the timetable period 2015 and which may affect traffic. The working programme, timing of tasks and the required track work will change as the funding and plans become more focused. The Finnish Transport Agency will publish the list of track work and maintain an updated version of the document on the Finnish Transport Agency's website <http://www.liikennevirasto.fi>⁴.

The text and appendices of the Network Statement may be updated once it has been published. The updates will be made available on the Finnish Transport Agency's website <http://www.liikennevirasto.fi>⁵.

³ http://portal.liikennevirasto.fi/sivu/www/e/professionals/network_statement

⁴ http://portal.liikennevirasto.fi/sivu/www/f/ammattiliikenteen_palvelut/rataverkolla_liikennointi/liikennesuunnittelu/ratatyot

⁵ http://portal.liikennevirasto.fi/sivu/www/e/professionals/network_statement

1.7 Publishing

The Network Statement is published in three languages: Finnish, Swedish and English. If any discrepancies are found between the different language versions, the Finnish language version will prevail. All language versions are available in PDF format on the Finnish Transport Agency's website <http://www.liikennevirasto.fi>⁶.

Development plans for the railway network for 2014–2017 are presented in the Finnish Transport Agency's action plan (TTS)⁷. Statistics concerning the railway network and railway traffic are presented in the annually published [Finnish Railway Statistics](#)⁸.

1.8 Contacts

Finnish Transport Agency

The Finnish Transport Agency operates under the auspices of the Ministry of Transport and Communications, assuming responsibility for maintaining and developing the state-owned railway network, allocating rail capacity, conducting traffic control and directing traffic. The Finnish Transport Agency is also responsible for maintaining roads and developing and safeguarding the operating prerequisites of merchant shipping and other forms of waterborne traffic.

Finnish Transport Agency Organization




Figure 1. The Finnish Transport Agency's organisational chart.

⁶ http://portal.liikennevirasto.fi/sivu/www/e/professionals/network_statement

⁷ http://portal.liikennevirasto.fi/sivu/www/f/liikennevirasto/tapamme_toimia/sunnittelu_seuranta

⁸ http://portal.liikennevirasto.fi/sivu/www/e/fta/statistics/traffic_statistics

P.O. Box 33 (street address: Opastinsilta 12 A)
FI-00521 HELSINKI
FINLAND
E-mail: kirjaamo(at)liikennevirasto.fi
Internet: <http://www.liikennevirasto.fi>⁹

On matters regarding entering the market or railway traffic, e-mail can be sent to oss(at)liikennevirasto.fi.

Other contact information can be found on the Finnish Transport Agency's website <http://www.liikennevirasto.fi>¹⁰.

Ministry of Transport and Communications

The Ministry of Transport and Communications is responsible for two broad sectors: transport policy and communications policy.

In the transport sector, the Ministry's responsibilities include transport systems and networks, transport of people and goods, traffic safety, and issues relating to climate and the environment. In the communications sector, the Ministry takes care of issues relating to communications networks, information security and data protection, information society policy, the mass media, and postal services.

PO Box 31 (street address: Eteläesplanadi 16-18)
FI-00023 VALTIONEUVOSTO
FINLAND
E-mail: kirjaamo(at)lvm.fi
Internet: <http://www.lvm.fi>¹¹

Finnish Transport Safety Agency

The Finnish Transport Safety Agency operates under the auspices of the Ministry of Transport and Communications. The Finnish Transport Safety Agency develops the safety of the transport system, promotes environmentally friendly transport solutions and is responsible for transport system regulatory duties.

P.O. Box 320 (Street Address: Kumpulantie 9)
FI-00101 HELSINKI
FINLAND
E-mail: kirjaamo(at)trafi.fi
Internet: <http://www.trafi.fi>¹²

Finnish Competition and Consumer Authority

The responsibilities of the Finnish Competition and Consumer Authority relate to implementing competition and consumer policy, ensuring good market performance, implementing competition legislation and EU competition rules, and securing the

⁹ <http://portal.liikennevirasto.fi/sivu/www/e/>

¹⁰ http://portal.liikennevirasto.fi/sivu/www/e/fta/contact_information

¹¹ <http://www.lvm.fi/web/en/home>

¹² <http://www.trafi.fi/en>

financial and legal position of the consumer. The agency also handles the supervision responsibilities of the Consumer Ombudsman.

P.O. Box 5 (Competition errands, street address: Pitkäsillanranta 3 A)
FI-00531 HELSINKI
FINLAND
E-mail: kirjaamo(at)kkv.fi
Internet: <http://www.kkv.fi>¹³

1.9 Co-operation between Infrastructure Managers

RailNetEurope (**RNE**)¹⁴ is a non-profit making association of Infrastructure Managers and Allocation Bodies (IMs/ABs). It is dedicated to facilitating International Traffic on the European Rail Infrastructure.

RNE has established one OSS contact point in every member country. Each customer can choose its favorite OSS contact point for all its needs regarding international rail services. From the initial questions related to network access to international path requests and *performance review after a train run – all these issues and more are handled* by one contact point for the whole international train journey at the customers' convenience.

A list of OSS contact persons is available at RailNetEurope's Internet pages at <http://www.rne.eu>¹⁵. The Finnish Transport Agency is no longer a member of RNE, but it is still active in the OSS. For more information, please send an e-mail to [oss\(at\)fta.fi](mailto:oss(at)fta.fi)

Network Statements of Other Countries

Internet addresses of Network Statements published by other railway network administrators are available at RailNetEurope's website at http://www.rne.eu/members_ns.html¹⁶.

1.10 Glossary

Coordination refers to a procedure by which the Finnish Transport Agency and the applicants attempt to solve situations where there are competing requests for rail capacity.

Engaging in railway traffic refers to the traffic conducted by a railway undertaking, traffic related to railway maintenance, traffic conducted by a museum train operator, a company or other association under private law whose main activity is some other

¹³ <http://www.kkv.fi/en-GB/>

¹⁴ <http://www.rne.eu/>

¹⁵ http://www.rne.eu/oss_network.html

¹⁶ http://www.rne.eu/members_ns.html

than operating railway traffic, or the railway infrastructure manager on the railway network.

Infrastructure management refers to construction, maintenance and development of tracks, of structures, equipment and systems connected with them, as well as of real property needed for infrastructure management.

LIIKE is a data system for requesting rail capacity.

Museum train traffic refers to traffic operated on a small scale on the railway network by a non-profit association with museum trains. Museum train refers to a stock registered as a museum train on the Finnish Transport Safety Agency's stock register.

Private siding refers to a track other than track owned by the Finnish Transport Agency.

Rail capacity refers to the capacity of a train path to carry train traffic over a particular period and depending on the characteristics of the railway network.

Railway infrastructure manager refers to the Finnish Transport Agency or a railway infrastructure manager of a private siding, on which the Railway Act (304/2011)¹⁷ is applied.

Railway undertaking refers to a company or other association, either public or under private law, whose main activity is to operate rail passenger or freight traffic. The company must have an appropriate operating licence issued in the European Economic Area and it is obliged to provide traction services. Undertakings providing only traction services are also regarded as railway undertakings.

Rail operator refers to railway undertakings, railway maintenance companies, infrastructure managers operating the railway network, and museum train operators. Other companies or associations operating in the railway network, and whose operations in the railway network are not part of their core activities, are also referred to as rail operators.

Ratapurkki is a data warehouse for railway data, which provides information about railway infrastructure for companies and data systems in the railway sector. The user interface is a browser, through which data can be searched via a map or through database reporting.

RATO refers to railway track's technical instructions, which include basic information on development, inspection and maintenance of a track and its equipment. RATO is based on the provisions issued by the Finnish Transport Safety Agency. **RATO**¹⁸ is published by the Finnish Transport Agency.

Advance information on train traffic (JETI) is a system, which includes the advance plans of track work and information on changes affecting traffic. Otherwise, these would have to be delivered by a traffic control message.

¹⁷ <http://www.finlex.fi/fi/laki/alkup/2011/20110304>

¹⁸ http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat_suunnittelijat/vaylanpidon_ohjeet/rakennuttaminen/rautatiet

Traffic control is the management of traffic on individual train paths. In addition traffic control duties include issuing permits and notices required for train traffic. Traffic control also includes protecting the track work areas, issuing permits for track work and receiving information on the termination of such work. If so required due to the volume and nature of traffic, or type of safety apparatus, a signal or turnout worker, shunting foreman, locomotive driver or a worker responsible for the safety of work done near the tracks or other person appointed in due order for the task may participate in traffic control to the extent required by their task.

TURO refers to safety instructions in track maintenance. The Finnish Transport Agency publishes the instructions on its website <http://www.liikennevirasto.fi>¹⁹.

Other, more detailed, definitions can be found in RATO ([Railway track technical instructions](#))²⁰.

¹⁹ http://www2.liikennevirasto.fi/julkaisut/pdf3/lo_2012-01_turo_web.pdf

²⁰ http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat_suunnittelijat/vaylanpidon_ohjeet/rakennuttaminen/rautatiet

2 Access Conditions

2.1 Introduction

Access requirements to the railway network are listed in this chapter. The prerequisites for operating railway traffic are an operating licence, safety certificate, allocated capacity and an access contract. In addition, for example, the rolling stock acceptance process and traffic safety staff qualifications are described in this chapter.

2.2 General Access Requirements

The legal framework of access to infrastructure is described in the Railway Act (304/2011)²¹. The provisions and instructions issued by the Finnish Transport Safety Agency and the Finnish Transport Agency shall be observed on the state-owned railway network. Information on the instructions issued by the Finnish Transport Safety Agency currently in force is available from the Finlex Data Bank, <http://www.finlex.fi>²² and on The Finnish Transport Safety Agency's website <http://www.trafi.fi>²³. Provisions issued by the Finnish Transport Agency are available on the Finnish Transport Agency's website <http://www.liikennevirasto.fi>²⁴.

The Act on safety and interoperability of the rail system (372/2011)²⁵ lays down, for example, the essential requirements for the rail system. The essential requirements can be supplemented with separate provisions.

Locomotives operating in the state-owned railway network must be fitted with an automatic train protection system (ATP). Museum stock can be operated on part of the railway network without automatic train safety equipment. Further information can be read from a chapter 3.3.3.6 ATP Systems.

2.2.1 General Requirements for Operating Railway Traffic

Operation of railway traffic on the state-owned railway network requires that the railway undertaking meet the following conditions:

1. The railway undertaking or international grouping of railway undertakings shall have an operating licence in accordance with the Railway Act or a corresponding operating licence issued in the European Economic Area.

²¹ <http://www.finlex.fi/fi/laki/alkup/2011/20110304>

²² <http://www.finlex.fi/fi/viranomaiset/normi/499001/>

²³ http://www.trafi.fi/rautatiet/saadokset/kansalliset_maaraykset

²⁴ http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat_suunnittelijat/vaylanpidon_ohjeet

²⁵ <http://www.finlex.fi/fi/laki/alkup/2011/20110372>

2. The railway undertaking shall have a safety certificate in accordance with the Railway Act, issued or approved by the Finnish Transport Safety Agency, which covers all the train paths on which traffic will be operated.
3. Capacity in accordance with the Railway Act has been allocated to the railway undertaking for its traffic.
4. The railway undertaking shall make an access contract with Finnish Transport Agency on necessary practical arrangements concerning the operating of railway traffic.
5. Other conditions for operating rail traffic, laid down in or under the Railway Act are in all respects fulfilled.

Access conditions and phases for entering the market are presented in Figure 2.




Figure 2. Phases for entering the market.

Museum Train Traffic

The same requirements described in this Network Statement are applied to museum train traffic as to other rail traffic, except with regard to the operating licence. The law provides that a museum train traffic operator must have a safety certificate granted by the Finnish Transport Safety Agency. The safety certificate will be granted upon application for a maximum of five years at a time. The prerequisites in order to be granted a safety certificate are presented in chapter 2.2.4.

Capacity may be requested only as ad hoc capacity.

Locomotives operating in the state-owned railway network must be fitted with an automatic train protection system (ATP) according to class B in the Finnish system (ATP-VR/RHK), or equipped with the European Train Control System in conjunction with legacy ATPs through a specific transmission module (ETCS + STM). Museum stock can be operated on part of the railway network without automatic train safety equipment. The line sections, on which the automatic train safety equipment is obligatory, are listed in the Finnish Transport Safety Agency's museum train traffic regulation ([RVI/295/411/2008](#))²⁶. Further information can be found in the chapter 3.3.3.6 ATP Systems.

The museum train traffic regulation (RVI/295/411/2008) will be updated in 2014.

2.2.2 General Requirements for Access to the Railway Network

The following railway undertakings or international groupings of railway undertakings may access the state-owned railway network to operate train traffic.

1. the railway undertakings and international groupings of railway undertakings referred to in the Railway Act providing domestic freight services or passenger services in international railway traffic between states belonging to the European Economic Area
2. VR Group has the exclusive right to operate domestic passenger traffic in the Finnish railway network on the line sections referred to in the agreement on exclusive rights between VR Group Ltd and the Ministry of Transport and Communications. Any railway undertaking can operate passenger traffic on the line sections which are not included in the agreement. VR Group has the exclusive right to operate railway transit traffic to and from Russia in the Finnish railway network, until the renewed agreement on transit traffic between Finland and Russia enters into force.

These railway undertakings and international groupings of railway undertakings may use the railway network in accordance with the Railway Act and the traffic operating points on the state-owned railway network for their traffic operating on separately agreed conditions (access contract). Other rail operators may also use the state-owned railway network, provided that the Finnish Transport Agency has given its consent.

2.2.3 Operating Licence

The Ministry of Transport and Communications issues an operating licence for the operation of railway traffic to applicants established in Finland. The granted operating licence is valid for the time being and the Ministry reviews the operating licence and its conditions every five years. An operating licence issued in one state belonging to the European Economic Area is valid throughout the territory of the European Economic Area. An operating licence granted elsewhere must be delivered to the Ministry of Transport and Communications for information.

²⁶ <http://www.finlex.fi/fi/viranomaiset/normi/499001/33637>

The prerequisite for granting the operating licence is that the main activity of the undertaking is to operate railway traffic. The undertaking must also have a safety certificate issued or approved by the Finnish Transport Safety Agency, a solid financial standing, a competent management team and sufficient liability insurance. The application for an operating licence is delivered to the Ministry of Transport and Communications.

2.2.4 Safety Certificate

The safety certificate is issued by the national safety authority. In Finland, it is issued by the Finnish Transport Safety Agency.

If a railway undertaking has been granted part A of the safety certificate in another country belonging to the European Economic Area, it must apply to the Finnish Transport Safety Agency for part B of the safety certificate before it can commence train operations or infrastructure management in Finland.

The safety certificate will be granted or approved for a maximum of five years at a time. The railway undertaking must apply for a new safety certificate as soon as its old certificate is no longer valid.

The safety certificate comprises two parts. Part A approves the safety management system, while part B accepts the documents and arrangements that the holder of the safety certificate has issued and put in place that indicates that the set requirements are fulfilled. The purpose of the safety certificate is to ensure that the applicant fulfills the safety requirements for its operations and that the undertaking has the necessary qualifications to operate safely on the railway network. These requirements are presented in the Railway Act. It is also possible to include other requirements in the safety certificate regarding railway safety. The purpose of these requirements is to ensure railway safety while taking into consideration the nature and scope of the railway traffic of the applicant. The aforementioned requirements are presented in more detail and explained in the instructions on how to apply for a safety certificate drawn up by the Finnish Transport Safety Agency.

The Finnish Transport Safety Agency requires that:

- the applicant's safety management system complies with regulations
- the applicant proves that it fulfils *those* rules and regulations on the use of the railway network that concern that part of the network where it intends to operate or engage in traffic operation and the applicant shows that it can safeguard compliance with the rules and regulations,
- the applicant proves that its staff groups and the staff groups of the subcontractor that it uses are appropriately trained and competent in their duties in accordance with the relevant regulations [concerning the network];
- the applicant proves that the rolling stock that it uses complies with the relevant regulations [concerning the network] and that the maintenance and servicing of the rolling stock are in order.

The Finnish Transport Safety Agency has drawn up instructions on how to apply for a safety certificate. The form used to apply for the safety certificate can be obtained from the Finnish Transport Safety Agency. The written application shall be submitted to the Finnish Transport Safety Agency. The Finnish Transport Safety Agency shall consider the application and if necessary request further information. The Finnish

Transport Safety Agency shall decide on the issuance or approval of the safety certificate within four months after the request has been filed. The Finnish Transport Safety Agency may grant a safety certificate for the entire state-owned railway network or individual train paths. If the rules or regulations on the safety of the rail system are essentially amended, the Finnish Transport Safety agency may review the certificate or part thereof. If the operation of the holder of the safety certificate alters essentially in nature or extent, it shall re-apply for approval of the safety certificate insofar as the change has an effect on the terms and conditions of the safety certificate.

2.2.5 Cover of Liabilities

The rail transport operator and infrastructure management company shall have sufficient liability insurance or other corresponding arrangement in case of such damage incurred by a party due to rail transport operations for which the rail transport operator or infrastructure management company is by law or contract responsible. The nature and scope of operations and risks related to the operations must be taken into account in evaluating the sufficiency of the insurance or a similar arrangement. The insurance or other corresponding arrangement shall be in force for the duration of the entire period during which rail transport is operated. More information can be found from the Finnish Transport Safety Agency's [guideline²⁷](#) regarding the insurance.

2.3 General Business Conditions

2.3.1 Framework Agreement

The Finnish Transport Agency may make a framework agreement on the use of capacity with applicants for capacity. The purpose of such an agreement is to specify the characteristics of the capacity requested by the applicant. The framework agreement does not, however, entitle the applicant to obtain such capacity as is specified in the agreement.

Railway undertakings shall request the capacity specified in the framework agreement for each timetable period separately. If requested, the Finnish Transport Agency allocates the capacity specified in the framework agreement following the procedure laid down in the Railway Act. Correspondingly, the access contract shall be concluded for each timetable period separately regardless of the framework agreement. The framework agreement does not, however, impede the application of the provisions of the Railway Act to other applicants for capacity.

The framework agreement is made for a maximum of five years. For special reasons, the Finnish Transport Agency may, however, also conclude framework agreements for a longer period. Conclusion of an agreement for more than five years can, however, be justified only by contracts, special investments or special business risks connected with the transport business of the party with which the agreement is concluded, as well as by the large-scale and long-term investments of the party with which the agreement is concluded or the contractual obligations connected with such activities.

²⁷ http://www.trafi.fi/filebank/a/1327667636/d582c3ee14540cf9601cad2e3d3e6401/9079-OHJE_RAUTATIELIIKENTEEN_HARJOITTAJAN_vastuuvakuutuksesta.pdf

2.3.2 Access Contract

Railway undertaking shall make an access contract with the Finnish Transport Agency on the use of necessary services with regard to the state-owned railway network and railway traffic operations. These services include, for example, the use of marshalling yards, storage sidings and other tracks, as well as use of traffic control services. It is also possible to agree on other practical arrangements concerning railway traffic operations.

The railway traffic operator shall contact the Finnish Transport Agency to prepare the access contract and contractual negotiations as early as possible, preferably before applying for capacity. The Finnish Transport Agency makes this contract with each licence holder while taking into account the nature and scale of capacity allocated. The access contract is made for each timetable period and can be changed if decisions made during the timetable period concerning the allocation of capacity or other facts, for example, concerning the condition of the railway network so require. The access contract can only be concluded after all conditions stipulated in the Railway Act for operating railway traffic have been fulfilled. After the contract has been concluded, traffic may begin.

Maintenance entrepreneurs do not have to conclude a separate access contract on the use of the railway network, since the right to use the railway network is already included in the maintenance contract.

2.3.3 Other Agreements Regarding Railway Network Usage

Rail infrastructure agreement between infrastructure managers

The agreement comprises e.g. the operation between railway networks, traffic control, the dividing line between railway networks, its ownership and maintenance, as well as the cooperation between infrastructure managers. In order to enter into an agreement, the infrastructure manager shall submit a request in free form to the Finnish Transport Agency at the address kirjaamo@fta.fi.

Agreement on the use of individual traffic operating points

Rail operators, whose operations in the railway network are not part of their core activities, may only use the state-owned railway network or individual traffic operating points in the network, if they have concluded an agreement on the use with the Finnish Transport Agency before commencing operation. The agreement is renewed every timetable period. In order to enter into an agreement, the operator of railway traffic shall send an application in free form to the Finnish Transport Agency at the address: kirjaamo@fta.fi.

Marshalling yard agreement

At traffic operating points where there are many rail operators, all actors negotiate a marshalling yard agreement. This agreement relates to the common rules, the use and operation of tracks on the marshalling yard in question, or on parts of it. The marshalling yard agreement is an appendix to the access contract or to the agreement on the use of individual traffic operating points. The marshalling yard agreement is renewed every timetable period. The Finnish Transport Agency summons the parties to negotiate the marshalling yard agreement.

Agreement on the operation of track cars

Track cars must not be operated on line sections with commercial traffic in the state-owned railway network. However, an agreement can be concluded on operation of track cars on certain line sections which are closed to traffic, provided that the track conditions are satisfactory and the safety requirements met. The entry of such an agreement is always decided on a case-by-case basis and the Finnish Transport Agency may reject an agreement. Requests concerning this matter shall be addressed to kirjaamo(at)fta.fi.

RAILI Agreement

In the state-owned railway network, the communication between traffic control, operation and track work takes place in the RAILI network. Companies operating in the state-owned railway network shall enter a RAILI agreement with the Finnish Transport Agency. In order to enter into an agreement, the company shall fill in the form on the Finnish Transport Agency's website and send it to the Finnish Transport Agency. More information can be found on the Finnish Transport Agency's website <http://www.liikennevirasto.fi>²⁸.

2.4 Operational Rules and Legislative Information

Operational rules drafted by the Finnish Transport Agency can be viewed on the Finnish Transport Agency's website <http://www.liikennevirasto.fi>²⁹ and regulations drafted by the Finnish Transport Safety Agency on its website <http://www.trafi.fi>³⁰. Legislative information can be viewed on the Finlex website <http://www.finlex.fi>³¹.

2.5 Exceptional Transport

Traffic restrictions are dealt with in item 3.4 and in Appendix 16. Regulations concerning railway traffic and rolling stock can be viewed on the Finlex website <http://www.finlex.fi>³² and other instructions on the Finnish Transport Safety Agency's website <http://www.trafi.fi>³³. Other provisions can be viewed on the Finnish Transport Agency's website <http://www.liikennevirasto.fi>³⁴.

²⁸ http://portal.liikennevirasto.fi/sivu/www/f/ammattiliikenteen_palvelut/rataverkolla_liikennointi/gsm_r_verkko

²⁹ http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat_suunnittelijat/vaylanpidon_ohjeet

³⁰ <http://www.trafi.fi/rautatiet/saadokset>

³¹ http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat_suunnittelijat/vaylanpidon_ohjeet

³² <http://www.finlex.fi/fi/viranomaiset/normi/499001/>

³³ <http://www.trafi.fi/rautatiet/saadokset>

³⁴ http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat_suunnittelijat/vaylanpidon_ohjeet

An exceptional transport permit is granted by the Finnish Transport Agency. More information can be found the appendices 4, 12 and 16.

2.6 Dangerous Goods

Transport of dangerous goods is dealt with in item 3.4.3. Regulations concerning railway traffic and rolling stock can be viewed on the Finlex website <http://www.finlex.fi>³⁵ and other instructions on the Finnish Transport Safety Agency's website <http://www.trafi.fi>³⁶.

2.7 Rolling Stock Acceptance Process Guidelines

An authorisation issued by the Finnish Transport Safety Agency is required for placing rolling stock in service. This authorisation can be issued for rolling stock that meets the requirements valid in Finland, which is laid down in legislation.

The requirements are based on the interoperability requirements for the rail system in accordance with Community law and the Finnish Transport Safety Agency has issued complementary and more detailed instructions. Conformity can be proved by the EC Declaration of Conformity or a corresponding declaration issued within the European Economic Area. Before issuing the authorisation, the Finnish Transport Safety Agency will ask for the Finnish Transport Agency's statement on stock type's or unit's suitability for railway network, in order to define possible restrictions.

The Finnish Transport Safety Agency maintains a register monitoring the validity and traffic safety of rolling stock. The purpose is to promote rail system safety and identify rolling stock. The rolling stock is recorded in a register maintained by the Finnish Transport Safety Agency, if the rolling stock has been granted a commissioning licence in Finland. Rolling stock that will be used on the state's railway network and has been granted a commissioning licence elsewhere within the European Economic Area or in a country outside the EEA must also be recorded in the register. Any rolling stock used on private sidings will also be recorded in the register.

The Finnish Transport Safety Agency can also register rolling stock for a limited time upon request. A fixed-period registration is also possible for any rolling stock that has been granted a commissioning licence in another country, if it has been granted a commissioning licence in Finland and is used on the state's railway network only temporarily.

The rolling stock register must include information on the owner, holder and renter of the rolling stock. The more detailed regulations on related information on other rolling stock to be recorded in the register will be set forth in a Council of State decree.

³⁵ <http://www.finlex.fi/fi/viranomaiset/normi/499001/>

³⁶ <http://www.trafi.fi/rautatiet>

With regards to any rolling stock used for railway traffic between Finland and Russia, the register must include information on the vehicle owner or renter, any possible limitations on the vehicle use and information on the vehicle's maintenance plan in so far as is essential to the vehicle safety.

The Finnish Transport Safety Agency provides more detailed information about the requirements and other matters related rolling stock.

The Finnish Transport Agency shall approve any rolling stock that is used solely for track work. If the stock at any point is used as a train or for shunting, it shall be approved by the Finnish Transport Safety Agency.

On the line section Toijala–Valkeakoski, there is a level crossing with a special warning system. Rolling stock and track construction/ maintenance machines on this line section must be equipped with transmitters of the system. A separate instruction on the operations will be available in summer 2014 at the Finnish Transport Agency's Infrastructure Management field.

RFID tags must be attached to all rolling stock.

The regulations and guidelines for track construction and maintenance machines can be found in chapter 6 of [LIMO](#)³⁷ (technical regulations and guidelines for rolling stock).

2.8 Staff Acceptance Process

Personnel with tasks related to traffic safety shall meet the health, training and other qualification requirements laid down in Finnish legislation. Specific provisions on qualifications are laid down in the Act on Traffic Safety Tasks in the Railway System (hereinafter the Qualification Act) which entered into force on 1 January 2010. The Act 860/2012 of 1 January 2013 on Traffic Safety Tasks in the Railway System, as amended, amends the Qualification Act ([1664/2009](#))³⁸. The Qualification Act lays down provisions for the qualifications required for personnel performing traffic safety tasks which have a direct impact on traffic safety. Those performing these tasks shall also meet the Finnish Transport Safety Agency requirements concerning health, training and other qualifications. The qualification requirements vary depending on the tasks.

Three Government Decrees have been issued pursuant to the Qualification Act. These entered into force on 15 January 2013. The Government Decree [12/2013](#)³⁹ lays down provisions on the language skills required by personnel with traffic safety tasks in the railway system. Government Decree [13/2013](#)⁴⁰ applies e.g. to the requirements regarding educational institutes providing railway safety training, instructors and examiners of tests taken by drivers of rolling stock. Government Decree [11/2013](#)⁴¹

³⁷ http://www.trafi.fi/filebank/a/1337751267/76847b3ff91e21745ca9ff5193d7c8e9/9723-Kumottu-LIMO_6.pdf

³⁸ <http://www.finlex.fi/fi/laki/alkup/2009/20091664>

³⁹ <http://www.finlex.fi/fi/laki/alkup/2013/20130012>

⁴⁰ <http://www.finlex.fi/fi/laki/alkup/2013/20130013>

⁴¹ <http://www.finlex.fi/fi/laki/alkup/2013/20130011>

applies to the qualification data of the traffic safety personnel to be entered into the railway system qualification register maintained by the Finnish Transport Safety Agency and into the supplementary certificate register of the traffic operator.

The Finnish Transport Safety Agency has issued more specific regulations pursuant to the Qualification Act. The regulation on training programmes for traffic safety tasks in the railway systems entered into force on 1 January 2011. Furthermore, the agency has issued regulations on the health requirements and health examinations for personnel with traffic safety tasks in the railway system. These regulations entered into force on 3 January 2011. The Finnish Transport Safety Agency has also issued a regulation, which entered into force on 15 May 2012, on the requirements regarding psychological aptitude and psychological personality assessments of personnel with traffic safety tasks in the railway system.

The amended Qualification Act and the Government Decrees and Regulations issued under the Qualification Act can be found (in Finnish) on the Finnish Transport Safety Agency's website <http://www.trafi.fi> (Säädökset)⁴².

The Qualification Act does, however, not apply to any such tasks which only have an indirect impact on traffic safety in the railway system. Therefore, the Finnish Transport Agency has issued safety instructions for track maintenance, which entered into force on 16 April 2012, regarding the specific technical qualifications (other than traffic safety qualifications) required for e.g. track work. These instructions can be found in Finnish on the Finnish Transport Agency's website:

<http://www.liikennevirasto.fi>⁴³.

A safety certificate can only be granted or approved, if the rail operator has submitted information to the Finnish Transport Safety Agency on the qualifications of personnel or any other persons performing traffic safety tasks in the railway system and to the extent necessary, on a case-to-case basis, of the qualifications of persons handling the technical certificates for track maintenance. If necessary, the Finnish Transport Safety Agency may upon issuing the safety certificate examine in other ways and in more detail whether a person or persons employed by the railway traffic operator or otherwise connected to his or her operation meets the set qualifications.

⁴² <http://www.trafi.fi/rautatiet/saadokset>

⁴³ http://www2.liikennevirasto.fi/julkaisut/pdf3/lo_2012-01_turo_web.pdf

3 Infrastructure

3.1 Introduction

The infrastructure refers to the state-owned railway network managed by the Finnish Transport Agency. The Finnish Transport Agency's infrastructure management comprises the construction and maintenance of tracks, structures and equipment connected with them, as well as of the immoveable property needed for infrastructure management and planning.

3.2 Extent of Network

3.2.1 Multi-Track Line Sections

3.2.1.1 *Double-Track Line Sections*

Leppävaara-Kirkkonummi
Huopalahti-Vantaankoski(-Havukoski from 1.7.2015)
Kytömaa-Kyrölä
Purola-Riihimäki-Sääksjärvi
Kouvola-Juurikorpi
Pohjois-Louko-Seinäjoki asema-Ruha
Kytömaa-Hakosilta
Riihimäki asema-Luumäki
Tampere tavara-Lielähti
Tampere Järvensivu-Orivesi

3.2.1.2 *Three-Track Line Sections*

Kyrölä-Purola
Sääksjärvi-Tampere tavara

3.2.1.3 *Four-Track Line Sections*

Helsinki asema-Leppävaara
Helsinki asema-Kytömaa

3.2.2 Limits

The available network is presented graphically in Figure 3 (state-owned railway network in the beginning of timetable period 2014) and in Appendix 1 (Basic Information on Railway Sections).

The following line sections are closed to traffic:

- Ruosniemi-Niinisalo
- Kihniö-Haapamäki
- Pesiökylä-Taivalkoski

- Kolari–Äkäsjoki
- Niesa–Rautuvaara
- Kiukainen–Säkylä
- Isokylä–Kellosekä
- Lautiosaari – Elijärvi
- Lohja–Lohjanjärvi

All changes will be published on the Finnish Transport Agency's website <http://www.liikennevirasto.fi>⁴⁴.

3.2.3 Connected Railway Networks

There is a rail connection from Finland to Sweden via Tornio. The main outlines of traffic operating on the Tornio–Haaparanta line section are presented in Appendix 3. The Swedish infrastructure manager is Trafikverket.

A rail connection exists from Finland to Russia via Vainikkala, Imatrankoski, Niirala and Vartiuss. Railway traffic between Finland and Russia is based on the Rail Traffic Agreement between Finland and Russia. VR Group has the exclusive right to operate railway transit traffic to and from Russia in the Finnish railway network, until the renewed agreement on transit traffic between Finland and Russia enters into force.

3.3 Network Description

3.3.1 Geographic Identification

3.3.1.1 Track Typologies

The network is presented in Figure 3 (railway network map) and in the Appendix 1 (Basic Information on Railway Sections).

3.3.1.2 Track Gauges

The nominal track gauge on the railway network is 1,524 mm. The speed-dependent limit values for the track gauge are indicated in the Finnish Transport Safety Agency's provision called "Rautatiejärjestelmän infrastruktuuriosajärjestelmä" (Trafi/18888/03.04.02.00/2011). The provision is available from the Finlex Data Bank, <http://www.finlex.fi>⁴⁵.

3.3.1.3 Stations and Nodes

The available traffic operating points (stations) are presented in Figure 4 (Rail traffic operating points) and in Appendix 2 (Rail Traffic Operating Points).

⁴⁴ http://portal.liikennevirasto.fi/sivu/www/e/professionals/network_statement

⁴⁵ <http://www.finlex.fi/fi/viranomaiset/normi/499001/35207>




Figure 3. State-owned railway network at the beginning of timetable period 2015.




Figure 4. Traffic operating points on the state-owned railway network at the beginning of timetable period 2015.




Figure 5. Trans-European railway network in Finland (The Finnish TEN network).

3.3.2 Capabilities

3.3.2.1 Loading Gauge and Structure Gauge

The loading gauge (KU) in Appendix 4, and the structure gauge (ATU) in Appendix 5, are used throughout the state-owned railway network. On private industrial sidings, there may be both loading and structure gauge limitations, which railway undertakings shall clarify separately before carrying out transportation.

The Finnish Transport Safety Agency provides more information on the vehicle gauge (LKU): <http://www.trafi.fi>⁴⁶. Further information on the structure gauge of the track can be found in the Finnish Transport Safety Agency regulation [Trafi/18888/03.04.02.00/2011](#)⁴⁷ (Infrastructure subsystem of the conventional rail system). Further information on the track work gauge can be found in [TURO](#)⁴⁸ (safety instructions in track maintenance).

3.3.2.2 Weight Limits

Axle Loads

225 kN axle loads are permitted on most of the railway network. The maximum permitted axle loads per line section are indicated in Appendix 6 (Superstructure Categories, EN Categories Derived from the Superstructure Categories and Permitted Speeds for Different Axle Loads). The same appendix specifies the axle loads and restrictions in connection with overweight loads and the wagons used in the eastern transit traffic.

Metre Loads

The permitted metre load of rolling stock throughout the state-owned railway network is 80 kN/m.

3.3.2.3 Line Gradients

The maximum gradient is 20 mm/m on the main lines and 22.5 mm/m on the secondary lines. The maximum gradient of line sections measured over a distance of 1,200 metres is presented in Appendix 1 (Basic Information on Line Sections).

The gradient between the traffic operating points Leinelä and Kivistö on the Ring Rail Line is 40 mm/m.

3.3.2.4 Line Speeds

The maximum speed is 220 km/h for passenger trains and 120 km/h for freight trains. The maximum speed on tracks without ATP is 80 km/h. The speeds permitted for passenger and freight trains on the railway network are indicated in Appendix 6

⁴⁶ http://www.trafi.fi/rautatiet/saadokset/kansalliset_maaraykset/kumotut_maaraykset

⁴⁷ <http://www.finlex.fi/fi/viranomaiset/normi/499001/35207>

⁴⁸ http://www2.liikennevirasto.fi/julkaisut/pdf3/lo_2012-01_turo_web.pdf

(Superstructure Categories, EN Categories Derived from the Superstructure Categories and Permitted Speeds for Different Axle Loads).

Areas where speed can be temporarily increased due to a steep gradient

A train with a maximum speed of 70 km/h is allowed to exceed its train-specific speed by 10 km/h in the following areas:

- Taavetin mäki in the direction Lä-Kvl: km 244.0-234.0
- Sitikkalan mäki in the direction Lä-Kvl: km 170.2-161.5
- Härmänmäki in the direction Aro-Kon: km 683.0-673.0

If in areas mentioned above (Taavetin mäki, Sitikkalan mäki and Härmänmäki) are temporary speed limits which are under 70 km/h, they must be obeyed.

3.3.2.5 Maximum Train Lengths

The maximum train length permitted on a line section shall be such that trains can also use secondary tracks at the traffic operating points. Trains need not, however, be capable of using all secondary tracks at all traffic operating points. The train lengths used for dimensioning line sections are 700, 750, 925 and 1100 metres. The longest secondary tracks at each traffic operating point are indicated in Appendix 2 (Rail Traffic Operating Points).

3.3.2.6 Power Supply

The nominal voltage of the electrification is 25 kV/50 Hz AC. On all electrified lines, power is taken from the contact line above the track. One or both of the running rails and return conductors form a return circuit. The neutral sections will be located at the overhead line near substations. Rolling stock cannot collect current from these neutral sections. The main switch of electric locomotive or electric train must be opened at the neutral sections. The electric traction unit of the train is not allowed to stop at a neutral section.

The width of the pantograph head shall be 1,950 mm. The maximum stagger of the contact wire is 400 mm. The contact wire height can vary from 5600 to 6500 mm. The normal height is 6150 mm. The electrified line sections are indicated in Appendix 7 (Electrification).

The maximum current supply capacity of the overhead line for electrically hauled stock is 350-800 A. The available current is affected by the number and position of stock using electric power at the same time in the power supply area.

For fixed installations, electrification is described in part 5 "[Sähköistetty rata](#)"⁴⁹ (Electrified railway) of the Ratatekniset ohjeet (RATO) publication.

⁴⁹ http://www2.liikennevirasto.fi/julkaisut/pdf4/rato_5_sahkoistetty_rata.pdf

Electrification for the electric equipment of rolling stock is described in the Finnish Transport Safety Agency's provision called "Rautatiekaluston sähköjärjestelmä" (RVI/376/411/2008) as well as in the "Liikkuva kalusto" instruction record number 4470/090/2011. The provision is available from the Finlex Data Bank <http://www.finlex.fi>⁵⁰.

The new rolling stock acquired after the year 2012 must have energy meters.

3.3.3 Traffic Control and Communications Systems

3.3.3.1 Signalling Systems

The signalling systems in use are indicated in Appendix 1 (Basic Information on Line Sections) and graphically in Appendix 8 (Signalling Systems).

A line with section block is a line divided into block sections. Only one train may be in a block section at a time. Issues related to section blocks are presented in the Finnish Transport Safety Agency's provision called "Turvalaitteet rautatiejärjestelmässä" (RVI/873/410/2009) as well as in RATO publication, part 6 "[Turvalaitteet](#)"⁵¹ (Signalling systems). The provision is available from the Finlex Data Bank <http://www.finlex.fi>⁵².

3.3.3.2 Rolling Stock Monitoring Equipment

Hot box detectors have been placed on the railway network at approx. 50 km intervals. Some of the hot box detectors have been placed near the busiest junction stations. The distance can be greater on line sections on which the maximum speed is less than 160 km/h. The devices are installed on the track and to ensure that they work as intended, the axle-box cases must be placed so that their lower surface is within the range of the detector. A map of the location of the hot box detectors is presented in Appendix 17 (Monitoring of rolling stock).

The wheel force measuring stations are situated in the vicinity of both the largest junction stations and the border stations for the eastern transit traffic. The devices measure the static and dynamic load impact of the wheelset on the rail. Based on these measuring results, excess weight, uneven loading and certain defects in the wheel tread can be detected. The devices are installed in the track. More information can be found in Appendix 17 (Monitoring of rolling stock).

The camera systems for monitoring the condition of contact strips in pantographs on electric traction units have mainly been installed on road bridges overpassing the track. The monitoring points have been located near the junction stations so that the pantographs approaching the station can be checked either manually or automatically, based on the photos taken by the system.

⁵⁰ <http://www.finlex.fi/fi/viranomaiset/normi/499001/35169>

⁵¹ http://www2.liikennevirasto.fi/julkaisut/pdf3/2012_rato6_en_web.pdf

⁵² <http://www.finlex.fi/fi/viranomaiset/normi/499001/34920>

Equipping the rolling stock with radio frequency identifiers (RFID) makes it possible to promptly allocate the monitoring information to the right stock unit and its maintenance manager.

3.3.3.3 Traffic Control Systems

The line sections equipped with an automated traffic control system are indicated in Appendix 1 (Basic Information on Line Sections) and in Appendix 8 (Signalling Systems). The following automated traffic control systems are in use: centralised traffic control and radio control. On the CTC- and radio-controlled lines, all routes are equipped with the remote control of turnouts and routes. On secondary, loading and storage sidings of these line sections, however, local route setting may also be necessary. On radio-controlled lines, routes shall be set locally if it is necessary to operate on secondary, loading or storage sidings.

Permission to depart is given either verbally or as a flash message to trains equipped with ATC on radio-controlled line sections. The permission to depart is sent to the locomotive driver's GSM or GSM-R phone.

3.3.3.4 Communications Systems

Traffic control, railway undertakings and contractors must use the RAILI network as their primary communications channel. Its key element is a GSM-R radio network, which complies with the technical railway interoperability specifications of the European Union. The GSM-R radio network will cover most of the state-owned railway network. Some track sections will remain outside the RAILI network. Detailed quality information can be found in the map of the RAILI network design standards and Appendix 15 (GSM-R (RAILI) network). More information can be found on the Finnish Transport Agency's website at <http://www.liikennevirasto.fi>⁵³.

If the RAILI network cannot be used for technical reasons or due to a poor GSM-R radio network reception, the parties must use other available phone or mobile phone networks. The traffic control, and also train drivers, shunting managers and persons responsible for the track work must be informed of any faults preventing or hindering the use of RAILI network, and alternative contact information in accordance with the communications instructions.

In accordance with section 84 in the Railway Act, the RAILI Network may only be used for traffic safety communication. The Finnish Transport Agency makes sure that the railway traffic communication, the information generated by the safety equipment and all other information necessary for incident and accident investigations is recorded and stored so that it is protected against unlawful interference. The information must be destroyed as soon as it has served its purpose and is no longer required. The competent authority uses the recordings for accident and incident investigations.

⁵³ http://portal.liikennevirasto.fi/sivu/www/f/ammattiliikenteen_palvelut/rataverkolla_liikennointi/gsm_r_verkko

The Finnish Transport Safety Agency sets regulations on, for example, traffic operation, track work and communications. The valid regulations can be obtained at the Finlex Data Bank <http://www.finlex.fi>⁵⁴.

The Finnish Transport Agency provides working instructions that deal with traffic control, traffic operation, track work and communications, and complement the regulations. The valid [working instructions](#)⁵⁵ can be obtained at the Finnish Transport Agency's website. Contact information for traffic control can be obtained at the Finnish Transport Agency [Extranetsite](#)⁵⁶.

Information of abnormal events or situations will be provided via the Advance Information System (ETJ), maintained by the Finnish Transport Agency, and through notifications given by the traffic control. Drivers and persons responsible for the track work must have knowledge of the advance plans that are valid for the duration of the work/journey and in the working area/track sections of the journey. They must also have the contact information for the traffic control.

Companies operating in the railway network shall enter a RAILI agreement with the Finnish Transport Agency, before taking the RAILI network into use. More information about this can be found in paragraph 2.3.3 and on the Finnish Transport Agency's website <http://www.liikennevirasto.fi>⁵⁷.

3.3.3.5 Other Systems

Many of the larger stations have camera surveillance. The system allows traffic controllers to monitor the movement of trains and the Information Centre to observe the movement of passengers on platforms as well as the technical functioning of the information equipment. The Safety Centre is able to monitor passenger safety and control vandalism. Technical control room and property maintenance can use the system to check on the tidiness of platform areas and spot any need for technical maintenance work.

3.3.3.6 ATP Systems

Automatic train protection (ATP) is a system that controls the speed of a train.

Locomotives operating in the state-owned railway network must be fitted with an automatic train protection system (ATP) according to class B in the Finnish system (ATP-VR/RHK), or equipped with the European Train Control System in conjunction with legacy ATPs through a specific transmission module (ETCS + STM). Information about the availability and terms of delivery of ATP equipment is given by [Bombardier Transportation Finland Oy](#)⁵⁸. Information regarding the conjunction ETCS+STM is

⁵⁴ http://www.finlex.fi/fi/viranomaiset/normi/499001/?_offset=0&_max=49

⁵⁵ http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat_suunnittelijat/vaylanpidon_ohjeet

⁵⁶ http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat_suunnittelijat/konsultit/Extranet

⁵⁷ http://portal.liikennevirasto.fi/sivu/www/f/ammattiliikenteen_palvelut/rataverkolla_liikennointi/gsm_r_verkko

⁵⁸ <http://www.bombardier.com/>

provided by both Bombardier Transportation Finland Oy and [Ansaldo STS Finland Oy](#)⁵⁹.

ATP locomotive equipment must be used in train traffic or, if operating without ATP locomotive equipment, an exceptional permit as referred to in section 76 of the Railway Act ([304/2011](#))⁶⁰ is compulsory. The Finnish Transport Safety Agency may grant an exceptional permit provided that it does not endanger the safety of the rail system. In cases concerning the use of ATP locomotive equipment, a fixed-term exceptional permit may be granted if the case involves a need for exceptional and temporary train operation or if ATP locomotive equipment or spare parts are not available. An exceptional permit may not be granted for a train unit or locomotive which is used in passenger or commercial freight traffic, when it is not directly connected with infrastructure management. ATP locomotive equipment is not required in stock that is used for shunting only.

Museum stock can be operated on part of the railway network without automatic train safety equipment. The Finnish Transport Safety Agency's museum train traffic regulation includes a list of the line sections on which Automatic Train Control is obligatory ([RVI/295/411/2008](#))⁶¹.

Further information can be obtained from the Finnish Transport Safety Agency, but also from its provisions called "[Liikennöinti ilman JKV-laitetta](#)"⁶² (RVI/301/412/2008) and "[Liikennöinti ja ratatyö rautatiejärjestelmässä](#)"⁶³ (RVI/1092/412/2009).

3.4 Traffic Restrictions

3.4.1 Specialised Infrastructure

The Finnish Transport Agency may designate a train path or a part of it as specialised infrastructure, if there are sufficiently alternative routes for other traffic. Specialised infrastructure refers to a train path or a part of it on which priority is given to the type of traffic for which the infrastructure is specialised. So far the Finnish Transport Agency has not designated any line section in Finland as specialised infrastructure.

⁵⁹ <http://www.ansaldo-sts.com/en/about-us/ansaldo-around-world/our-companies/ansaldo-sts-finland>

⁶⁰ <http://www.finlex.fi/fi/laki/ajantasa/2011/20110304>

⁶¹ <http://www.finlex.fi/fi/viranomaiset/normi/499001/33637>

⁶² <http://www.finlex.fi/data/normit/33917-Maarays.pdf>

⁶³ <http://www.finlex.fi/fi/viranomaiset/normi/499001/35183>

3.4.2 Environmental Restrictions

When registering rolling stock, the Finnish Transport Safety Agency's regulations and instructions are applied. The regulations set out general and special requirements for rolling stock concerning noise, vibration, electromagnetic interferences, emissions, substances hazardous to the environment and the use of recycled construction materials. For more information, go to the Finnish Transport Safety Agency's website <http://www.trafi.fi>⁶⁴.

Vibration-related speed restrictions are imposed on parts of the railway line on seventeen line sections throughout Finland. The restrictions mainly apply to over 3,000 ton gross weight heavy trains. More information can be found in Appendix 9 (Vibration-related Speed Restrictions).

3.4.3 Dangerous Goods

3.4.3.1 Carriage by rail of dangerous goods

Safe transport and handling of goods classified as dangerous can only be achieved if all parties involved have a consistent understanding of the hazardous nature of the goods to be transported. Both national and international regulations have been issued in order to prevent damages and to alleviate the consequences of possible damages caused by the carriage of dangerous goods. In Finland two international regulations are applied, depending on the destination of the wagon (east or west).

No absolute restrictions have been imposed on the transport of dangerous goods if carried out according to the regulations. It is recommended that wagons loaded with dangerous goods should not be parked in densely populated or groundwater areas. The transport of dangerous goods on tracks with spike fastening or laid with less than 43 kg rails shall be avoided.

It is prescribed by Government decree that railway undertakings shall carry out a safety analysis for railway yards through which considerable quantities of dangerous goods are carried. The decree defines, for example, the following: The Finnish Transport Safety Agency defines those railway yards for which the safety analysis must be carried out. The Finnish Transport Agency may define the form of the safety analysis. The Finnish Transport Agency organises co-operation between railway companies in order to carry out the safety analysis. The safety analysis shall be submitted to the local rescue and environmental authorities for an opinion. The safety analysis shall be submitted to the Finnish Transport Agency, which delivers it further for approval. The safety plan is approved by the Finnish Transport Safety Agency.

⁶⁴ http://www.trafi.fi/rautatiet/saadokset/kansalliset_maaraykset/kumotut_maaraykset

3.4.3.2 Westbound and Domestic Traffic

Finland has signed the intergovernmental OTIF Convention (SopS 5/1985), which regulates international rail traffic.

Appendix B of the OTIF Convention lays down the provisions on the carriage by rail of dangerous goods (RID). As they stand, the RID regulations govern the international rail transportation of dangerous goods within the territories of member states that have acceded to the OTIF Convention. Rail transport of dangerous goods within Finland is subject to the national statutes which enforce the RID framework directive (2008/68/EC)⁶⁵ in Finland.

The Finnish internal regulations on frostproof structural material used for tank wagons, tank containers and plastic receptacles are more rigid than the RID regulations. In domestic traffic the required cold resistance level for these packages and tanks is -40 °C (RID: -20 °C). The decree of the Ministry of Transport and Communications also takes into account the requirements of the VOC directive (94/63/EC)⁶⁶ concerning the recovery of vapours from petrol in connection with rail transport.

3.4.3.3 Eastbound Traffic

The regulations on the transport of dangerous goods in railway transit traffic between Finland and Russia in Appendix No. 8 of the transport tariff of the Convention on the Railway Transit Traffic between Finland and the Soviet Union (Treaty Series of the Statute Book of Finland 1/1948) are applied in the transport of dangerous goods by rail between Finland and Russia as well as via Russia to the CSTO nations and from these to Finland. Transports in eastbound traffic shall take place with railway wagons registered in Russia or in another CSTO nation. This agreement is still applied, even though the agreement in question is no longer in force. More information concerning international railway agreements can be found from the Finnish Transport Safety Agency's website on <http://www.trafi.fi>⁶⁷.

An agreement between Finland and Russia on transport of dangerous goods by rail was concluded on 25 June 2013. The appendix of the new RID convention is based on the regulations in appendix II of the 2009 SMGS agreement.

3.4.4 Tunnel Restrictions

There are tunnel restrictions on the Helsinki–Turku and Orivesi–Jyväskylä line sections. The restrictions are indicated in Appendix 11.

Only freight trains and rolling stock required in track work are allowed to operate in tunnels on the Vuosaari line. It is forbidden to take passengers through the tunnels on

⁶⁵ <http://eur-lex.europa.eu/LexUriServ/LexUriServ.do?uri=OJ:L:2008:260:0013:01:FI:HTML>

⁶⁶ <http://eur-lex.europa.eu/LexUriServ/LexUriServ.do?uri=CELEX:31994L0063:EN:HTML>

⁶⁷ http://www.trafi.fi/rautatiet/saadokset/kansainvaliset_sopimukset

the Vuosaari line. Only electric freight traffic is allowed. Individual diesel locomotive transfers are permitted.

In the Vuosaari tunnel the locomotive and track work machinery must be equipped with an oxygen apparatus.

3.4.5 Bridge Restrictions

Bridge restrictions are described in Appendix 12.

3.4.6 Overweight Load Transport

Details concerning the axle loads and restrictions applicable to the carriage of overweight loads and wagons used in the eastern transit traffic can be found from the Appendix 16 "Rolling stock speed in the railway network".

3.5 Availability of the Infrastructure

The restrictions affecting traffic are presented in appendices 9, 10, 11, 12 and in the JETI system (the system for advance information on train traffic). Track work causing traffic restrictions is presented in Appendix 13.

The substations of the electric railway have a limited capacity for supplying power to the contact line. The power supply will shut down automatically in overload situations, which will cause a temporary power failure in the contact line.

3.6 Passenger Stations

The lengths of passenger platforms (shortest/longest) are indicated in Appendix 2 (Rail Traffic Operating Points). Platforms not maintained by the Finnish Transport Agency are indicated in brackets.

3.7 Freight Terminals

Loading possibilities are indicated in Appendix 2 (Rail Traffic Operating Points). K means "yes" and Y "private". For loading platforms, the register lists their available length.

Private siding connections at traffic operating points are indicated by the marking "Private sidings" in Appendix 2 (Rail Traffic Operating Points).

3.8 Service Facilities

3.8.1 Train Formation Yards

Train formation yards are railway yards in which the layout and size of the track system make it possible to form trains. The train formation yards are indicated by the marking “K” in column “Shunting” in Appendix 2 (Rail Traffic Operating Points).

All train formation yard tracks have not been electrified. If necessary, the field of activity Infrastructure Management at the Finnish Transport Agency provides more information on the electrified tracks.

The use of train formation yards may become chargeable. All possible changes are updated on the Finnish Transport Agency's website <http://www.liikennevirasto.fi>⁶⁸.

3.8.2 Storage Sidings

Storage sidings are yard tracks primarily intended for the parking of wagons and coaches waiting for a transport task. Storage sidings can also be used for other purposes required by traffic operating. Only railway operators and contractors are allowed to let wagons stand on the storage sidings. The Finnish Transport Agency determines which tracks are used as storage sidings.

3.8.3 Maintenance and Service Facilities

The 400 and 1,500 V power supply facilities for rolling stock are indicated in Appendix 2 (Rail Traffic Operating Points). Also for the 400 V power supply, the maximum current available is indicated in amperes. The use of maintenance and service facilities requires an agreement with their owner.

3.8.4 Refuelling Facilities

The Finnish Transport Agency does not own refuelling equipment or provide refuelling services. The Appendix 2 (Rail Traffic Operating Points) shows the refuelling facilities on traffic operating points. The use of refuelling facilities requires an agreement with their owner.

3.8.5 Technical Equipment

The use of other technical equipment (e.g. scales, cranes, etc.) must be agreed with their respective owners. The Finnish Transport Agency does not provide rail operators with access to this equipment. Appendix 2 (Rail Traffic Operating Points) shows the cranes located at traffic operating points.

⁶⁸ http://portal.liikennevirasto.fi/sivu/www/e/professionals/network_statement

3.9 Infrastructure Development

The development plans for the railway network are presented in the Finnish Transport Agency's Action and Financial Plan for the years 2013–2016, published in February 2012. During the Action and Financial Plan period the focus will be on replacing ballast and enhancing traffic control safety and flexibility in railway yards by introducing new automation technology. Ballast replacements will be made on the line sections Lielähti–Kokemäki, Pieksämäki–Kuopio and Huopalahti–Vantaankoski. Old remote control systems will be replaced on the line section Seinäjoki–Ylivieska. In addition, work will be commenced to replace the remote control system on the line section Parikkala–Joensuu and the signal boxes on the section Riihimäki–Seinäjoki and in Lahdenperä. Railway network development projects underway include the improvement of the level of service on the line section Seinäjoki–Oulu, construction of the Ring Rail Line and Kokkola–Ylivieska double track.

The Government's transport policy report includes these railway network development projects:

- Repairs of areas with ground frost heaving and soft soils on main railway lines
- Riihimäki triangle track
- Improvement of the rail connection Ylivieska–Iisalmi–Kontiomäki (electrification)
- Capacity enhancement on the line section Helsinki–Riihimäki
- Raw timber terminals
- Renewal of the railway traffic control systems.
- Functional improvement of Helsinki railway yard

4 Capacity Allocation

4.1 Introduction

The legal framework of capacity allocation is described in the [Directive 2012/34/EU](#)⁶⁹ of the European Parliament and of the Council on the allocation of railway infrastructure capacity and the levying of charges for the use of railway infrastructure and safety certification (hereinafter referred to as the "Capacity and Infrastructure Charge Directive"), but also Railway Act ([304/2011](#))⁷⁰ and in the Government Decree on the Timetable Period in Railway Traffic and Applying for Infrastructure Capacity ([413/2011](#))⁷¹.

4.2 Description of Process

Capacity for operating regular train services on the state-owned railway network shall be requested from the Finnish Transport Agency for each timetable period within the time defined. Capacity for regular train services can also be requested during the timetable period. The schedule for train path requests and for allocation is shown in a diagrammatic form in Figure 6. It is also possible to make *ad hoc* requests for capacity for other than regular traffic.




Figure 6. Diagrammatic presentation of the schedule for train path requests and for allocation process.

Requesting rail capacity

The principles of capacity requests are described in the Railway Act ([304/2011](#))⁷² and in the Government Decree on the Timetable Period in Railway Traffic and Applying for Infrastructure Capacity ([413/2011](#))⁷³. In order to specify the Act and Decree, the Finnish Transport Agency has drawn up an instruction for requesting rail capacity.

⁶⁹ <http://eur-lex.europa.eu/LexUriServ/LexUriServ.do?uri=CELEX:32001L0014:en:HTML>

⁷⁰ <http://www.finlex.fi/fi/laki/ajantasa/2011/20110304>

⁷¹ <http://www.finlex.fi/fi/laki/alkup/2011/20110413>

⁷² <http://www.finlex.fi/fi/laki/ajantasa/2011/20110304>

⁷³ <http://www.finlex.fi/fi/laki/alkup/2011/20110413>

The instruction is available at the Finnish Transport Agency's Field of Activity Traffic and Information. The same information is available also on the Finnish Transport Agency's website at

<http://www.liikennevirasto.fi>⁷⁴.

Requests for rail capacity for regular services and for ad hoc capacity as well as for alterations to the regular services are to be submitted in the **LIIKE**⁷⁵ information system. Apart from the LIIKE system, data on rail capacity (=trains) can be generated via the interface specified by the Finnish Transport Agency. The Finnish Transport Agency will provide further information on the requirements for and access to the interface. For example, the Finland version of the Viriato timetable planning software meets the relevant interface requirements. It is possible to link timetables produced using the software to a rail capacity application generated in the LIIKE information system.

In order to ensure that the timetabling of trains in connection with rail capacity applications is harmonised, all rail capacity applicants must use the background information for timetable planning supplied and maintained by the Finnish Transport Agency. Up-to-date data is available on the Finnish Transport Agency's website <http://www.liikennevirasto.fi>⁷⁶.

Requesting rail capacity for shunting operations

Rail capacity for shunting operations between traffic operating points and between parts of divided traffic operating points is requested in the LIIKE system. Shunting operations performed at the freight yards of traffic operating points are separately agreed upon in the railway yard agreement. The main order of priority for the traffic at the traffic operating point is the following:

1. Train traffic (passenger, freight, including border traffic and track work units using the line)
2. Traffic between different parts of the traffic operating point due to shunting operations
3. Wagon sorting operations (formation/splitting-up of trains)
4. Moving of rolling stock to holding siding.

⁷⁴ http://portal.liikennevirasto.fi/sivu/www/f/ammattiliikenteen_palvelut/rataverkolla_liikennointi/ratakapasiteetin_hallinta/liike

⁷⁵ http://portal.liikennevirasto.fi/sivu/www/f/ammattiliikenteen_palvelut/rataverkolla_liikennointi/ratakapasiteetin_hallinta/liike

⁷⁶ http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat_suunnittelijat/konsulteille/Extranet

4.3 Schedule for Train Path Requests and Allocation Capacity Requests

4.3.1 Schedule for Working Timetable

The timetable period in railway traffic starts annually at the second weekend of December, at 00.00 hrs on the night between Saturday and Sunday, and ends at the corresponding time the following year. The timetable period 2015 will start on 14.12.2014 and end on 12.12.2015. Correspondingly, the timetable period 2016 will start on 13.12.2015 and end on 10.12.2016. Applicants for capacity shall request capacity no earlier than 12 and no later than 8 months ahead of the timetable period. One request may include all the changes in traffic to be made during the timetable period.

Decisions on the allocation of capacity for regular services may be changed for the rest of the timetable period during the timetable period concerned at specified dates, provided that these changes do not affect the capacity allocated to other railway undertakings or to international traffic within the European Economic Area. The changes may take effect at 00.00 hrs on the night between Saturday and Sunday in the beginning of the timetable period and at 00.00 hrs on the night between Sunday and Monday at the weekend following the end of the school year. In addition to the above dates, the Finnish Transport Agency may for special reasons decide on other dates on which changes can take place. The preliminary dates on which changes can take place during the timetable period 2015 are the following:

14.12.2014
29.3.2015
15.6.2015
10.8.2015
25.10.2015

The Finnish Transport Agency shall inform all railway undertakings of possible new dates on which the capacity for regular services may be changed. The decision on the dates for applying changes will also be published in the Finnish Transport Agency's website <http://www.liikennevirasto.fi>⁷⁷.




Figure 7. *Dates on which the capacity for regular services may be changed during the timetable period 2015.*

⁷⁷ http://portal.liikennevirasto.fi/sivu/www/f/ammatti/likenteen_palvelut/rataverkolla_liikennointi/liikennesuunnittelu/muutokset_saannottiiseen

Requests for changing capacity allocated for regular services must be submitted no later than four weeks before the date on which the change shall take effect. When the date on which the changes may take effect, is Sunday or a public holiday, the request shall be made on the first weekday. The application for the first change of the timetable period must be submitted already six weeks in advance, when the track order is determined for the first time.

4.3.2 Requesting Rail Capacity for Temporary Traffic

Applicants for rail capacity may request capacity from the Finnish Transport Agency regardless of the prescribed period if they urgently need capacity for one or more provisional train paths. Ad hoc capacity requests for the time period between the change dates can be made after the rail capacity application period has ended. Rail capacity for museum traffic can be applied no earlier than four months before the scheduled departure. It is however recommended that applications for ad hoc capacity are submitted no earlier than two months before the traffic operations; otherwise the rail capacity may have to be withdrawn due to track work specifications. An applicant, who despite of this requests rail capacity earlier than two months before the traffic operations, is under the obligation to make sure that the requested rail capacity does not conflict with the specified track work reservation. The Finnish Transport Agency will announce its decision concerning the capacity request within five working days of receiving the application. The more detailed application instructions can be found on the Finnish Transport Agency's website <http://www.liikennevirasto.fi>⁷⁸.

4.4 Allocation Process

4.4.1 Coordination Process

Based on the applications, the Finnish Transport Agency's Traffic Services Department draws up the rail capacity allocation proposal (called "draft working timetable" in the Railway Act) for the next timetable period no later than four months after the deadline for the submission of requests for capacity. It has, however, been agreed by European railway infrastructure managers that no more than 2.5 months shall be used for the coordination of requests. The rail capacity allocation proposal contains information on the rail capacity that the Finnish Transport Agency proposes to allocate to an applicant only to such an extent and with such restrictions as is necessary for implementing traffic control for the use of this capacity.

The rail capacity allocation proposal is primarily based on the assumption that the requested rail capacity will be allocated, provided that the different train paths enable railway traffic to be operated in accordance with the technical and safety requirements. In order to improve the use of rail capacity, the Finnish Transport Agency may, however, offer applicant's capacity that does not essentially differ from the capacity they have requested. The Finnish Transport Agency may also decide not

⁷⁸ http://porta.liikennevirasto.fi/sivu/www/f/ammattiliikenteen_palvelut/rataverkolla_liikennointi/ratakapasteetin_hallinta/liike

to allocate capacity, provided that reserve capacity is needed for the timetable period as a result of the priority order applied to railway traffic.

The Finnish Transport Agency sends the rail capacity allocation proposal to applicants for information within the prescribed period of time and gives them the opportunity to comment. Comments shall be presented within 30 days after receipt of the capacity allocation proposal, i.e. as soon as the rail capacity allocation proposal has been published in the LIIKE system. Customers purchasing freight transport services and associations representing purchasers of rail transport services also have the right to present comments on the capacity allocation proposal within 30 days, counted from the date on which the Finnish Transport Agency publishes an announcement on its website that the capacity allocation proposal has been prepared.

Coordination for the timetable period

If several applicants apply for the same rail capacity or the requested rail capacity affects the capacity requested by another applicant, the Finnish Transport Agency will attempt to arbitrate between the applicants' requests. Applicants must be prepared to participate in settlement negotiations. The aim is to organise the negotiations by the beginning of June, i.e. approximately two months after the application deadline for the timetable period. Conflicting requests are discussed in the negotiations, with the goal to reach a solution satisfactory to all parties.

If the coordination of the rail capacity applications has failed to result in a settlement among applicants, the Finnish Transport Agency will determine the order of priority in each individual case on the grounds laid down in the Railway Act. The Finnish Transport Agency shall decide on an individual priority order no later than ten days after final settlement.

The Finnish Transport Agency will send the rail capacity allocation proposal to the applicants within the prescribed period of time. The capacity allocation proposal will be published on the Finnish Transport Agency's website.

The Finnish Transport Agency sends the capacity allocation proposal to applicants for information within the prescribed period of time and gives them the opportunity to comment. Comments shall be presented within 30 days after receipt of the capacity allocation proposal, i.e. as soon as the capacity allocation proposal has been published in the LIIKE system. Customers purchasing freight transport services and associations representing purchasers of rail transport services also have the right to present comments on the capacity allocation proposal within 30 days, counted from the date on which the Finnish Transport Agency publishes an announcement on its website (<http://www.liikennevirasto.fi>)⁷⁹ that the capacity allocation proposal has been prepared. The consultation period begins as soon as the Finnish Transport Agency has announced the completion of the capacity allocation proposal on its website. In addition to the allocation proposal, the website includes information on when and where the comments must be sent.

⁷⁹ http://portal.liikennevirasto.fi/sivu/www/ff/ammatillikenteen_palvelut/rataverkolla_liikennointi/ratakapasiteetin_hallinta/liike

Confirmation of the rail capacity allocation proposal

Based on the rail capacity allocation proposal and the comments presented by the parties involved, the Finnish Transport Agency shall decide on the allocation of rail capacity on a fair and non-discriminatory basis. In deciding, the Finnish Transport Agency shall pay particular attention to the needs of passenger and freight traffic and infrastructure management, as well as to efficient use of the railway network. The priority order determined for specialised and congested infrastructure shall also be taken into account, unless otherwise provided in this chapter.

Allocation of rail capacity on the dates when the capacity allocated for regular services may be changed

On the dates when the capacity allocated for regular services may be changed, requests for capacity are processed in the same way as during the timetable period request phase. If several applicants request the same rail capacity, or if the requested rail capacity affects the capacity requested by another applicant, the Finnish Transport Agency no longer coordinates the requests between the applicants. Instead the applicants must try to reach a compromise solution themselves. The change date applications are processed in the LIIKE system.

Allocating ad hoc rail capacity

The Finnish Transport Agency allocates the requested ad hoc capacity if there is sufficient capacity for the use specified in the request. Unless otherwise provided in the Railway Act, the ad hoc capacity is allocated on a first-come first-served basis.

During office hours, the unit for Railway Network Usage processes the requests for ad hoc capacity. The Rail Traffic Management Centre processes the requests outside office hours.

Rail capacity plans regarding tracks

The use of tracks at traffic operating points is planned simultaneously with the applications for rail capacity. Applications for the track plans of regular services are submitted in the LIIKE system in connection with the applications for the dates on which the capacity allocated for regular rail services may be changed. Applications for the tracks used by regular services at exceptional dates are also registered at this point.

When submitting an application for ad hoc rail capacity, the track data must be included. Default track data has been entered in the LIIKE system, but if a rail capacity applicant wishes to use a specific track at a traffic operating point, he must enter this information himself in the application for rail capacity. Before the applicant submits his application, he must check in the track usage diagram that the train does not conflict with the timetables granted earlier at different traffic operating points.

Cancelling train paths and submitting new applications

If the applicant no longer requires the reserved capacity, the train path must be cancelled as soon as possible. Furthermore, train paths must be cancelled and new

applications submitted, if any of the following changes occur in the granted timetable:

1. changes in the timetable information or route
A new application for rail capacity shall also be submitted if the train is expected to depart more than 120 minutes later than scheduled from its original place of departure or more than 30 minutes before its official time of departure. Otherwise the train will not be registered in the JETI system. There is no need to apply for new rail capacity if a train is delayed or runs ahead of time during the journey.
2. changes in the stopping behaviour or in the type of stop (commercial vs. non-commercial stop)
3. changes in speed profile, braked weight speed or brake type (which affect the driver's timetable)

If a train is expected to depart significantly later or earlier than the official time of departure, it is recommended that a new application for rail capacity shall be submitted. Otherwise uninterrupted train operations cannot be guaranteed.

4.4.2 Dispute Resolution

Railway undertakings may appeal against a capacity allocation decision by the Finnish Transport Agency by filing a claim for rectification with the Finnish Transport Safety Agency's Regulatory Body. For further information, see 1.4.3.

4.4.3 Congested Infrastructure

If the coordination of capacity requests does not lead to a satisfactory result, the Finnish Transport Agency will declare that section of infrastructure to be congested. This must also be done for infrastructure which can be predicted to suffer from insufficient capacity in the near future. When infrastructure has been declared to be congested, the Finnish Transport Agency will carry out a capacity analysis which includes consultation of the infrastructure users. Traffic management, timetable structures, speed alterations and potential infrastructure improvements will be taken into account when making the analysis. The Finnish Transport Agency will compile a capacity enhancement plan within six months of the completion of the capacity analysis.

Priority order in Finland

The Finnish Transport Agency declares an element of infrastructure or a part of it to be congested infrastructure if the coordination of several requests for the same infrastructure has not led to a satisfactory result. The Finnish Transport Agency may also designate an element of infrastructure as congested if it is evident that it will become congested during the timetable period.

If there are several applications for the same infrastructure, the priority order is as presented in Table 1. Application of this priority order is based on the assumption that each train can be defined during its whole journey by one of the terms listed in

the table. The term by which the train is defined may change during the journey of the train.

If there is a need to prioritize trains within a particular priority group in the table, priority will be given on the basis of the length of the journey and the number of operating days. In this way higher priority is given to a longer and more regular transport need.

Table 1. Priority order on congested infrastructure.

| Priority | Traffic |
|----------|--|
| 1. | Synergic passenger traffic entity ⁸⁰ |
| 2.a | Express train traffic ⁸¹ |
| 2.b | Transport for the processing industry ⁸² |
| 3.a | Local and other passenger traffic |
| 3.b | Other regular freight traffic |
| 4. | Freight traffic not requiring strict transport times |
| 5. | Other traffic ⁸³ |

Derogation from the priority order laid down in the Network Statement

The Finnish Transport Agency may by a separate decision make derogation from the general priority order laid down in the Railway Act and the Network Statement in favour of an applicant operating international traffic or such traffic as otherwise maintains or improves the functioning of the rail transport system or public transport. The same applies to cases where the rejection of the application would cause unreasonable damage to applicants or to the business activities of their customers.

4.4.4 Impact of the Framework Agreements

The Finnish Transport Agency has no valid framework agreements with railway undertakings. Framework agreements help to define the rights and obligations of the applicant and the FTA for a period of time exceeding that of one timetable period.

⁸⁰ The term "synergic passenger traffic entity" refers in passenger traffic to the whole of trains which form a transport system producing clear added value for customers. A system of this kind is, for example, traffic operated according to the basic interval timetable.

⁸¹ The term "express train traffic" refers to traffic which in some respect does not belong within the scope of the synergy-producing traffic system. International passenger traffic may belong in this category.

⁸² The term "transport for the processing industry" mainly refers to transport whose immediate place of destination or origin is a port or a private siding. This transport is essentially connected with total logistics management. This group includes, in particular, combined transport, transport for the wood-processing industry and transport to ports.

⁸³ Other traffic refers to e.g. traffic in connection with track work, museum traffic or shunting operations on the line sections.

Framework agreements must not, however, hinder other applicants from using the infrastructure in question and do not bind the FTA to grant the capacity defined in the agreement to the railway undertaking in question.

4.5 Allocation of Capacity for Maintenance, Renewal and Enhancements

The railway network may also be used for transferring track machines from depots to worksites, between worksites, and for maintenance purposes. Certain tracks are mainly used for infrastructure management purposes. Under the Railway Act, a safety certificate granted by the Finnish Transport Safety Agency is required for traffic operation, if it is a train movement or shunting movement, outside the area reserved for infrastructure management. The safety certificate is granted upon application for a maximum of five years at a time. The requirements for obtaining a safety certificate are that the traffic operator engaged in infrastructure management has sufficient liability insurance and an adequate risk management system, its stock has been approved by the Finnish Transport Safety Agency and that the persons conducting the traffic operations are competent to do so.

Requests for the rail capacity required to operate traffic must be submitted in the LIIKE system. The [TURO publication](#)⁸⁴ contains detailed instructions on the infrastructure management machinery used on the track as well as on the persons and undertakings charged with traffic safety duties.

Track works which will probably be carried out during the timetable period 2015 and which are likely to have an impact on train traffic are indicated in Appendix 13. The working programme, timing of tasks, and track possessions required for the work will change as the funding and plans become more focused and thus the Finnish Transport Agency is not bound by Appendix 13. Once the Network Statement is published, the Finnish Transport Agency will maintain up-to-date information on the working programme for the upcoming timetable period on its website <http://www.liikennevirasto.fi>⁸⁵, and regularly inform the rail capacity applicants about the programme.

The Finnish Transport Agency will decide separately on all track work and track possessions required for their completion. The decision will be made prior to the upcoming timetable period that is in December 2014 for the timetable period 2015.

Any required track possessions or changes to an earlier decision, arising after the decision has been made, can be discussed separately, if necessary. The basic rule is that track possessions requiring traffic arrangements are no longer arranged at this stage, but instead the work requested after the decision will be carried out according to (or in between) the traffic.

⁸⁴ http://www2.liikennevirasto.fi/julkaisut/pdf3/lo_2012-01_turo_web.pdf

⁸⁵ http://portal.liikennevirasto.fi/sivu/www/f/ammattiliikenteen_palvelut/rataverkolla_liikennointi/liikennesuunnittelu/ratatyot

In addition to the aforementioned, the person or group applying for track possession must contact the Finnish Transport Agency's traffic planner separately for each request and agree on track possession and its details in accordance with the Finnish Transport Agency's track possession decision no later than two months before the work is scheduled to start.

The party performing the work must have granted rail capacity, permission for track work, and if necessary, a voltage cut-off prior to starting the work for the agreed track possessions.

4.6 Non-Usage Rules

The Finnish Transport Agency has the right to cancel the capacity allocated to an applicant, or a part of it, if the applicant has used this capacity over a period of not less than 30 days less than required by the threshold quota specified below. In Finland, the threshold quota for the minimum use of capacity is 80 %, except on the line sections Helsinki–Kerava, Helsinki–Vantaankoski and Helsinki–Leppävaara, where the threshold quota for the minimum use is 95 %.

The Finnish Transport Agency may not, however, cancel the capacity if the failure to use it is due to non-economic reasons beyond the applicant or the railway operator's control. The Finnish Transport Agency always cancels the capacity for such a period during which the railway undertaking does not have a safety certificate for operating rail services.

4.7 Exceptional Transport and Dangerous Goods

For information on the transport of dangerous goods, see point 3.4.3, Dangerous Goods. Regulations concerning railway traffic and rolling stock are available on the Internet pages of the Finlex Data Bank at <http://www.finlex.fi>⁸⁶ and other instructions on the Finnish Transport Safety Agency's website at <http://www.trafi.fi>⁸⁷.

All special permits are granted by the Finnish Transport Agency.

⁸⁶ <http://www.finlex.fi/fi/viranomaiset/normi/499001/>

⁸⁷ http://www.trafi.fi/rautatiet/saadokset/kansalliset_maaraykset

4.8 Special Measures to be taken in the Event of Disturbance

4.8.1 Principles

The Finnish Transport Agency has the right to cancel the capacity completely or partially on a train path provisionally out of service due to a technical failure in the railway network, an accident or other incident.

In such case, the Finnish Transport Agency offers the operator alternative train paths, as far as possible. The Finnish Transport Agency is, however, not obliged to compensate for damage that may be caused to the operator, unless otherwise is agreed upon with the operator in conformity with the Railway Act.

Compensations due to disruptions are dealt with in chapter 6.4 (Performance Scheme).

4.8.2 Operational Regulation

The Finnish Transport Agency determines the rules on the management of disturbances between railway undertakings. Railway undertakings have the right to present their own proposals for instructions how to handle disturbances connected with their own trains.

The Rail Traffic Management Centre of the Finnish Transport Agency resolves instances of disruption and provides guidelines on the correct action to take in such situations. Further information can be found in the Finnish Transport Agency's publication Rail Traffic Management Manual on the Finnish Transport Agency's website <http://www.liikennevirasto.fi>⁸⁸.

In its guidelines on railway accident preparedness (OVRO), the Finnish Transport Agency specifies the measures to be taken in case of an accident and how to prepare for accidents in advance. The guidelines can be found on the Finnish Transport Agency's website <http://www.liikennevirasto.fi>⁸⁹.

4.8.3 Foreseen Problems

In cases of disruption the guidelines issued by the Finnish Transport Agency's Traffic Management Centre shall apply.

4.8.4 Unforeseen Problems

The Finnish Transport Agency, railway undertakings and railway maintenance undertakings shall be prepared for railway accidents in their fields of activity and

⁸⁸ http://www2.liikennevirasto.fi/julkaisut/pdf3/ohje_2011_rautatietliikenteenohjauksen_kasikirja_web.pdf

⁸⁹ http://www2.liikennevirasto.fi/julkaisut/pdf3/lo_2011-16_ohje_varautumisesta_web.pdf

follow the Finnish Transport Agency's guidelines (OVRO) on how to prepare for railway accidents.

The principle is that railway undertakings and railway track contractors shall be prepared to clear their own vehicles and the transported freight off the track, as well as remedy the damage caused to the environment within a reasonable time after the accident. Each undertaking shall draw up an emergency preparedness plan, which the Finnish Transport Agency shall approve. The preparedness measures included in the plan shall be taken before traffic operating is started. The undertakings themselves bear the costs caused by the creation and maintenance of the emergency preparedness system. Liability in cases of accident is determined in line with the Act on liability in rail traffic and the Tort Liability Act.

The Finnish Transport Agency is prepared to restore the track quickly to operable condition and within a reasonable time to the condition it had before the accident. The Finnish Transport Agency agrees thereupon when making the railway network maintenance agreements.

If any safety deficiencies affecting traffic are detected in the railway network, the Finnish Transport Agency may have to reduce the applicable axle load or speed limit.

The Ministry of Transport and Communications provides guidelines for and supervises the preparedness of the different operators in the railway sector for accidents and exceptional circumstances.

5 Services

5.1 Introduction

The legal framework of capacity allocation is described in the Railway Act (304/2011)⁹⁰.

The Council of State is currently drafting its decree on the services offered to the rail operators. Services concerning the usability of the railway network are described in Appendix 2 (Rail Traffic Operating Points) of the Network Statement. These services may be supplied by the Finnish Transport Agency or other parties.

5.2 Services Offered by the Finnish Transport Agency

Finnish Transport Agency offers rail operators on the state-owned railway network the right against payment to utilise the train paths in accordance with the capacity granted to it by the Finnish Transport Agency, marshalling yards, storage sidings, loading tracks and other tracks and passenger platforms. The Finnish Transport Agency also offers train traffic control, passenger information and public address systems at the railway stations specified in the Network Statement (Appendix 14).

Traffic control in connection with shunting is a chargeable service. It is not included in the infrastructure charge.

Use of capacity includes the right of the rail operator to use of the Finnish Transport Agency's electricity supply network for traffic on the electrified line sections specified in the Network Statement. The Finnish Transport Agency does not, however, provide the electricity but the rail operator shall conclude an agreement with a service provider. The Finnish Transport Agency also does not provide refuelling facilities.

The Finnish Transport Agency can offer services on a commercial basis for the use of rail operators. The additional services could comprise, for example, the use of buildings and land areas owned by the Finnish Transport Agency. Moreover, additional charges are levied for maintenance services provided at Ilmala.

The use of services provided by the Finnish Transport Agency is agreed upon between the parties in the access contract or in a separate lease agreement.

⁹⁰ <http://www.finlex.fi/fi/laki/ajantasa/2011/20110304>

5.3 Services Offered by Others

Railway undertakings are obliged to supply certain services and track access to services facilities for the use of rail operators if only one undertaking provides these services and it is not possible to otherwise arrange them. The availability of services shall be negotiated and an agreement shall be concluded with the service provider. The service provider has the right to charge a payment for its services. The payment shall be equitable for all railway undertakings and reasonable with respect to the costs incurred from providing the service.

Services supplied by others may include, for example:

- use of electrical supply equipment
- use of refuelling equipment
- use of passenger stations
- use of freight terminals
- use of train formation yards
- use of train formation equipment
- use of depot sidings
- premises and equipment needed for the servicing and maintenance of rolling stock
- use of other technical devices (e.g. sand distributors, water and electrical connections for rolling stock, radiation measurement devices, tank wagon filling gauges, wagon scales, and brake testing equipment), and
- training services for those involved in traffic safety tasks

6 Charges

6.1 Charging Principles and Services Included in the Infrastructure Charge

The legal framework of the basic infrastructure charge is described in the Railway Act (304/2011)⁹¹, Railway Infrastructure Tax (605/2003)⁹² and the Ministry of Transport and Communications Decree on the basic infrastructure charge (1084/2009)⁹³.

The basic infrastructure charge covers the minimum access package (the minimum access package is described under 5.2.), including track access to service facilities on the state-owned railway network.

6.2 Charging System

There will be changes in the charging system during the timetable period 2015. These are based on the statutes amended due to the **First Railway Package**⁹⁴. The basic principle remains that the Finnish Transport Agency shall collect a basic infrastructure charge from railway operators on a fair and non-discriminatory basis for the minimum access package and track access to service facilities, calculated on the actual level of use. The basic infrastructure charge shall always be based on the costs directly caused by the operation of railway traffic.

The infrastructure tax consists of a charge for external costs and a supplementary charge in accordance with the Capacity and Infrastructure Charge Directive. In the charge for external costs, the environmental effects caused by the operation of railway traffic can be taken into account. There may be changes in the levying of infrastructure tax after the Network Statement has been published. Information about this change will be updated on the Finnish Transport Agency's website <http://www.liikennevirasto.fi>⁹⁵.

The supplementary charge can be collected for covering the full amount of the costs caused by the use of the infrastructure. Additionally, investment tax will be levied until 31 August 2021 in order to partly cover the investments made on the line section Kerava–Lahti.

⁹¹ <http://www.finlex.fi/fi/laki/ajantasa/2011/20110304>

⁹² <http://www.finlex.fi/fi/laki/ajantasa/2003/20030605>

⁹³ <http://www.finlex.fi/fi/laki/alkup/2009/20091084>

⁹⁴ <http://eur-lex.europa.eu/LexUriServ/LexUriServ.do?uri=OJ:L:2012:343:0032:0077:EN:PDF>

⁹⁵ http://portal.liikennevirasto.fi/sivu/www/e/professionals/network_statement

6.3 Tariffs

The infrastructure charge consists of the charges mentioned in Table 2.

Table 2. *Infrastructure charge*

| | |
|---|--|
| Basic charge | Freight traffic 0,1350 cent/ gross tonne-kilometre Passenger traffic 0,1308 cent/ gross tonne-kilometre |
| Infrastructure tax | Freight traffic - electric 0.05 cent/ gross tonne-kilometre - diesel 0.1 cent/ gross tonne-kilometre Passenger traffic 0.01 cent/ gross tonne-kilometre |
| Investment tax (for line section Kerava-Lahti) | Freight traffic 0.5 cent/ gross tonne-kilometre Passenger traffic 0.5 cent/ gross tonne-kilometre |

6.4 Performance Scheme

In order to promote the effective use of the railway network and improve the timeliness of rail services and to minimise operational disruptions to the railway network caused by railway traffic and track maintenance, rail operators and the Finnish Transport Agency are encouraged to limit disruptions arising from their activities and increase the effective use of the railway network by means of performance incentive schemes.

A rail operator shall compensate the Finnish Transport Agency if the operation of the rail operator essentially differs from the rail capacity allocated to it for a reason due to the operator, and such a deviation impedes the functioning of the rail system. The Finnish Transport Agency shall compensate a rail operator if, for reasons due to the Finnish Transport Agency, the availability of the railway network essentially differs from the rail capacity allocated to the operator, and such a deviation impedes the functioning of the rail system.

The performance system only applies to train traffic, not to traffic in relation to shunting operations.

6.5 Changes to Charges

Infrastructure charge system is about to change. The principles of the valid infrastructure charge system and the amount of infrastructure charge are published on the Finnish Transport Agency website.

6.6 Billing Arrangements

The Finnish Transport Agency invoices the infrastructure charge each calendar month based on the realised performances of the previous month.

When this Network Statement is published the infrastructure charge is levied as follows: For invoicing, railway operators shall provide the Finnish Transport Agency contact person with information each month on the rail services operated by them. The reports shall be sent to the address [kirjaamo\(at\)fta.fi](mailto:kirjaamo@fta.fi) and for the attention of [leena.rouhiainen\(at\)fta.fi](mailto:leena.rouhiainen@fta.fi).

The Finnish Transport Agency aims at changing the practice, so that in the future the infrastructure charge is levied based on information obtained from the Finnish Transport Agency's RataDW system. The rail operators will be given written notice about this reform. In addition, there will be information about the new practice on the Finnish Transport Agency's website <http://www.liikennevirasto.fi>⁹⁶.

The Finnish Transport Agency does not require any guarantee for the payment of infrastructure charges. The infrastructure charge and other charges connected with it are, however, subject to distraint without sentence or decision.

⁹⁶ http://portal.liikennevirasto.fi/sivu/www/e/professionals/network_statement

Basic Information on Railway Sections

Markings:

| | |
|-----|---------------------------------------|
| On | "yes" |
| — | "no" |
| AC2 | electrification voltage 25 kV / 50 Hz |
| ATP | Automatic train protection |

Chart columns:

Traffic operating points (Node of the network) indicates all traffic operating points where the route of the train can be changed.

Length of line is the distance between traffic operating points (Nodes of the network).

Max gradient is the maximum gradient measured in a distance of 1,200 m.

Electrification system indicates that the section of line is electrified.

Section blocking or radio-controlled section indicates that on the section of line there is an automatic safety device system in use in order to protect the railway traffic.

ATP indicates that the section of line is equipped with pan-European safety device system and GSM-R radio network.

ERTMS indicates that the section of line is equipped with pan-European safety device system and GSM-R radio network.

ATP coding for tilting trains indicates the sections on which ATP allows higher speeds for tilting trains.

Radio system indicates that the digital (GSM-R) communication equipment is in use between the driver and traffic control in mention traffic operating points.

Finnish Railway Network Statement 2015

| Liikennepaikka (verkon solmupiste) | Liikennepaikka (verkon solmupiste) | Radan pituus | Määrävä kaltevuus | Sähköistys-järjestelmä | Suojustettu tai radio-ohjattu osuus | Junan kulunvalvonta-järjestelmä | ERTMS | Kallistuvakoristen junien JKV-koodaus | Radio-järjestelmä |
|---|---|----------------|-------------------|--------------------------|--|---------------------------------|-------|---------------------------------------|-------------------|
| Trafikplats (bannätets knutpunkt) | Trafikplats (bannätets knutpunkt) | Banans längd | Största lutningen | Elektrifierings-systemet | Linje-blockerad eller radiostyrd sträcka | Automatisk tågkontrol | | ATC-kodning av lutande tåg | Radio system |
| Traffic operating point (Node of the network) | Traffic operating point (Node of the network) | Length of line | Max gradient | Electrification system | Section blocking or radio controlled section | ATP | | ATP-coding for tilting trains | |
| Helsinki asema | Havukoski | 18 | 10,0 | AC2 | On | ATP | — | On | GSM-R |
| Havukoski | Kerava asema | 11 | 7,0 | AC2 | On | ATP | — | On | GSM-R |
| Kerava asema | Hyvinkää | 29 | 7,5 | AC2 | On | ATP | — | On | GSM-R |
| Hyvinkää | Riihimäki asema | 12 | 7,5 | AC2 | On | ATP | — | On | GSM-R |
| Kerava asema | Vuosaari | 19 | 10,0 | AC2 | On | ATP | — | — | GSM-R |
| Kerava asema | Sköldvik | 27 | 10,0 | AC2 | On | ATP | — | — | GSM-R |
| Kerava asema | Hakosilta | 65 | 10,0 | AC2 | On | ATP | — | On | GSM-R |
| Hyvinkää | Lohja | 64 | 10,5 | — | On | ATP | — | — | GSM-R |
| Lohja | Karjaa | 35 | 10,0 | — | On | ATP | — | — | GSM-R |
| Helsinki asema | Huopalahti | 6 | 10,0 | AC2 | On | ATP | — | — | GSM-R |
| Huopalahti | Vantaankoski | 9 | 11,5 | AC2 | On | ATP | — | — | GSM-R |
| Vantaankoski (from 1.7.2015) | Havukoski | 18 | 40,0 | AC2 | On | ATP | — | — | GSM-R |
| Huopalahti | Kirkkonummi | 31 | 10,5 | AC2 | On | ATP | — | — | GSM-R |
| Kirkkonummi | Karjaa | 49 | 12,0 | AC2 | On | ATP | — | On | GSM-R |
| Karjaa | Hanko asema | 50 | 10,5 | — | On | ATP | — | — | GSM-R |
| Karjaa | Turku asema | 107 | 12,7 | AC2 | On | ATP | — | On | GSM-R |
| Turku asema | Turku satama | 3 | 7,0 | AC2 | On | ATP | — | — | GSM-R |
| Riihimäki asema | Toijala | 76 | 10,0 | AC2 | On | ATP | — | On | GSM-R |
| Toijala | Turku asema | 128 | 10,5 | AC2 | On | ATP | — | On | GSM-R |
| Toijala | Tampere asema | 40 | 10,0 | AC2 | On | ATP | — | On | GSM-R |
| Toijala | Valkeakoski | 18 | 8,0 | — | — | — | — | — | GSM-R |
| Turku asema | Raisio | 8 | 7,0 | — | On | ATP | — | — | GSM-R |
| Raisio | Naantali | 6 | 9,0 | — | — | — | — | — | GSM-R |
| Raisio | Uusikaupunki | 57 | 9,0 | — | On | ATP | — | — | GSM-R |
| Uusikaupunki | Hangonsaari | 3 | 11,5 | — | — | — | — | — | GSM-R |
| Tampere asema | Lielähti | 6 | 9,0 | AC2 | On | ATP | — | On | GSM-R |
| Lielähti | Kokemäki | 91 | 12,5 | AC2 | On | ATP | — | On | GSM-R |
| Kokemäki | Rauma | 47 | 9,0 | AC2 | On | ATP | — | — | GSM-R |
| Kokemäki | Pori | 38 | 9,5 | AC2 | On | ATP | — | — | GSM-R |
| Pori | Mäntyluoto | 21 | 5,5 | — | On | ATP | — | — | GSM-R |
| Pori | Ruosniemi | 8 | 10,0 | — | — | — | — | — | GSM-R |
| Mäntyluoto | Tahkoluoto | 11 | 5,5 | — | On | ATP | — | — | GSM-R |
| Lielähti | Parkano | 69 | 10,5 | AC2 | On | ATP | — | On | GSM-R |
| Niinisalo | Parkano | 42 | 10,0 | — | — | — | — | — | — |
| Parkano | Kihniö | 17 | 9,5 | — | — | — | — | — | — |
| Parkano | Seinäjoen asema | 84 | 10,0 | AC2 | On | ATP | — | On | GSM-R |
| Riihimäki asema | Hakosilta | 48 | 8,0 | AC2 | On | ATP | — | — | GSM-R |
| Hakosilta | Lahti | 11 | 10,0 | AC2 | On | ATP | — | On | GSM-R |
| Lahti | Loviisan satama | 77 | 12,0 | — | — | — | — | — | — |
| Lahti | Heinola | 38 | 12,0 | — | — | — | — | — | — |
| Lahti | Mukkula | 7 | 15,0 | — | — | — | — | — | GSM-R |
| Lahti | Kouvola asema | 61 | 10,0 | AC2 | On | ATP | — | — | GSM-R |
| Kouvola asema | Luumäki | 59 | 10,0 | AC2 | On | ATP | — | — | GSM-R |
| Kouvola asema | Juurikorpi | 33 | 10,0 | AC2 | On | ATP | — | — | GSM-R |
| Juurikorpi | Kotka asema | 18 | 8,5 | AC2 | On | ATP | — | — | GSM-R |
| Kotka asema | Kotkan satama | 1 | 0,0 | AC2 | On | ATP | — | — | GSM-R |
| Kotka Hovinsaari | Kotka Mussalo | 5 | 6,0 | AC2 | — | ATP | — | — | GSM-R |
| Juurikorpi | Hamina | 19 | 10,0 | AC2 | On | ATP | — | — | GSM-R |

Finnish Railway Network Statement 2015

| Liikennepaikka (verkon solmupiste) | Liikennepaikka (verkon solmupiste) | Radan pituus | Määrävä kaltevuus | Sähköistys-järjestelmä | Suojastettu tai radio-ohjattu osuus | Junan kulunvalvonta-järjestelmä | ERTMS | Kallistuvakoristen junien JKV-koodaus | Radio-järjestelmä |
|---|---|----------------|-------------------|--------------------------|--|---------------------------------|-------|---------------------------------------|-------------------|
| Trafikplats (bannätets knutpunkt) | Trafikplats (bannätets knutpunkt) | Banans längd | Största lutningen | Elektrifierings-systemet | Linje-blockerad eller radiostyrd sträcka | Automatisk tågkontrol | | ATC-kodning av lutande tåg | Radio system |
| Traffic operating point (Node of the network) | Traffic operating point (Node of the network) | Length of line | Max gradient | Electrification system | Section blocking or radio controlled section | ATP | | ATP-coding for tilting trains | |
| Kouvola asema | Kuusankoski | 10 | 9,0 | AC2 | — | — | — | — | GSM-R |
| Kouvola asema | Mynttilä | 86 | 12,0 | AC2 | On | ATP | — | On | GSM-R |
| Mynttilä | Ristiina | 21 | 12,5 | — | — | — | — | — | — |
| Mynttilä | Otava | 20 | 10,0 | AC2 | On | ATP | — | On | GSM-R |
| Otava | Otavan satama | 2 | 22,5 | — | — | — | — | — | GSM-R |
| Otava | Pieksämäki asema | 86 | 11,0 | AC2 | On | ATP | — | On | GSM-R |
| Luumäki | Vainikkala asema | 33 | 8,0 | AC2 | On | ATP | — | — | GSM-R |
| Luumäki | Lappeenranta | 27 | 9,5 | AC2 | On | ATP | — | — | GSM-R |
| Lappeenranta | Mustolan satama | 18 | 10,0 | — | — | — | — | — | GSM-R |
| Lappeenranta | Imatra tavara | 39 | 9,0 | AC2 | On | ATP | — | On | GSM-R |
| Imatra tavara | Imatrankoski-raja | 10 | 11,0 | — | — | — | — | — | GSM-R |
| Imatra tavara | Parikkala | 60 | 10,0 | AC2 | On | ATP | — | On | GSM-R |
| Pieksämäki asema | Huutokoski | 31 | 11,0 | — | On | ATP | — | — | GSM-R |
| Huutokoski | Savonlinna | 75 | 12,0 | — | On | ATP | — | — | — |
| Savonlinna | Parikkala | 59 | 12,0 | — | On | ATP | — | — | GSM-R |
| Parikkala | Säkäniemi | 93 | 10,0 | AC2 | On | ATP | — | — | GSM-R |
| Niirala-raja | Säkäniemi | 33 | 10,5 | — | On | ATP | — | — | GSM-R |
| Säkäniemi | Joensuu asema | 37 | 10,5 | AC2 | On | ATP | — | — | GSM-R |
| Joensuu asema | Ilomantsi | 71 | 12,0 | — | — | — | — | — | — |
| Joensuu asema | Viinijärvi | 32 | 9,0 | — | — | ATP | — | — | GSM-R |
| Huutokoski | Varkaus | 18 | 10,0 | — | On | ATP | — | — | GSM-R |
| Varkaus | Kommila | 6 | 10,0 | — | — | — | — | — | GSM-R |
| Varkaus | Viinijärvi | 101 | 11,0 | — | On | ATP | — | — | GSM-R |
| Joensuu asema | Uimaharju | 50 | 17,6 | — | On | ATP | — | — | GSM-R |
| Uimaharju | Lieksa | 54 | 11,5 | — | On | ATP | — | — | GSM-R |
| Lieksa | Pankakoski | 6 | 10,0 | — | — | — | — | — | GSM-R |
| Lieksa | Nurmes | 56 | 12,5 | — | On | ATP | — | — | GSM-R |
| Nurmes | Vuokatti | 85 | 11,5 | — | — | — | — | — | — |
| Vuokatti | Lahnaslampi | 12 | 10,0 | — | — | — | — | — | — |
| Vuokatti | Kontiomäki | 24 | 10,5 | — | — | — | — | — | GSM-R |
| Pieksämäki asema | Suonenjoki | 38 | 9,0 | AC2 | On | ATP | — | — | GSM-R |
| Suonenjoki | Iisvesi | 6 | 10,0 | — | — | — | — | — | — |
| Suonenjoki | Siilinjärvi | 76 | 12,0 | AC2 | On | ATP | — | — | GSM-R |
| Siilinjärvi | Sysmäjärvi | 99 | 10,5 | — | On | ATP | — | — | GSM-R |
| Siilinjärvi | Iisalmi | 60 | 12,0 | AC2 | On | ATP | — | — | GSM-R |
| Iisalmi | Murtomäki | 62 | 12,7 | AC2 | On | ATP | — | On | GSM-R |
| Murtomäki | Otanmäki | 25 | 11,0 | — | — | — | — | — | — |
| Murtomäki | Kajaani | 20 | 12,0 | AC2 | On | ATP | — | On | GSM-R |
| Kontiomäki | Vartius | 95 | 11,0 | AC2 | On | ATP | — | — | GSM-R |
| Vartius | Vartius-raja | 2 | 10,0 | AC2 | On | ATP | — | — | GSM-R |
| Kontiomäki | Ämmänsaari | 92 | 12,0 | — | — | — | — | — | — |
| Tampere asema | Orivesi | 40 | 12,0 | AC2 | On | ATP | — | On | GSM-R |
| Orivesi | Vilppula | 47 | 12,5 | — | On | ATP | — | — | GSM-R |
| Vilppula | Mänttä | 8 | 5,0 | — | — | — | — | — | GSM-R |
| Vilppula | Haapamäki | 26 | 12,5 | — | On | ATP | — | — | GSM-R |
| Haapamäki | Seinäjoen asema | 118 | 12,0 | — | On | ATP | — | — | GSM-R |
| Haapamäki | Jyväskylä | 77 | 12,0 | — | On | ATP | — | — | GSM-R |
| Orivesi | Jämsä | 56 | 12,5 | AC2 | On | ATP | — | On | GSM-R |

Finnish Railway Network Statement 2015

| Liikennepaikka (verkon solmupiste) | Liikennepaikka (verkon solmupiste) | Radan pituus | Määrävä kaltevuus | Sähköistys-järjestelmä | Suojastettu tai radio-ohjattu osuus | Junan kulunvalvonta-järjestelmä | ERTMS | Kallistuvakoristen junien JKV-koodaus | Radio-järjestelmä |
|---|---|----------------|-------------------|--------------------------|--|---------------------------------|-------|---------------------------------------|-------------------|
| Trafikplats (bannätets knutpunkt) | Trafikplats (bannätets knutpunkt) | Banans längd | Största lutningen | Elektrifierings-systemet | Linje-blockerad eller radiostyrd sträcka | Automatisk tågkontrol | | ATC-kodning av lutande tåg | Radio system |
| Traffic operating point (Node of the network) | Traffic operating point (Node of the network) | Length of line | Max gradient | Electrification system | Section blocking or radio controlled section | ATP | | ATP-coding for tilting trains | |
| Jämsä | Kaipola | 7 | 12,0 | — | — | — | — | — | GSM-R |
| Jämsä | Jämsänkoski | 4 | 10,0 | AC2 | On | ATP | — | On | GSM-R |
| Jämsänkoski | Jyväskylä | 52 | 10,5 | AC2 | On | ATP | — | — | GSM-R |
| Jyväskylä | Äänekoski | 47 | 10,5 | — | On | ATP | — | — | GSM-R |
| Äänekoski | Haapajärvi | 164 | 10,5 | — | — | — | — | — | — |
| Jyväskylä | Pieksämäki asema | 80 | 12,5 | AC2 | On | ATP | — | On | GSM-R |
| Seinäjoki asema | Kaskinen | 112 | 10,0 | — | On | ATP | — | — | GSM-R |
| Seinäjoki asema | Vaasa | 75 | 12,0 | AC2 | On | ATP | — | — | GSM-R |
| Vaasa | Vaskiluoto | 5 | 1,0 | — | — | — | — | — | GSM-R |
| Iisalmi | Pyhäkumpu erkanemisvaihde | 63 | 10,0 | — | On | ATP | — | — | GSM-R |
| Pyhäkumpu erkanemisvaihde | Pyhäkumpu | 3 | 3,0 | — | — | — | — | — | GSM-R |
| Pyhäkumpu erkanemisvaihde | Haapajärvi | 36 | 9,5 | — | On | ATP | — | — | GSM-R |
| Haapajärvi | Ylivieska | 55 | 8,0 | — | On | ATP | — | — | GSM-R |
| Seinäjoki asema | Pännäinen | 101 | 10,0 | AC2 | On | ATP | — | On | GSM-R |
| Pännäinen | Pietarsaari | 10 | 6,0 | — | — | — | — | — | GSM-R |
| Pietarsaari | Alholma | 4 | 3,0 | — | — | — | — | — | GSM-R |
| Pännäinen | Kokkola | 33 | 7,0 | AC2 | On | ATP | — | On | GSM-R |
| Kokkola | Ykspihlaja | 5 | 10,0 | AC2 | — | — | — | — | GSM-R |
| Kokkola | Ylivieska | 79 | 10,0 | AC2 | On | ATP | — | On | GSM-R |
| Ylivieska | Tuomioja | 68 | 10,0 | AC2 | On | ATP | — | On | GSM-R |
| Tuomioja | Raahe | 28 | 10,0 | AC2 | On | ATP | — | — | GSM-R |
| Raahe | Rautaruukki | 9 | 10,0 | AC2 | — | — | — | — | GSM-R |
| Tuomioja | Oulu asema | 54 | 10,0 | AC2 | On | ATP | — | On | GSM-R |
| Oulu asema | Kontiomäki | 166 | 10,0 | AC2 | On | ATP | — | — | GSM-R |
| Oulu asema | Kemi | 105 | 10,0 | AC2 | On | ATP | — | — | GSM-R |
| Kemi | Ajos | 9 | 10,0 | — | — | — | — | — | GSM-R |
| Kemi | Laurila | 7 | 10,0 | AC2 | On | ATP | — | — | GSM-R |
| Laurila | Tornio asema | 19 | 7,5 | — | On | ATP | — | — | GSM-R |
| Laurila | Rovaniemi | 106 | 10,0 | AC2 | On | ATP | — | — | GSM-R |
| Rovaniemi | Kemijärvi | 85 | 12,0 | AC2 | On | ATP | — | — | GSM-R |
| Kemijärvi | Isokylä | 7 | 5,5 | — | — | — | — | — | — |
| Tornio asema | Tornio-raja | 3 | 4,0 | — | On | ATP | — | — | GSM-R |
| Tornio asema | Röyttä | 8 | 8,0 | — | — | — | — | — | GSM-R |
| Tornio asema | Kolari | 183 | 10,5 | — | On | ATP | — | — | GSM-R |
| Sysmäjärvi | Vuonos | 7 | 10,0 | — | — | — | — | — | GSM-R |
| Viinijärvi | Sysmäjärvi | 13 | 7,5 | — | On | ATP | — | — | GSM-R |
| Murtomäki | Talvivaara | 24 | 12,5 | AC2 | On | ATP | — | — | GSM-R |
| Kajaani | Lamminniemi | 3 | 10,0 | — | — | — | — | — | GSM-R |
| Kajaani | Kontiomäki | 26 | 12,0 | AC2 | On | ATP | — | — | GSM-R |

Rail Traffic Operating Points

Legend:

| | |
|--|---|
| () in columns regarding platforms | platform not maintained by the Finnish Transport Agency |
| K | yes |
| Y | private |
| K in columns regarding traffic control | remote control |
| M in columns regarding traffic control | manual |

Chart columns:

Name refers the official name of the station and is used in traffic safety work.

Another name is the name of a traffic operating point in Finland's second official language. Another name is usually a Swedish name and only in Sköldvik is the Finnish name Kilpilahti used as another name, contrary to what the present language situation in the municipality would imply.

Abbreviation indicates the abbreviation used of the official name of the station.

Commercial name is mentioned in those cases where it differs from the official name of the stations, used in traffic safety work.

Km Hki describes the distance of a traffic operating point to the old station hall of Helsinki (already torn down), measured by a track kilometre system. According to the system, the location of all elements on tracks is fixed to landmarks.

Municipality refers to the municipality in which the traffic operating point is located.

Traffic control describes whether the traffic operating point has the technical equipment to control the train traffic manually or remote. It does not mean that traffic control services are regularly provided.

Private sidings indicates that the traffic operating point has at least one connection to a siding, owned or managed by a private owner (includes everyone except the Finnish Transport Agency).

Shunting indicates that the form of the tracks at a traffic operating point is such that it is possible to move at least a locomotive to the other end of a line of rolling stock without having to go through the main line of the traffic operating point.

Minimum and maximum platform length indicates the minimum and maximum length of platforms used by passenger trains at the traffic operating point. A passenger train should not be longer than the platform at which it stops. If the platform length is in brackets (), the platform is not maintained by the Finnish Transport Agency and services are operated at the responsibility of the railway undertaking.

Platform height indicates the nominal height of platforms used by passenger trains, calculated from the surface of the rail.

Design train length indicates the longest track of a traffic operating point, other than the main line going through it. The length is measured in such a way that it is usable in both directions.

Power supply indicates at which traffic operating point it is possible to get 400 V or 1500 V electric current mainly for rolling stock or track machinery power supply purposes.

Side loading platform indicates at which traffic operating point it is possible to load freight cars from the side, and shows the maximum platform length at the traffic operating point.

End loading platform indicates at which traffic operating point it is possible load freight rolling stock from the end of the platform (combined transports).

Loading site indicates at which traffic operating point it is possible to load freight rolling stock at rail level. A typical example is loading of raw timber from a vehicle or an intermediate depot at a rail yard onto flatcars.

Crane indicates at which traffic operating point it is possible to use a crane to load wagons, and states the maximum capacity of the crane. This service is not provided by the Finnish Transport Agency.

Fuel indicates at which traffic operating point there is a fuel distribution point. This service is not provided by the Finnish Transport Agency.

The Passenger traffic column shows the operating points where passenger traffic can be operated.

The Freight transport column shows the operating points where freight transport can be operated.

The Turntables column indicates the traffic operating points where turntables can be used. If turntable is privately owned it is marked with Y. If it is owned by Finnish Transport Agency, length of turntable is marked.

| Nimi | Toinen nimi | Lyhenne | Kaupallinen nimi | Tyyppi | Km Hki | Rataosuus | Kunta | Liikenteenohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|-------------------------|--------------------|-------------|-------------------|--|----------------|---|------------------|------------------|---------------------------|------------------------|
| Namn | Annat namn | Förkortning | Kommersiellt namn | Typ | Km Hki | Banavsnitt | Kommun | Trafikledning | Privata spår-anläggningar | Möjlighet till växling |
| Name | Another name | Abbr. | Commercial name | Type | Km Hki | Section | Municipality | Traffic control | Private sidings | Shunting |
| Ahvenus | | Ahv | | Traffic operating point | 270+960 | Lietähti-Kokemäki | Kokemäki | K | | |
| Airaksela | | Arl | | Traffic operating point | 436+985 | Pieksämäki-Kontiomäki | Kuopio | K | | |
| Ajos | | Ajo | | Traffic operating point | 867+100 | Kemi-Ajos | Kemi | | K | |
| Alapitkä | | Apt | | Traffic operating point | 505+840 | Pieksämäki-Kontiomäki | Lapinlahti | K | | |
| Alavus | | Alv | | Traffic operating point | 373+445 | Orivesi-Seinäjoki | Alavus | K | | |
| Alholma | Alholmen | Alh | | Traffic operating point | 532+570 | Pietarsaari-Alholma | Pietarsaari | | K | |
| Arola | | Aro | | Traffic operating point | 707+668 | Kontiomäki-Vartiuss-rajaa | Hyrnsalmi | K | | |
| Dragsvik | | Dra | | Traffic operating point | 171+180 | Karjaa-Hanko | Raasepori | K | | |
| Dynamiittivaihte | | Dmv | | Switch on a track line | 199+185 | Karjaa-Hanko | Hanko | | K | |
| Eläinpuisto-Zoo | | Epz | | Stopping point | 338+751 | Orivesi-Seinäjoki | Ähtäri | | | |
| Eno | | Eno | | Traffic operating point | 660+170 | Joensuu-Nurmes | Joensuu | K | | |
| Ervelä | | Erv | | Traffic operating point | 119+816 | Helsinki-Turku satama | Salo | K | | |
| Eskola | | Ela | | Traffic operating point | 603+762 | Seinäjoki-Oulu | Kannus | K | | |
| Espoo | Esbo | Epo | | Traffic operating point | 20+600 | Helsinki-Turku satama | Espoo | K | | |
| Haapajärvi | | Hpj | | Traffic operating point | 649+205 | Iisalmi-Ylivieska, Äänekoski-Haapajärvi | Haapajärvi | K | K | |
| Haapakoski | | Hps | | Traffic operating point | 393+454 | Pieksämäki-Kontiomäki | Pieksämäki | K | | |
| Haapamäen | | Hmk | | | | | | | | |
| kyllästämö | | | | Switch on a track line | 304+940 | Orivesi-Seinäjoki | Keuruu | | K | |
| Haapamäki | | Hpk | | Traffic operating point | 300+235 | Haapamäki-Jyväskylän, Orivesi-Seinäjoki | Keuruu | K | K | |
| Haarajoki | | Haa | | Traffic operating point | 39+567 | Kerava-Hakosilta | Järvenpää | K | | |
| Hakosilta | | Hlt | | Traffic operating point | 119+540 | Kerava-Hakosilta, Riihimäki-Kouvola | Hollola | K | | |
| Haksi | Hax | Hsi | | Stopping point | 56+737 | Olli-Porvoo | Porvoo | | | |
| Hamina | Fredrikshamn | Hma | | Traffic operating point | 243+646 | Juurikorpi-Hamina | Hamina | M | K | |
| Hammaslahti | | Hsl | | Traffic operating point | 602+199 | Kouvola-Joensuu | Joensuu | K | | |
| Hanala | Hanaböle | Hna | | Traffic operating point | 21+394 | Helsinki-Riihimäki | Vantaa | K | | |
| Hangonsaari | | Hgs | | Traffic operating point | 269+655 | Uusikaupunki-Hangonsaari | Uusikaupunki | | K | |
| Hanhikoski | | Hnh | | Switch on a track line | 1047+083 | Laurila-Kemijärvi | Kemijärvi | | | |
| Hankasalmi | | Hks | | Traffic operating point | 418+089 | Jyväskylä-Pieksämäki | Hankasalmi | K | K | |
| HANKO | | Han | | Divided Traffic Operating Point | - | Karjaa-Hanko | | K | | |
| <i>Hanko asema</i> | <i>Hangö</i> | <i>Hnk</i> | <i>Hanko</i> | <i>Part of a Traffic Operating Point (Hanko)</i> | <i>207+119</i> | | <i>Hanko</i> | | <i>K</i> | <i>K</i> |
| <i>Hanko tavara</i> | | <i>Hnkt</i> | | <i>Part of a Traffic Operating Point (Hanko)</i> | <i>206+350</i> | | <i>Hanko</i> | | | <i>K</i> |
| <i>Hanko-Pohjoinen</i> | <i>Hangö Norra</i> | <i>Hkp</i> | | <i>Part of a Traffic Operating Point (Hanko)</i> | <i>205+935</i> | | <i>Hanko</i> | | | |
| Harjavalta | | Hva | | Traffic operating point | 295+542 | Kokemäki-Pori | Harjavalta | K | K | |
| Harju | | Hj | | Traffic operating point | 201+643 | Kouvola-Pieksämäki | Kouvola | K | | |
| Harviala | | Hrv | | Traffic operating point | 99+456 | Riihimäki-Tampere | Janakkala | K | | |
| Haukipudas | | Hd | | Traffic operating point | 775+159 | Oulu-Laurila | Oulu | K | | |
| Haukivuori | | Hau | | Traffic operating point | 344+442 | Kouvola-Pieksämäki | Mikkeli | K | | |
| HAUSJÄRVI | | Hjr | | Divided Traffic Operating Point | - | Riihimäki-Kouvola | | K | | |
| <i>Hausjärvi tavara</i> | | <i>Has</i> | | <i>Part of a Traffic Operating Point (Hausjärvi)</i> | <i>86+210</i> | | <i>Hausjärvi</i> | | | <i>K</i> |
| <i>Oitti</i> | | <i>Oi</i> | | <i>Part of a Traffic Operating Point (Hausjärvi)</i> | <i>86+809</i> | | <i>Hausjärvi</i> | | | |
| Haviseva | | Hvs | | Traffic operating point | 208+135 | Tampere-Jyväskylä | Kangasala | K | | |
| Heikkilä | | Hek | | Traffic operating point | 34+856 | Helsinki-Turku satama | Kirkkonummi | K | | |
| Heinola | | Ha | | Traffic operating point | 167+607 | Lahti-Heinola | Heinola | M | K | |

| Nimi | Toinen nimi | Lyhenne | Kaupallinen nimi | Tyyppi | Km Hki | Rataosuus | Kunta | Liikenteenohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|-------------------------------|---------------------------|-------------|--------------------------------------|---|----------------|---|-----------------|------------------|---------------------------|------------------------|
| Namn | Annat namn | Förkortning | Kommersiellt namn | Typ | Km Hki | Banavsnitt | Kommun | Trafikledning | Privata spär-anläggningar | Möjlighet till växling |
| Name | Another name | Abbr. | Commercial name | Type | Km Hki | Section | Municipality | Traffic control | Private sidings | Shunting |
| Heinoo | | Hno | | Traffic operating point | 237+965 | Lielähti-Kokemäki | Sastamala | K | | |
| Heinävaara | | Häv | | Traffic operating point | 648+408 | Joensuu-Ilomantsi | Joensuu | | | K |
| Heinävesi | | Hnv | | Traffic operating point | 468+135 | Pieksämäki-Joensuu | Heinävesi | K | | K |
| HELSINKI | | Hel | | Divided Traffic Operating Point | – | Helsinki-Turku satama, Helsinki-Riihimäki | | M | | |
| <i>Helsinki asema</i> | <i>Helsingfors</i> | <i>Hki</i> | <i>Helsinki päärautatieasema</i> | <i>Part of a Traffic Operating Point (Helsinki)</i> | <i>0+159</i> | | <i>Helsinki</i> | | | <i>K</i> |
| <i>Pasila asema</i> | <i>Böle</i> | <i>Psl</i> | <i>Pasila</i> | <i>Part of a Traffic Operating Point (Helsinki)</i> | <i>3+230</i> | | <i>Helsinki</i> | | | |
| <i>Pasila autajuna-asema</i> | <i>Böle biltågstation</i> | <i>Pau</i> | | <i>Part of a Traffic Operating Point (Helsinki)</i> | <i>4+319</i> | | <i>Helsinki</i> | | | |
| <i>Ilmala asema</i> | | <i>Ila</i> | <i>Ilmala</i> | <i>Part of a Traffic Operating Point (Helsinki)</i> | <i>4+434</i> | | <i>Helsinki</i> | | | |
| <i>Helsinki Kivihaka</i> | <i>Stenhagen</i> | <i>Khk</i> | | <i>Part of a Traffic Operating Point (Helsinki)</i> | <i>4+701</i> | | <i>Helsinki</i> | | | |
| <i>Pasila tavara</i> | | <i>Pslt</i> | | <i>Part of a Traffic Operating Point (Helsinki)</i> | <i>4+748</i> | | <i>Helsinki</i> | | <i>K</i> | <i>K</i> |
| <i>Ilmala ratapiha</i> | | <i>Ilr</i> | | <i>Part of a Traffic Operating Point (Helsinki)</i> | <i>4+950</i> | | <i>Helsinki</i> | | <i>K</i> | <i>K</i> |
| <i>Käpylä</i> | <i>Kottby</i> | <i>Käp</i> | | <i>Part of a Traffic Operating Point (Helsinki)</i> | <i>5+840</i> | | <i>Helsinki</i> | | | |
| <i>Oulunkylä</i> | <i>Äggelby</i> | <i>Olk</i> | | <i>Part of a Traffic Operating Point (Helsinki)</i> | <i>7+399</i> | | <i>Helsinki</i> | | <i>K</i> | |
| Herrala | | Hr | | Seisake | 115+790 | Riihimäki-Kouvola | Hollola | | | |
| Hiirola | | Hir | | Traffic operating point | 318+957 | Kouvola-Pieksämäki | Mikkeli | K | | |
| Hikiä | | Hk | | Stopping point | 79+743 | Riihimäki-Kouvola | Hausjärvi | | <i>K</i> | |
| Hiliosensalmi | | Hls | | Traffic operating point | 233+344 | Kouvola-Pieksämäki | Kouvola | K | | |
| Hinthaara | Hindhår | Hh | | Stopping point | 52+150 | Olli-Porvoo | Porvoo | | | |
| Hirvineva | | Hvn | | Traffic operating point | 715+500 | Seinäjoki-Oulu | Liminka | K | | <i>K</i> |
| Humppila | | Hp | | Traffic operating point | 188+778 | Toijala-Turku | Humppila | K | <i>K</i> | <i>K</i> |
| Huopalahti | Hoplax | Hpl | | Traffic operating point | 6+375 | Helsinki-Turku satama, Huopalahti-Vantaankoski | Helsinki | K | | |
| Huutokoski | | Hko | | Traffic operating point | 406+988 | Pieksämäki-Joensuu, Huutokoski-Savonlinna | Joroinen | K | <i>K</i> | |
| Hyrynsalmi | | Hys | | Traffic operating point | 704+601 | Kontiomäki-Ämmänsaari | Hyrynsalmi | M | | <i>K</i> |
| Hyvinkää | Hyvinge | Hy | | Traffic operating point | 58+792 | Helsinki-Riihimäki, Hyvinkää-Karjaa | Hyvinkää | K | <i>K</i> | <i>K</i> |
| Hämeenlinna | Tavastehus | Hl | | Traffic operating point | 107+559 | Riihimäki-Tampere | Hämeenlinna | K | <i>K</i> | <i>K</i> |
| Härmä | | Hm | | Traffic operating point | 472+940 | Seinäjoki-Oulu | Kauhava | K | | <i>K</i> |
| Höljää | | Höl | | Stopping point | 765+261 | Joensuu-Nurmes | Nurmes | | <i>K</i> | <i>K</i> |
| Ii | | Ii | | Traffic operating point | 789+165 | Oulu-Laurila | Ii | K | | <i>K</i> |
| Iisalmen teollisuusraiteet | Keveli | Itr | | Switch on a track line | 548+611 | Pieksämäki-Kontiomäki | Iisalmi | | <i>K</i> | <i>K</i> |
| Iisalmi | Idensalmi | Ilm | | Traffic operating point | 550+360 | Iisalmi-Ylivieska, Pieksämäki-Kontiomäki | Iisalmi | K | <i>K</i> | <i>K</i> |
| Iisvesi | | Isv | | Traffic operating point | 420+127 | Suonenjoki-Iisvesi | Suonenjoki | | <i>K</i> | <i>K</i> |
| Iittala | | Iita | | Stopping point | 129+286 | Riihimäki-Tampere | Hämeenlinna | | | |
| Ilomantsi | Ilomants | Ilo | | Traffic operating point | 695+203 | Joensuu-Ilomantsi | Ilomantsi | M | <i>K</i> | <i>K</i> |
| IMATRA | | Ima | | Divided Traffic Operating Point | 326+542 | Kouvola-Joensuu, Imatra tavara-Imatrankoski-raja | Imatra | K | | |
| <i>Imatra asema</i> | | <i>Imr</i> | <i>Imatra</i> | <i>Part of a Traffic Operating Point (Imatra)</i> | <i>323+977</i> | | <i>Imatra</i> | | | |
| <i>Imatra tavara</i> | | <i>Imt</i> | | <i>Part of a Traffic Operating Point (Imatra)</i> | <i>326+542</i> | | <i>Imatra</i> | | <i>K</i> | <i>K</i> |

| Nimi | Toinen nimi | Lyhenne | Kaupallinen nimi | Tyyppi | Km Hki | Rataosuus | Kunta | Liikenteenohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|--------------------|--------------|-------------|-------------------|---|----------|---|---------------|------------------|---------------------------|------------------------|
| Namn | Annat namn | Förkortning | Kommersiellt namn | Typ | Km Hki | Banavsnitt | Kommun | Trafikledning | Privata spär-anläggningar | Möjlighet till växling |
| Name | Another name | Abbr. | Commercial name | Type | Km Hki | Section | Municipality | Traffic control | Private sidings | Shunting |
| Imatrankoski | | Imk | | Part of a Traffic Operating Point (Imatra) | 331+267 | | Imatra | | K | K |
| Pelkola | | Pa | | Part of a Traffic Operating Point (Imatra) | 335+672 | | Imatra | | K | K |
| Imatrankoski-raja | | Imkr | | Traffic operating point | 337+095 | Imatra tavara-Imatrankoski-raja | Imatra | | | |
| Inha | | In | | Switch on a track line | 341+367 | Orivesi-Seinäjoki | Ahtäri | | | K |
| Inkeroinen | | Ikkr | | Traffic operating point | 212+781 | Kouvola-Kotka | Kouvola | K | K | K |
| Inkoo | Ingå | Iko | | Traffic operating point | 70+620 | Helsinki-Turku satama | Inkoo | K | | K |
| Isokangas | | Isg | | Switch on a track line | 431+759 | Niinisalo-Parkano-Kihniö | Parkano | | | |
| Isokylä | | Ikä | | Traffic operating point | 1062+829 | Kemijärvi-Kelloselkä | Kemijärvi | M | K | K |
| Isokyrö | Storkyro | Iky | | Traffic operating point | 447+488 | Seinäjoki-Vaasa | Isokyrö | K | | K |
| Jalasjärvi | | Jal | | Traffic operating point | 309+871 | Tampere-Seinäjoki | Jalasjärvi | K | | K |
| Jepua | Jeppo | Jpa | | Traffic operating point | 495+784 | Seinäjoki-Oulu | Uusikaarlepyy | K | | K |
| JOENSUU | | Joe | | Divided Traffic Operating Point | - | Pieksämäki-Joensuu, Kouvola-Joensuu, Joensuu-Ilomantsi, Joensuu-Nurmes | | M | | |
| Joensuu Sulkulahti | | Sul | | Part of a Traffic Operating Point (Joensuu) | 622+650 | | Joensuu | | | K |
| Joensuu Peltola | | Plt | | Part of a Traffic Operating Point (Joensuu) | 623+540 | | Joensuu | | K | K |
| Joensuu asema | | Jns | Joensuu | Part of a Traffic Operating Point (Joensuu) | 624+313 | | Joensuu | | | K |
| Jokela | | Jk | | Traffic operating point | 47+937 | Helsinki-Riihimäki | Tuusula | K | | K |
| Joroinen | Jorois | Jor | | Switch on a track line | 414+617 | Huutokoski-Savonlinna | Joroinen | | | K |
| Jorvas | | Jrs | | Stopping point | 32+322 | Helsinki-Turku satama | Kirkkonummi | | | |
| Joutseno | | Jts | | Traffic operating point | 305+826 | Kouvola-Joensuu | Lappeenranta | K | K | K |
| Juankoski | | Jki | | Traffic operating point | 531+995 | Siilinjärvi-Viinijärvi | Juankoski | K | K | K |
| Jutila | | Jut | | Traffic operating point | 94+620 | Riihimäki-Kouvola | Kärkölä | K | | |
| Juupajoki | | Jj | | Stopping point | 246+580 | Orivesi-Seinäjoki | Juupajoki | | | |
| Juurikorpi | | Jri | | Traffic operating point | 224+898 | Kouvola-Kotka, Juurikorpi-Hamina | Kotka | K | | |
| Jyväskylä | | Jy | | Traffic operating point | 340+370 | Jyväskylä-Pieksämäki, Haapamäki-Jyväskylä, Jyväskylä-Äänekoski, Tampere-Jyväskylä | Jyväskylä | K | K | K |
| Jämsä | | Jäs | | Traffic operating point | 284+084 | Jämsä-Kaipola, Tampere-Jyväskylä | Jämsä | K | | K |
| Jämsänkoski | | Jsk | | Traffic operating point | 287+917 | Tampere-Jyväskylä | Jämsä | K | K | K |
| Järvelä | | Jr | | Traffic operating point | 103+596 | Riihimäki-Kouvola | Kärkölä | K | K | K |
| JÄRVENPÄÄ | | Jvp | | Divided Traffic Operating Point | - | Helsinki-Riihimäki | | K | | |
| Järvenpää asema | Träskända | Jp | Järvenpää | Part of a Traffic Operating Point (Järvenpää) | 36+786 | | Järvenpää | | | |
| Saunakallio | | Sau | | Part of a Traffic Operating Point (Järvenpää) | 38+846 | | Järvenpää | | K | K |
| Purola | | Pur | | Part of a Traffic Operating Point (Järvenpää) | 40+533 | | Järvenpää | K | | |
| Kaipiainen | | Kpa | | Traffic operating point | 214+451 | Kouvola-Joensuu | Kouvola | K | K | K |
| Kaipola | | Kla | | Traffic operating point | 290+303 | Jämsä-Kaipola | Jämsä | | K | K |
| Kairoskoski | | Kko | | Switch on a track line | 423+184 | Niinisalo-Parkano-Kihniö | Parkano | | | K |
| Kaitjärvi | | Kjr | | Traffic operating point | 226+912 | Kouvola-Joensuu | Luumäki | K | | |
| Kajaani | Kajana | Kaj | | Traffic operating point | 633+491 | Pieksämäki-Kontiomäki, Kajaani-Lamminniemi | Kajaani | K | | K |
| Kaleton | | Ktn | | Switch on a track line | 320+875 | Haapamäki-Jyväskylä | Keuruu | | | |
| Kalkku | | Kau | | Traffic operating point | 199+471 | Lielähti-Kokemäki | Tampere | K | K | |
| Kalliovarasto | | Kao | | Switch on a track line | 644+770 | Pieksämäki-Kontiomäki | Kajaani | | K | |

| Nimi | Toinen nimi | Lyhenne | Kaupallinen nimi | Tyyppi | Km Hki | Rataosuus | Kunta | Liikenteenohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|------------------|--------------|-------------|-------------------|---|----------|--|--------------|------------------|---------------------------|------------------------|
| Namn | Annat namn | Förkortning | Kommersiellt namn | Typ | Km Hki | Banavsnitt | Kommun | Trafikledning | Privata spär-anläggningar | Möjlighet till växling |
| Name | Another name | Abbr. | Commercial name | Type | Km Hki | Section | Municipality | Traffic control | Private sidings | Shunting |
| Kallistahti | | Kll | | Switch on a track line | 465+822 | Huutokoski–Savonlinna | Savonlinna | | | K |
| Kalvitsa | | Ksa | | Traffic operating point | 330+634 | Kouvola–Pieksämäki | Mikkeli | K | | K |
| Kangas | | Kgs | | Traffic operating point | 642+466 | Seinäjoki–Oulu | Ylivieska | K | | K |
| Kannelmäki | Gamlas | Kan | | Traffic operating point | 9+300 | Huopalahti–Vantaankoski | Helsinki | K | | |
| Kannonkoski | | Ksi | | Traffic operating point | 488+694 | Äänekoski–Haapajärvi | Kannonkoski | M | | K |
| Kannus | | Kns | | Traffic operating point | 591+582 | Seinäjoki–Oulu | Kannus | K | | K |
| Karhejärvi | | Krr | | Traffic operating point | 224+902 | Tampere–Seinäjoki | Ylöjärvi | K | | K |
| Karhukangas | | Khg | | Traffic operating point | 621+508 | Seinäjoki–Oulu | Ylivieska | K | | |
| Karjaa | Karis | Kr | | Traffic operating point | 157+817 | Helsinki–Turku satama, Hyvinkää–Karjaa, Karjaa–Hanko | Raasepori | K | K | K |
| Karkku | | Kru | | Traffic operating point | 230+733 | Lielähti–Kokemäki | Sastamala | K | | K |
| Karviainen | | Kar | | Traffic operating point | 247+320 | Toijala–Turku | Aura | K | | |
| Kaskinen | Kaskö | Ksk | | Traffic operating point | 530+522 | Seinäjoki–Kaskinen | Kaskinen | K | K | K |
| Kattilaharju | | Kth | | Traffic operating point | 205+556 | Kouvola–Joensuu | Kouvola | K | | |
| Kauhajoki | | Kji | | Traffic operating point | 472+720 | Seinäjoki–Kaskinen | Kauhajoki | K | | |
| Kauhava | | Kha | | Traffic operating point | 455+728 | Seinäjoki–Oulu | Kauhava | K | K | K |
| KAUKLAHTI | | Kal | | Divided Traffic Operating Point | – | Helsinki–Turku satama | | K | | |
| Kauklahti asema | Köklax | Klh | Kauklahti | Part of a Traffic Operating Point (Kauklahti) | 24+277 | | Espoo | | | K |
| Mankki | Mankby | Mnk | | Part of a Traffic Operating Point (Kauklahti) | 25+401 | | Kirkkonummi | | K | |
| Kaulinranta | | Klr | | Traffic operating point | 963+350 | Tornio–Kolari | Ylitornio | K | | |
| Kauniainen | Grankulla | Kni | | Traffic operating point | 16+054 | Helsinki–Turku satama | Kauniainen | K | | K |
| Kauppihanmäki | | Kpl | | Traffic operating point | 568+751 | Pieksämäki–Kontiomäki | Iisalmi | K | | K |
| Kausala | | Ka | | Stopping point | 169+425 | Riihimäki–Kouvola | Jitti | | | |
| Keitelepoija | | Ktp | | Traffic operating point | 519+256 | Äänekoski–Haapajärvi | Viitasaari | M | | K |
| Kekomäki | | Kek | | Traffic operating point | 79+288 | Riihimäki–Kouvola | Hausjärvi | K | | |
| Kelkkämäki | | Klk | | Switch on a track line | 399+992 | Jyväskylä–Pieksämäki | Laukaa | | | |
| Kemi | | Kem | | Traffic operating point | 858+300 | Oulu–Laurila, Kemi–Ajos | Kemi | K | K | K |
| Kemijärvi | | Kjä | | Traffic operating point | 1056+399 | Kemijärvi–Kellosoelkä, Laurila–Kemijärvi | Kemijärvi | K | K | K |
| Kempele | | Kml | | Traffic operating point | 741+075 | Seinäjoki–Oulu | Kempele | K | | K |
| Kera | | Kea | | Stopping point | 14+536 | Helsinki–Turku satama | Espoo | | | |
| KERAVA | | Kev | | Divided Traffic Operating Point | – | Helsinki–Riihimäki, Kerava–Häskosilta, Kerava–Sköldvik, Kerava–Vuosaari | | K | | |
| Kerava asema | Kervo | Ke | Kerava | Part of a Traffic Operating Point (Kerava) | 28+869 | | Kerava | | K | K |
| Kytömaa | | Kyt | | Part of a Traffic Operating Point (Kerava) | 31+274 | | Kerava | | | |
| Kerimäki | | Kiä | | Traffic operating point | 495+531 | Savonlinna–Parikkala | Savonlinna | K | | K |
| Kesälahti | | Kti | | Traffic operating point | 428+003 | Kouvola–Joensuu | Kitee | K | | |
| Keuruu | | Keu | | Traffic operating point | 316+041 | Haapamäki–Jyväskylä | Keuruu | K | | K |
| Kihniö | | Kiö | | Traffic operating point | 444+460 | Niinisalo–Parkano–Kihniö | Kihniö | M | | K |
| Kiiala | Kiala | Kia | | Stopping point | 60+013 | Oli–Porvoo | Porvoo | | | |
| Kilo | | Kil | | Stopping point | 13+035 | Helsinki–Turku satama | Espoo | | | |
| Kilpua | | Kua | | Traffic operating point | 668+910 | Seinäjoki–Oulu | Oulainen | K | | K |
| Kinahmi | | Knh | | Switch on a track line | 508+922 | Siilinjärvi–Viinijärvi | Kuopio | | K | |
| Kinni | | Kii | | Traffic operating point | 247+982 | Kouvola–Pieksämäki | Mäntyharju | K | | |
| Kirjola | | Kij | | Switch on a track line | 384+475 | Kouvola–Joensuu | Parikkala | | K | |
| Kirkkonummi | Kyrkslätt | Kkn | | Traffic operating point | 37+503 | Helsinki–Turku satama | Kirkkonummi | K | | K |

| Nimi | Toinen nimi | Lyhenne | Kaupallinen nimi | Tyyppi | Km Hki | Rataosuus | Kunta | Liikenteenohjaus | Yksityisraiteita | Vaihtotyö- mahdollisuus |
|--------------------------|--------------|-------------|-------------------|--|----------------|---|-----------------|------------------|-------------------------------|----------------------------|
| Namn | Annat namn | Förkortning | Kommersiellt namn | Typ | Km Hki | Banavsnitt | Kommun | Trafikledning | Privata spår- anläggningar | Möjlighet till växling |
| Name | Another name | Abbr. | Commercial name | Type | Km Hki | Section | Municipality | Traffic control | Private sidings | Shunting |
| Kirkniemi | Gerknäs | Krn | | Traffic operating point | 136+261 | Hyvinkää–Karjaa | Lohja | K | K | K |
| Kitee | | Kit | | Traffic operating point | 460+016 | Kouvola–Joensuu | Kitee | K | K | K |
| Kiukainen | | Kn | | Traffic operating point | 297+395 | Kokemäki–Rauma | Eura | K | | K |
| Kiuruvesi | | Krv | | Traffic operating point | 583+985 | Iisalmi–Ylivieska | Kiuruvesi | K | K | K |
| Kivesjärvi | | Kvj | | Traffic operating point | 878+146 | Oulu–Kontiomäki | Paltamo | K | | |
| Kohtavaara | | Koh | | Stopping point | 775+927 | Joensuu–Nurmes | Nurmes | | | |
| Koivu | | Kvu | | Traffic operating point | 923+373 | Laurila–Kemijärvi | Tervola | K | | K |
| Koivuhovi | Björkgård | Kvh | | Stopping point | 17+861 | Helsinki–Turku satama | Espoo | | | |
| Koivukylä | Björkby | Kvy | | Stopping point | 19+440 | Helsinki–Riihimäki | Vantaa | | | |
| Kokemäki | Kumo | Kki | | Traffic operating point | 284+442 | Lielähti–Kokemäki, Kokemäki–Rauma, Kokemäki–Pori | Kokemäki | K | | K |
| Kokkola | Karleby | Kok | | Traffic operating point | 551+441 | Kokkola–Ykspihlaja, Seinäjoki–Oulu | Kokkola | K | K | K |
| Kolari | | Kli | | Traffic operating point | 1067+206 | Tornio–Kolari | Kolari | K | | K |
| Kolho | | Klo | | Stopping point | 286+265 | Orivesi–Seinäjoki | Mänttä-Vilppula | | | K |
| Kolppi | Källby | Kpi | | Traffic operating point | 525+100 | Seinäjoki–Oulu | Pedersöre | K | | K |
| Kommila | | Kmm | | Traffic operating point | 429+700 | Varkaus–Kommila | Varkaus | | K | K |
| Komu | | Kom | | Switch on a track line | 607+174 | Iisalmi–Ylivieska | Pyhäjärvi | | K | |
| Kontiolahti | | Khi | | Traffic operating point | 640+295 | Joensuu–Nurmes | Kontiolahti | K | | K |
| Kontiomäki | | Kon | | Traffic operating point | 658+786 | Nurmes–Kontiomäki, Oulu–Kontiomäki, Kontiomäki–Ämmänsaari, Pieksämäki–Kontiomäki, Kontiomäki–Vartius-raja | Paltamo | K | K | K |
| Koria | | Kra | | Stopping point | 185+374 | Riihimäki–Kouvola | Kouvola | | | |
| Korkeakoski | | Kas | | Traffic operating point | 247+910 | Orivesi–Seinäjoki | Juupajoki | K | K | K |
| Korso | | Krs | | Stopping point | 22+669 | Helsinki–Riihimäki | Vantaa | | | |
| Korvensuo | | Ksu | | Traffic operating point | 50+500 | Kerava–Hakosilta | Mäntsälä | K | | |
| Koskenkorva | | Kos | | Traffic operating point | 442+447 | Seinäjoki–Kaskinen | Ilmajoki | M | | K |
| KOTKA | | Kot | | Divided Traffic Operating Point | – | Kouvola–Kotka, Kotka Hovinsaari–Kotka Mussalo | | M | | |
| <i>Kotka Hovinsaari</i> | | <i>Hos</i> | | <i>Part of a Traffic Operating Point (Kotka)</i> | <i>240+400</i> | | <i>Kotka</i> | | <i>K</i> | <i>K</i> |
| <i>Kotka tavara</i> | | <i>Ktt</i> | | <i>Part of a Traffic Operating Point (Kotka)</i> | <i>240+870</i> | | <i>Kotka</i> | | | <i>K</i> |
| <i>Paimenportti</i> | | <i>Pti</i> | | <i>Part of a Traffic Operating Point (Kotka)</i> | <i>241+190</i> | | <i>Kotka</i> | | | |
| <i>Kotka asema</i> | | <i>Kta</i> | <i>Kotka</i> | <i>Part of a Traffic Operating Point (Kotka)</i> | <i>242+775</i> | | <i>Kotka</i> | | <i>K</i> | <i>K</i> |
| <i>Kotkan satama</i> | | <i>Kts</i> | | <i>Part of a Traffic Operating Point (Kotka)</i> | <i>243+579</i> | | <i>Kotka</i> | | <i>K</i> | <i>K</i> |
| <i>Kotolahti</i> | | <i>Koo</i> | | <i>Part of a Traffic Operating Point (Kotka)</i> | <i>245+203</i> | | <i>Kotka</i> | | <i>K</i> | <i>K</i> |
| <i>Kotka Mussalo</i> | | <i>Mss</i> | | <i>Part of a Traffic Operating Point (Kotka)</i> | <i>247+057</i> | | <i>Kotka</i> | | <i>K</i> | <i>K</i> |
| KOUVOLA | | Kvl | | Divided Traffic Operating Point | – | Riihimäki–Kouvola, Kouvola–Pieksämäki, Kouvola–Kotka, Kouvola–Joensuu, Kouvola–Kuusankoski | | M | | |
| <i>Kouvola asema</i> | | <i>Kv</i> | <i>Kouvola</i> | <i>Part of a Traffic Operating Point (Kouvola)</i> | <i>191+540</i> | | <i>Kouvola</i> | | <i>K</i> | <i>K</i> |
| <i>Kouvola lajittelu</i> | | <i>Kvla</i> | | <i>Part of a Traffic Operating Point (Kouvola)</i> | <i>192+570</i> | | <i>Kouvola</i> | | <i>K</i> | <i>K</i> |
| <i>Kouvola tavara</i> | | <i>Kvt</i> | | <i>Part of a Traffic Operating Point (Kouvola)</i> | <i>194+050</i> | | <i>Kouvola</i> | | <i>K</i> | <i>K</i> |
| <i>Kouvola Oikoraide</i> | | <i>Oik</i> | | <i>Part of a Traffic Operating Point (Kouvola)</i> | <i>194+460</i> | | <i>Kouvola</i> | | | |

| Nimi | Toinen nimi | Lyhenne | Kaupallinen nimi | Tyyppi | Km Hki | Rataosuus | Kunta | Liikenteenohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|------------------------|-----------------------------------|-------------|-------------------|---|---------|--|---------------|------------------|---------------------------|------------------------|
| Namn | Annat namn | Förkortning | Kommersiellt namn | Typ | Km Hki | Banavsnitt | Kommun | Trafikledning | Privata spär-anläggningar | Möjlighet till växling |
| Name | Another name | Abbr. | Commercial name | Type | Km Hki | Section | Municipality | Traffic control | Private sidings | Shunting |
| Kullasvaara | | Kuv | | Part of a Traffic Operating Point (Kouvola) | 197+300 | | Kouvola | | | |
| Kovjoki | | Koi | | Traffic operating point | 508+925 | Seinäjoki–Oulu | Uusikaarlepyy | K | | |
| Kruunupyy | Kronoby | Kpy | | Traffic operating point | 537+585 | Seinäjoki–Oulu | Kruunupyy | K | K | K |
| Kuivasjärvi | | Kis | | Traffic operating point | 276+327 | Tampere–Seinäjoki | Parkano | K | | K |
| KUOPIO | | Kpo | | Divided Traffic Operating Point | – | Pieksämäki–Kontiomäki | | M | | |
| Kuopio asema | | Kuo | Kuopio | Part of a Traffic Operating Point (Kuopio) | 464+590 | | Kuopio | | | K |
| Kuopio tavara | | Kuot | | Part of a Traffic Operating Point (Kuopio) | 465+500 | | Kuopio | | K | K |
| Kurkimäki | | Krm | | Traffic operating point | 444+074 | Pieksämäki–Kontiomäki | Kuopio | K | | K |
| Kuurila | | Ku | | Traffic operating point | 138+769 | Riihimäki–Tampere | Hämeenlinna | K | | |
| Kuusankoski | | Kuk | | Traffic operating point | 199+290 | Kouvola–Kuusankoski | Kouvola | M | K | K |
| Kylänlahti | | Kyn | | Stopping point | 742+960 | Joensuu–Nurmes | Lieksa | | | |
| Kymi | Kymmene | Ky | | Traffic operating point | 233+450 | Kouvola–Kotka | Kotka | M | K | K |
| Kyminlinna | | Kln | | Stopping point | 237+229 | Kouvola–Kotka | Kotka | | | |
| Kyrö | | Kö | | Traffic operating point | 232+875 | Toijala–Turku | Karinainen | K | | K |
| Kyrölä | Nimi 1. 7.2015 alkaen Ainola (ty) | Krö | | Stopping point | 34+784 | Helsinki–Riihimäki | Järvenpää | | | |
| Kälviä | Kelviä | Klv | | Traffic operating point | 568+144 | Seinäjoki–Oulu | Kokkola | K | | K |
| Köykkäri | | Kök | | Traffic operating point | 486+491 | Seinäjoki–Oulu | Kauhava | K | | |
| Lahdenperä | | Lpr | | Traffic operating point | 267+080 | Tampere–Jyväskylä | Jämsä | K | | |
| Lahnaslampi | | Lhn | | Traffic operating point | 881+053 | Vuokatti–Lahnaslampi | Sotkamo | | K | K |
| Lahti | Lahtis | Lh | | Traffic operating point | 130+170 | Riihimäki–Kouvola, Lahti–Heinola, Lahti–Mukkula, Lahti–Loviisan satama | Lahti | K | K | K |
| Laihia | Laihela | Lai | | Traffic operating point | 468+916 | Seinäjoki–Vaasa | Laihia | K | | K |
| Lakiala | | Lak | | Traffic operating point | 209+214 | Tampere–Seinäjoki | Ylöjärvi | K | | K |
| Lamminkoski | | Lmk | | Traffic operating point | 268+785 | Tampere–Seinäjoki | Parkano | K | | |
| Lamminniemi | | Lam | | Traffic operating point | 636+664 | Kajaani–Lamminniemi | Kajaani | | K | K |
| Lapinjärvi | Lappträsk | Lpj | | Traffic operating point | 185+432 | Lahti–Loviisan satama | Lapinjärvi | M | | K |
| Lapinlahti | | Lna | | Traffic operating point | 525+604 | Pieksämäki–Kontiomäki | Lapinlahti | K | | K |
| Lapinneva | | Lpn | | Switch on a track line | 415+618 | Niinisalo–Parkano–Kihniö | Parkano | | | K |
| Lappeenranta | Villmanstrand | Lr | | Traffic operating point | 287+726 | Kouvola–Joensuu, Lappeenranta–Mustolan satama | Lappeenranta | K | K | K |
| Lappila | | Laa | | Stopping point | 97+693 | Riihimäki–Kouvola | Kärkölä | | | |
| Lappohja | Lappvik | Lpo | | Traffic operating point | 189+639 | Karjaa–Hanko | Hanko | K | K | K |
| Lapua | Lappo | Lpa | | Traffic operating point | 441+094 | Seinäjoki–Oulu | Lapua | K | K | K |
| Larvakyö | | Lyö | | Traffic operating point | 333+057 | Tampere–Seinäjoki | Seinäjoki | K | | |
| Laukaa | | Lau | | Traffic operating point | 401+193 | Jyväskylä–Äänekoski | Laukaa | K | | |
| Laurila | | Lla | | Traffic operating point | 865+776 | Laurila–Kemijärvi, Oulu–Laurila, Laurila–Tornio-raja | Keminmaa | K | | K |
| Lauritsala | | Lrs | | Traffic operating point | 291+936 | Kouvola–Joensuu | Lappeenranta | K | K | K |
| Lautiosaari | | Li | | Traffic operating point | 863+064 | Lautiosaari–Eltjärvi, Oulu–Laurila | Kemi | K | | |
| Leikola | | Lkl | | Traffic operating point | 276+011 | Kouvola–Pieksämäki | Hirvensalmi | K | | |
| Lempäälä | | Lpä | | Traffic operating point | 165+928 | Riihimäki–Tampere | Lempäälä | K | | |
| Leppäkoski | | Lk | | Traffic operating point | 87+830 | Riihimäki–Tampere | Janakkala | K | | |
| Leppävaara | Alberga | Lpv | | Traffic operating point | 11+249 | Helsinki–Turku satama | Espoo | K | | K |
| Leteensuo | | Lts | | Traffic operating point | 123+554 | Riihimäki–Tampere | Hattula | K | | |
| Lieksa | | Lis | | Traffic operating point | 728+121 | Joensuu–Nurmes, Lieksa–Pankakoski | Lieksa | K | K | K |
| Lieksan teollisuuskylä | | Ltk | | Switch on a track line | 728+847 | Lieksa–Pankakoski | Lieksa | | K | K |

| Nimi | Toinen nimi | Lyhenne | Kaupallinen nimi | Tyyppi | Km Hki | Rataosuus | Kunta | Liikenteenohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|-----------------|--------------|-------------|-------------------|-------------------------|----------|---|--------------|------------------|---------------------------|------------------------|
| Namn | Annat namn | Förkortning | Kommersiellt namn | Typ | Km Hki | Banavsnitt | Kommun | Trafikledning | Privata spär-anläggningar | Möjlighet till växling |
| Name | Another name | Abbr. | Commercial name | Type | Km Hki | Section | Municipality | Traffic control | Private sidings | Shunting |
| Lielähti | | Llh | | Traffic operating point | 193+393 | Tampere–Seinäjoki, Lielähti–Kokemäki | Tampere | K | K | K |
| Lievestuore | | Lvt | | Traffic operating point | 402+191 | Jyväskylä–Pieksämäki | Laukaa | K | K | K |
| Liminka | Limingo | Lka | | Traffic operating point | 728+483 | Seinäjoki–Oulu | Liminka | K | | K |
| Lohiluoma | | Luo | | Switch on a track line | 463+619 | Seinäjoki–Kaskinen | Kurikka | | | |
| Lohja | Lojo | Lo | | Traffic operating point | 122+965 | Hyvinkää–Karjaa | Lohja | K | | K |
| Loimaa | | Lm | | Traffic operating point | 208+870 | Toijala–Turku | Loimaa | K | | K |
| Louhela | Klippsta | Loh | | Stopping point | 13+190 | Huopalahti–Vantaankoski | Vantaa | | | |
| Loukolampi | | Lol | | Traffic operating point | 360+013 | Kouvola–Pieksämäki | Pieksämäki | K | | |
| Loviisan satama | Lovisa hamn | Lvs | | Traffic operating point | 207+209 | Lahti–Loviisan satama | Loviisa | M | K | K |
| Luikonlahti | | Lui | | Traffic operating point | 557+061 | Siltinjärvi–Viinijärvi | Kaavi | K | K | K |
| Luoma | Bobäck | Lma | | Stopping point | 27+807 | Helsinki–Turku satama | Kirkkonummi | | | |
| Lusto | | Lus | | Stopping point | 509+170 | Savonlinna–Parikkala | Savonlinna | | | |
| Luumäki | | Lä | | Traffic operating point | 250+540 | Kouvola–Joensuu, Luumäki–Vainikkala-raja | Luumäki | K | K | K |
| Lähdemäki | | Läh | | Traffic operating point | 79+373 | Kerava–Hakosilta | Orimattila | K | | |
| Läkipohja | | Läp | | Traffic operating point | 256+024 | Tampere–Jyväskylä | Jämsä | K | | |
| Maanselkä | | Mlk | | Traffic operating point | 836+049 | Nurmes–Kontiomäki | Sotkamo | M | | K |
| Maaria | St Marie | Mri | | Traffic operating point | 262+070 | Toijala–Turku | Turku | K | | |
| Madesjärvi | | Md | | Traffic operating point | 291+821 | Tampere–Seinäjoki | Jalasjärvi | K | | K |
| Majajärvi | | Mjj | | Traffic operating point | 216+317 | Tampere–Seinäjoki | Ylöjärvi | K | | |
| Malmi | Malm | ML | | Traffic operating point | 10+900 | Helsinki–Riihimäki | Helsinki | K | | |
| Malminkartano | Malmgård | Mlo | | Stopping point | 10+730 | Huopalahti–Vantaankoski | Helsinki | | | |
| Mankala | | Mka | | Traffic operating point | 160+050 | Riihimäki–Kouvola | Iitti | K | | |
| Markkala | | Mrk | | Traffic operating point | 403+737 | Pieksämäki–Kontiomäki | Suonenjoki | K | | |
| Martinlaakso | Mårtensdal | Mrl | | Stopping point | 14+010 | Huopalahti–Vantaankoski | Vantaa | K | | |
| Masala | Masaby | Mas | | Stopping point | 29+561 | Helsinki–Turku satama | Kirkkonummi | | | |
| Matkaneva | | Mtv | | Traffic operating point | 562+059 | Seinäjoki–Oulu | Kokkola | K | | |
| Mattila | | Mat | | Traffic operating point | 159+906 | Riihimäki–Tampere | Lempäälä | K | | |
| Meltola | Mjölbolsta | Mel | | Switch on a track line | 149+862 | Hyvinkää–Karjaa | Raasepori | | K | |
| Metsäkansa | | Msä | | Switch on a track line | 155+811 | Toijala–Valkeakoski | Valkeakoski | | | K |
| Mikkeli | St Michel | Mi | | Traffic operating point | 305+165 | Kouvola–Pieksämäki | Mikkeli | K | K | K |
| Misi | | Mis | | Traffic operating point | 1021+255 | Laurila–Kemijärvi | Rovaniemi | M | | K |
| Mommila | | Mla | | Stopping point | 91+430 | Riihimäki–Kouvola | Hausjärvi | | | |
| Muhos | | Mh | | Traffic operating point | 788+424 | Oulu–Kontiomäki | Muhos | K | | K |
| Mukkula | | Muk | | Traffic operating point | 140+012 | Lahti–Mukkula | Lahti | | K | K |
| Murtomäki | | Mur | | Traffic operating point | 613+165 | Pieksämäki–Kontiomäki, Murtomäki–Talvivaara, Murtomäki–Otanmäki | Kajaani | K | | K |
| Mustio | Svartå | Mso | | Switch on a track line | 143+000 | Hyvinkää–Karjaa | Raasepori | | | K |
| Mustolan satama | | Mst | | Traffic operating point | 296+720 | Lappeenranta–Mustolan satama | Lappeenranta | | K | |
| Muukko | | Mko | | Traffic operating point | 297+112 | Kouvola–Joensuu | Lappeenranta | K | | |
| Muurame | | Muu | | Traffic operating point | 324+768 | Tampere–Jyväskylä | Muurame | K | | K |
| Muurola | | Mul | | Traffic operating point | 948+494 | Laurila–Kemijärvi | Rovaniemi | K | | K |
| Myllykangas | | Mys | | Traffic operating point | 815+693 | Oulu–Laurila | Ii | K | | |
| Myllykoski | | Mki | | Stopping point | 203+742 | Kouvola–Kotka | Kouvola | K | | |
| Myllymäki | | My | | Stopping point | 333+721 | Orivesi–Seinäjoki | Ahtari | | | K |
| Myllyoja | | Myl | | Traffic operating point | 161+727 | Lahti–Heinola | Heinola | K | K | K |
| Mynttilä | | Myt | | Traffic operating point | 270+889 | Kouvola–Pieksämäki, Mynttilä–Ristina | Mäntyharju | K | | |
| Mynämäki | | Myn | | Traffic operating point | 229+607 | Turku–Uusikaupunki | Mynämäki | K | | |
| Myrskylä | Mörskom | Myä | | Switch on a track line | 169+771 | Lahti–Loviisan satama | Lapinjärvi | | | K |

| Nimi | Toinen nimi | Lyhenne | Kaupallinen nimi | Tyyppi | Km Hki | Rataosuus | Kunta | Liikenteenohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|------------------|--------------|-------------|-------------------|--|---------|---|-----------------|------------------|---------------------------|------------------------|
| Namn | Annat namn | Förkortning | Kommersiellt namn | Typ | Km Hki | Banavsnitt | Kommun | Trafikledning | Privata spär-anläggningar | Möjlighet till växling |
| Name | Another name | Abbr. | Commercial name | Type | Km Hki | Section | Municipality | Traffic control | Private sidings | Shunting |
| Myyrmäki | Myrbacka | Myr | | Traffic operating point | 12+130 | Huopalahti–Vantaankoski | Vantaa | K | | |
| Mäkkylä | | Mäk | | Stopping point | 9+511 | Helsinki–Turku satama | Espoo | | | |
| Mäntsälä | | Mlä | | Traffic operating point | 59+210 | Kerava–Hakosilta | Mäntsälä | K | | |
| Mänttä | | Män | | Traffic operating point | 282+740 | Vilppula–Mänttä | Mänttä-Vilppula | | K | K |
| Mäntyharju | | Mr | | Traffic operating point | 262+680 | Kouvola–Pieksämäki | Mäntyharju | K | | K |
| Mäntyluoto | | Mn | | Traffic operating point | 342+020 | Pori–Mäntyluoto | Pori | K | K | K |
| Naantali | Nädendal | NnL | | Traffic operating point | 213+193 | Raisio–Naantali | Naantali | | K | K |
| Naarajärvi | | Nri | | Traffic operating point | 449+862 | Jyväskylä–Pieksämäki | Pieksämäki | K | | K |
| Nakkila | | Nal | | Traffic operating point | 308+091 | Kokemäki–Pori | Nakkila | K | | |
| Nastola | | Nsl | | Stopping point | 146+169 | Riihimäki–Kouvola | Nastola | | | |
| Niemenpää | | Nmp | | Traffic operating point | 923+605 | Tornio–Kolari | Tornio | K | | |
| Niinimaa | | Nii | | Switch on a track line | 383+155 | Orivesi–Seinäjoki | Alavus | | | |
| Niinimäki | | Nmä | | Traffic operating point | 172+534 | Riihimäki–Kouvola | Iitti | | | |
| Niinisalo | | Nns | | Traffic operating point | 386+215 | Niinisalo–Parkano–Kihniö | Kankaanpää | M | K | K |
| Niirala | | Nrl | | Traffic operating point | 555+846 | Niirala–raja–Säkäniemi | Tohmajärvi | M | K | K |
| Niirala–raja | | Nrlr | | Traffic operating point | 554+080 | Niirala–raja–Säkäniemi | Tohmajärvi | | | |
| Niittylahti | | Nth | | Traffic operating point | 613+475 | Kouvola–Joensuu | Joensuu | K | | |
| Nikkilä | Nickby | Nlä | | Stopping point | 39+176 | Kerava–Sköldvik | Sipoo | | | |
| Nivala | | Nvl | | Traffic operating point | 676+878 | Iisalmi–Ylivieska | Nivala | K | | K |
| Nokia | | Noa | | Traffic operating point | 204+004 | Lielähti–Kokemäki | Nokia | K | K | K |
| Nummela | | Nm | | Traffic operating point | 109+368 | Hyvinkää–Karjaa | Vihti | K | | K |
| Nuppulinna | | Nup | | Stopping point | 44+210 | Helsinki–Riihimäki | Tuusula | | | |
| Nurmes | | Nrm | | Traffic operating point | 784+420 | Nurmes–Kontiomäki, Joensuu–Nurmes | Nurmes | K | K | K |
| Närpiö | Närpes | När | | Switch on a track line | 518+255 | Seinäjoki–Kaskinen | Närpiö | | | |
| Ohenmäki | | Ohm | | Switch on a track line | 542+264 | Pieksämäki–Kontiomäki | Iisalmi | | | K |
| Olli | | Oli | | Switch on a track line | 45+734 | Kerava–Sköldvik, Olli–Porvoo | Porvoo | K | | |
| Onttola | | Ont | | Switch on a track line | 631+177 | Pieksämäki–Joensuu | Joensuu | | K | K |
| Oirimattila | | Om | | Switch on a track line | 150+407 | Lahti–Loviisan satama | Oirimattila | | | K |
| Orivesi | | Ov | | Traffic operating point | 228+276 | Tampere–Jyväskylä, Orivesi–Seinäjoki | Orivesi | K | | K |
| Orivesi keskusta | | Ovk | | Stopping point | 231+512 | Orivesi–Seinäjoki | Orivesi | | | |
| Otanmäki | | Otm | | Traffic operating point | 638+822 | Murto–Otanmäki | Kajaani | | K | K |
| Otava | | Ot | | Traffic operating point | 290+521 | Kouvola–Pieksämäki, Otava–Otavan satama | Mikkeli | K | | K |
| Otavan satama | | Ots | | Traffic operating point | 292+885 | Otava–Otavan satama | Mikkeli | | K | K |
| Oulainen | | Ou | | Traffic operating point | 657+850 | Seinäjoki–Oulu | Oulainen | K | K | K |
| OULU | | Oul | | Divided Traffic Operating Point | – | Seinäjoki–Oulu, Oulu–Kontiomäki, Oulu–Laurila | | M | | |
| Oulu Nokela | | Nok | | Part of a Traffic Operating Point (Oulu) | 750+030 | | Oulu | | K | K |
| Oulu Oritkari | | Ori | | Part of a Traffic Operating Point (Oulu) | 751+180 | | Oulu | | K | K |
| Oulu tavara | | Olt | | Part of a Traffic Operating Point (Oulu) | 751+360 | | Oulu | | K | K |
| Oulu asema | Uleåborg | Ol | Oulu | Part of a Traffic Operating Point (Oulu) | 752+778 | | Oulu | | | K |
| Oulu Tuira | | Tua | | Part of a Traffic Operating Point (Oulu) | 755+510 | | Oulu | | K | K |
| Paimio | Pemar | Po | | Traffic operating point | 171+885 | Helsinki–Turku satama | Paimio | K | | |
| Palopuro | | Plp | | Traffic operating point | 54+535 | Helsinki–Riihimäki | Hyvinkää | K | | |
| Paltamo | | Pto | | Traffic operating point | 901+579 | Oulu–Kontiomäki | Paltamo | K | | K |
| Pankakoski | | Pas | | Traffic operating point | 731+865 | Liekka–Pankakoski | Liekka | | K | K |

| Nimi | Toinen nimi | Lyhenne | Kaupallinen nimi | Tyyppi | Km Hki | Rataosuus | Kunta | Liikenteenohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|-----------------------------|--------------|-------------|-------------------|---|----------------|--|-------------------|------------------|---------------------------|------------------------|
| Namn | Annat namn | Förkortning | Kommersiellt namn | Typ | Km Hki | Banavsnitt | Kommun | Trafikledning | Privata spär-anläggningar | Möjlighet till växling |
| Name | Another name | Abbr. | Commercial name | Type | Km Hki | Section | Municipality | Traffic control | Private sidings | Shunting |
| Parikkala | | Par | | Traffic operating point | 387+302 | Kouvola-Joensuu, Savonlinna-Parikkala | Parikkala | K | | K |
| Parkano | | Pko | | Traffic operating point | 262+483 | Niinisalo-Parkano-Kihniö, Tampere-Seinäjoki | Parkano | K | K | K |
| Parola | | Prl | | Traffic operating point | 115+764 | Riihimäki-Tampere | Hattula | K | K | K |
| Pello | | Pel | | Traffic operating point | 1002+632 | Tornio-Kolari | Pello | K | K | |
| Peltosalmi | | Pmi | | Traffic operating point | 545+355 | Pieksämäki-Kontiomäki | Iisalmi | | | |
| Peräseinäjoki | | Psj | | Traffic operating point | 318+481 | Tampere-Seinäjoki | Seinäjoki | K | K | K |
| Pesiökylä | | Psk | | Traffic operating point | 732+752 | Kontiomäki-Ämmänsaari | Suomussalmi | M | | K |
| Petäjävesi | | Pvi | | Traffic operating point | 343+357 | Haapamäki-Jyväskylä | Petäjävesi | K | | K |
| PIEKSÄMÄKI | | Pie | | Divided Traffic Operating Point | - | Kouvola-Pieksämäki, Pieksämäki-Kontiomäki, Jyväskylä-Pieksämäki, Pieksämäki-Joensuu | Pieksämäki | M | | |
| <i>Pieksämäki asema</i> | | <i>Pm</i> | <i>Pieksämäki</i> | <i>Part of a Traffic Operating Point (Pieksämäki)</i> | <i>376+000</i> | | <i>Pieksämäki</i> | | <i>K</i> | <i>K</i> |
| <i>Pieksämäki Temu</i> | | <i>Tmu</i> | | <i>Part of a Traffic Operating Point (Pieksämäki)</i> | <i>377+340</i> | | <i>Pieksämäki</i> | | <i>K</i> | <i>K</i> |
| <i>Pieksämäki lajittelu</i> | | <i>Pmla</i> | | <i>Part of a Traffic Operating Point (Pieksämäki)</i> | <i>378+640</i> | | <i>Pieksämäki</i> | | <i>K</i> | <i>K</i> |
| <i>Pieksämäki tavara</i> | | <i>Pmt</i> | | <i>Part of a Traffic Operating Point (Pieksämäki)</i> | <i>379+960</i> | | <i>Pieksämäki</i> | | <i>K</i> | <i>K</i> |
| Pietarsaari | Jakobstad | Pts | | Traffic operating point | 528+780 | Pännäinen-Pietarsaari, Pietarsaari-Alholma | Pietarsaari | M | | K |
| Pihlajavesi | | Ph | | Traffic operating point | 312+500 | Orivesi-Seinäjoki | Keuruu | K | | K |
| Pihlupudas | | Pp | | Traffic operating point | 540+605 | Äänekoski-Haapajarvi | Pihlupudas | M | | K |
| Pikkiö | Pikis | Pik | | Traffic operating point | 182+785 | Helsinki-Turku satama | Kaarina | K | | K |
| Pikkarala | | Pkl | | Traffic operating point | 771+765 | Oulu-Kontiomäki | Oulu | K | K | |
| Pitäjänmäki | Sockenbacka | Pjm | | Stopping point | 8+474 | Helsinki-Turku satama | Helsinki | | | |
| Pohjankuru | Skuru | Pku | | Traffic operating point | 94+907 | Helsinki-Turku satama | Raasepori | K | K | K |
| Pohjois-Haaga | Norra Haga | Poh | | Stopping point | 8+050 | Huopalahti-Vantaankoski | Helsinki | | | |
| Pohjois-Louko | | Plu | | Traffic operating point | 329+329 | Tampere-Seinäjoki | Seinäjoki | K | | |
| Poikkeus | | Pkk | | Traffic operating point | 254+744 | Tampere-Seinäjoki | Parkano | K | | |
| Poiksilta | | Poi | | Traffic operating point | 416+728 | Kouvola-Joensuu | Kitee | | | K |
| Pori | Björneborg | Pri | | Traffic operating point | 322+278 | Pori-Ruosniemi, Pori-Mäntyluoto, Kokemäki-Pori | Pori | K | K | K |
| Porokylä | | Por | | Traffic operating point | 787+046 | Nurmes-Kontiomäki | Nurmes | | K | K |
| Porvoo | Borgå | Prv | | Traffic operating point | 62+287 | Olli-Porvoo | Porvoo | | | K |
| Puhos | | Pus | | Traffic operating point | 452+808 | Kouvola-Joensuu | Kitee | K | K | K |
| Puistola | Parkstad | Pla | | Stopping point | 14+050 | Helsinki-Riihimäki | Helsinki | | | |
| Pukimäki | Bocksbacka | Pmk | | Stopping point | 9+442 | Helsinki-Riihimäki | Helsinki | | | |
| Pulsa | | Pl | | Traffic operating point | 262+491 | Luumäki-Vainikkala-ralja | Lappeenranta | K | | K |
| Punkaharju | | Pun | | Traffic operating point | 515+111 | Savonlinna-Parikkala | Savonlinna | K | K | K |
| Pyhäkumpu | | Pyk | | Traffic operating point | 615+415 | Pyhäkumpu erkanemisvaihde- Pyhäkumpu | Pyhäjärvi | | K | |
| Pyhäkumpu erkanemisvaihde | | Pye | | Traffic operating point | 613+511 | Iisalmi-Ylivieska, Pyhäkumpu erkanemisvaihde- Pyhäkumpu | Pyhäjärvi | K | | |
| Pyhäsalmi | | Phä | | Traffic operating point | 615+934 | Iisalmi-Ylivieska | Pyhäjärvi | K | | K |
| Pännäinen | Bennäs | Pnä | | Traffic operating point | 518+604 | Pännäinen-Pietarsaari, Seinäjoki-Oulu | Pedersöre | K | | K |
| Raahe | Brahestad | Rhe | | Traffic operating point | 726+726 | Raahe-Rautaruukki, Tuomioja-Raahe | Raahe | K | K | K |
| Raippo | | Rpo | | Traffic operating point | 270+052 | Luumäki-Vainikkala-ralja | Lappeenranta | K | K | K |
| Raisio | Reso | Rai | | Traffic operating point | 207+829 | Turku-Uusikaupunki, Raisio-Naantali | Raisio | K | K | K |
| Rajamäki | | Rm | | Traffic operating point | 72+267 | Hyvinkää-Karjaa | Nurmijärvi | | | K |
| Rajaperkiö | | Rjp | | Traffic operating point | 448+396 | Seinäjoki-Oulu | Lapua | K | | |
| Rantasalmi | | Rmi | | Traffic operating point | 445+165 | Huutokoski-Savonlinna | Rantasalmi | K | | K |
| Rasinsuo | | Ras | | Traffic operating point | 258+510 | Kouvola-Joensuu | Luumäki | K | | |

| Nimi | Toinen nimi | Lyhenne | Kaupallinen nimi | Tyyppi | Km Hki | Rataosuus | Kunta | Liikenteenohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|----------------------------|--------------|-------------|-------------------|---|---------|--|-------------------|------------------|---------------------------|------------------------|
| Namn | Annat namn | Förkortning | Kommersiellt namn | Typ | Km Hki | Banavsnitt | Kommun | Trafikledning | Privata spär-anläggningar | Möjlighet till växling |
| Name | Another name | Abbr. | Commercial name | Type | Km Hki | Section | Municipality | Traffic control | Private sidings | Shunting |
| Ratikylä | Raumo | Rlä | | Traffic operating point | 284+344 | Tampere–Seinäjoki | Kihniö | K | | K |
| Rauha | | Rah | | Traffic operating point | 318+490 | Kouvola–Joensuu | Lappeenranta | K | | K |
| Rauhalahdi | | Rhl | | Traffic operating point | 380+510 | Jyväskylä–Pieksämäki | Jyväskylä | | K | K |
| Rauma | | Rma | | Traffic operating point | 331+659 | Kokemäki–Rauma | Rauma | K | K | K |
| Raunio | | Rio | | Traffic operating point | 464+845 | Seinäjoki–Oulu | Kauhava | K | | |
| Rautaruukki | | Rat | | Traffic operating point | 730+050 | Raahe–Rautaruukki | Raahe | | K | K |
| Rautjärvi | | Rjä | | Traffic operating point | 345+788 | Kouvola–Joensuu | Rautjärvi | K | | |
| Rautpohja | | Rph | | Traffic operating point | 372+829 | Haapamäki–Jyväskylä | Jyväskylä | | K | |
| Rekola | Räckhals | Rkl | | Stopping point | 20+615 | Helsinki–Riihimäki | Vantaa | | | |
| Retretti | | Ree | | Stopping point | 507+500 | Savonlinna–Parikkala | Savonlinna | | | |
| RIIHIMÄKI | | Rii | | Divided Traffic Operating Point | – | Helsinki–Riihimäki, Riihimäki–Kouvola, Riihimäki–Tampere | | K | | |
| <i>Riihimäki Arolampi</i> | | Arp | | <i>Part of a Traffic Operating Point (Riihimäki)</i> | 66+600 | | <i>Hausjärvi</i> | | | |
| <i>Riihimäki tavara</i> | | Rit | | <i>Part of a Traffic Operating Point (Riihimäki)</i> | 68+773 | | <i>Riihimäki</i> | | | K |
| <i>Riihimäki lajittelu</i> | | Rila | | <i>Part of a Traffic Operating Point (Riihimäki)</i> | 70+068 | | <i>Riihimäki</i> | | | K |
| <i>Riihimäki asema</i> | | Ri | | <i>Part of a Traffic Operating Point (Riihimäki)</i> | 71+410 | | <i>Riihimäki</i> | | K | K |
| Rijärvi | Sandö | Rjr | Riihimäki | Traffic operating point | 502+567 | Seinäjoki–Oulu | Uusikaarlepyy | K | | |
| Riippa | | Rpa | | Traffic operating point | 578+065 | Seinäjoki–Oulu | Kokkola | K | | |
| Ristiina | | Rst | | Traffic operating point | 291+162 | Mynttilä–Ristiina | Mikkeli | M | K | K |
| Ristijärvi | | Rjv | | Traffic operating point | 676+804 | Kontiomäki–Ämmänsaari | Ristijärvi | K | | |
| Rovaniemi | | Roi | | Traffic operating point | 971+775 | Laurila–Kemijärvi | Rovaniemi | K | K | K |
| Ruha | | Rha | | Traffic operating point | 431+132 | Seinäjoki–Oulu | Lapua | K | | |
| Runni | | Rnn | | Stopping point | 568+518 | Iisalmi–Ylivieska | Iisalmi | | | |
| Ruosniemi | | Rsn | | Traffic operating point | 330+936 | Pori–Ruosniemi | Pori | | K | |
| Ruukki | | Rki | | Traffic operating point | 705+228 | Seinäjoki–Oulu | Siikajoki | K | | K |
| Ryttylä | | Ry | | Traffic operating point | 80+770 | Riihimäki–Tampere | Hausjärvi | K | K | K |
| Röyttä | | Röy | | Traffic operating point | 893+917 | Tornio–Röyttä | Tornio | | K | K |
| Saakoski | | Saa | | Traffic operating point | 305+373 | Tampere–Jyväskylä | Jyväskylä | K | | |
| Saari | | Sr | | Traffic operating point | 405+246 | Kouvola–Joensuu | Parikkala | K | | |
| Saarijärvi | | Srj | | Traffic operating point | 452+723 | Äänekoski–Haapajärvi | Saarijärvi | M | | K |
| Salminen | | Sln | | Traffic operating point | 426+718 | Pieksämäki–Kontiomäki, Pieksämäki–Kontiomäki | Suonenjoki | K | | K |
| Salo | | Slo | | Traffic operating point | 143+981 | Helsinki–Turku satama | Salo | K | | K |
| Sammalisto | | Sam | | Traffic operating point | 74+487 | Riihimäki–Tampere | Riihimäki | K | | |
| Santala | | Sta | | Stopping point | 196+908 | Karjaa–Hanko | Hanko | | | |
| Saunamäki | | Smä | | Traffic operating point | 180+534 | Riihimäki–Kouvola | Iitti | | | |
| Savio | | Sav | | Stopping point | 26+265 | Helsinki–Riihimäki | Kerava | | | |
| SAVONLINNA | | Svl | | Divided Traffic Operating Point | – | Savonlinna–Parikkala, Huutokoski–Savonlinna | | | | |
| <i>Savonlinna asema</i> | Nyslott | Sl | | <i>Part of a Traffic Operating Point (Savonlinna)</i> | 482+797 | | <i>Savonlinna</i> | K | | |
| <i>Pääskylahdi</i> | | Pky | | <i>Part of a Traffic Operating Point (Savonlinna)</i> | 484+913 | | <i>Savonlinna</i> | K | | K |
| SEINÄJOKI | | Sei | | Divided Traffic Operating Point | – | Tampere–Seinäjoki, Seinäjoki–Oulu, Orivesi–Seinäjoki, Seinäjoki–Vaasa, Seinäjoki–Kaskinen | | M | | |
| <i>Seinäjoki tavara</i> | | Skt | | <i>Part of a Traffic Operating Point (Seinäjoki)</i> | 416+580 | | <i>Seinäjoki</i> | | K | K |

| Nimi | Toinen nimi | Lyhenne | Kaupallinen nimi | Tyyppi | Km Hki | Rataosuus | Kunta | Liikenteenohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|------------------|--------------|-------------|-------------------|---|----------|---|--------------|------------------|---------------------------|------------------------|
| Namn | Annat namn | Förkortning | Kommersiellt namn | Typ | Km Hki | Banavsnitt | Kommun | Trafikledning | Privata spår-anläggningar | Möjlighet till växling |
| Name | Another name | Abbr. | Commercial name | Type | Km Hki | Section | Municipality | Traffic control | Private sidings | Shunting |
| Seinäjoki asema | | Sk | Seinäjoki | Part of a Traffic Operating Point (Seinäjoki) | 418+001 | | Seinäjoki | | K | K |
| Selänpää | | Spä | | Traffic operating point | 209+869 | Kouvola–Pieksämäki | Kouvola | K | | |
| Sieppijärvi | | Spj | | Traffic operating point | 1045+904 | Tornio–Kolari | Kolari | K | | K |
| Sievi | | Svi | | Traffic operating point | 613+592 | Seinäjoki–Oulu | Sievi | K | | K |
| Siikamäki | | Skä | | Traffic operating point | 389+747 | Pieksämäki–Joensuu | Pieksämäki | K | | |
| Siilinjärvi | | Sij | | Traffic operating point | 489+718 | Siilinjärvi–Viinijärvi, Pieksämäki–Kontiomäki | Siilinjärvi | K | K | K |
| Simo | | Sim | | Traffic operating point | 833+715 | Oulu–Laurila | Simo | K | | K |
| Simpele | | Spl | | Traffic operating point | 368+317 | Kouvola–Joensuu | Rautjärvi | K | K | K |
| Sipilä | | Sip | | Traffic operating point | 68+697 | Kerava–Hakosilta, Kerava–Hakosilta | Mäntsälä | K | | |
| Sisäntö | | Stö | | Traffic operating point | 235+602 | Tampere–Seinäjoki | Ikaalinen | K | | |
| Siuntio | Sjundeå | Sti | | Traffic operating point | 51+285 | Helsinki–Turku satama | Siuntio | K | | |
| Siuro | | Siu | | Traffic operating point | 213+355 | Lielähti–Kokemäki | Nokia | K | | K |
| Skogby | | Sgy | | Stopping point | 184+790 | Karjaa–Hanko | Raasepori | | | |
| Sköldvik | Kilpilahti | Sld | | Traffic operating point | 56+360 | Kerava–Sköldvik | Porvoo | M | K | K |
| Soinlahti | | Soa | | Traffic operating point | 559+651 | Pieksämäki–Kontiomäki | Iisalmi | | K | K |
| Sorsasalo | | Sor | | Traffic operating point | 473+754 | Pieksämäki–Kontiomäki | Kuopio | | K | |
| Sukeva | | Skv | | Traffic operating point | 589+222 | Pieksämäki–Kontiomäki | Sonkajärvi | K | | K |
| Suolahti | | Suo | | Traffic operating point | 417+796 | Jyväskylä–Äänekoski | Äänekoski | K | K | K |
| Suonenjoki | | Snj | | Traffic operating point | 413+842 | Pieksämäki–Kontiomäki, Suonenjoki–Iisvesi | Suonenjoki | K | | K |
| Suoniemi | | Snm | | Traffic operating point | 220+655 | Lielähti–Kokemäki | Nokia | K | | |
| Syrjä | | Syr | | Traffic operating point | 452+865 | Pieksämäki–Joensuu | Heinävesi | | | K |
| Syrjämäki | | Ski | | Traffic operating point | 341+621 | Tampere–Seinäjoki | Seinäjoki | K | | |
| Sysmäjärvi | | Smj | | Traffic operating point | 669+601 | Sysmäjärvi–Vuonos, Siilinjärvi–Viinijärvi | Outokumpu | K | K | K |
| Säkäniemi | | Sä | | Traffic operating point | 480+242 | Niirala–raja–Säkäniemi, Kouvola–Joensuu | Tohmajärvi | K | | |
| Sänkimäki | | Skm | | Traffic operating point | 504+505 | Siilinjärvi–Viinijärvi | Kuopio | | | K |
| Sääksjärvi | | Sj | | Traffic operating point | 177+734 | Riihimäki–Tampere | Tampere | K | | |
| Taavetti | | Ta | | Traffic operating point | 238+589 | Kouvola–Joensuu | Luumäki | K | K | K |
| Tahkoluoto | | Tko | | Traffic operating point | 350+750 | Pori–Mäntyluoto | Pori | | K | K |
| Taipale | | Te | | Traffic operating point | 537+605 | Pieksämäki–Kontiomäki | Iisalmi | K | | |
| Talviainen | | Tv | | Traffic operating point | 247+245 | Tampere–Jyväskylä | Orivesi | K | | K |
| Talvivaara | | Tlv | | Traffic operating point | 637+700 | Murtomäki–Talvivaara | | | | |
| Tammisaari | Ekenäs | Tms | | Stopping point | 174+056 | Karjaa–Hanko | Raasepori | | | |
| TAMPERE | | Tre | | Divided Traffic Operating Point | – | Riihimäki–Tampere, Tampere–Seinäjoki, Tampere–Jyväskylä | | M | | |
| Tampere tavara | | Tpet | | Part of a Traffic Operating Point | 184+100 | | Tampere | | K | K |
| Tampere Viinikka | | Vka | | Part of a Traffic Operating Point | 185+400 | | Tampere | | K | K |
| Tampere asema | Tammerfors | Tpe | Tampere asema | Part of a Traffic Operating Point | 187+389 | | Tampere | | | K |
| Tampere | | Jvs | | Part of a Traffic Operating Point | 187+814 | | Tampere | | | |
| Järvensivu | | Tna | | Stopping point | 12+610 | Helsinki–Riihimäki | Helsinki | | | |
| Tapanila | Mosabacka | Tap | | Traffic operating point | 270+405 | Kouvola–Joensuu | Lappeenranta | K | | |
| Tapavainola | | Tsl | | Stopping point | 228+854 | Kouvola–Kotka | Kotka | | | |
| Tavastila | | Tk | | Stopping point | 460+156 | Seinäjoki–Vaasa | Isokyrö | | | |
| Tervajoki | | Trv | | Traffic operating point | 900+521 | Laurila–Kemijärvi | Tervola | K | | K |
| Tervola | | Tuv | | Traffic operating point | 497+474 | Seinäjoki–Kaskinen | Teuva | M | | K |
| Teuva | Östermark | Tkk | | Traffic operating point | 592+461 | Kouvola–Joensuu | Tohmajärvi | K | | |
| Tikkala | | Tkp | | Traffic operating point | 720+645 | Seinäjoki–Oulu | Liminka | K | | |

| Nimi | Toinen nimi | Lyhenne | Kaupallinen nimi | Tyyppi | Km Hki | Rataosuus | Kunta | Liikenteenohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|-----------------|----------------|-------------|---------------------------|---|---------|--|--------------|------------------|---------------------------|------------------------|
| Namn | Annat namn | Förkortning | Kommersiellt namn | Typ | Km Hki | Banavsnitt | Kommun | Trafikledning | Privata spär-anläggningar | Möjlighet till växling |
| Name | Another name | Abbr. | Commercial name | Type | Km Hki | Section | Municipality | Traffic control | Private sidings | Shunting |
| TIKKURILA | | Tik | | Divided Traffic Operating Point | | Helsinki-Riihimäki | | | | |
| Havukoski | | Hvk | | Part of a Traffic Operating Point (Tikkurila) | 17+725 | | Vantaa | K | | |
| Hiekkaharju | Sandkulla | Hkh | | Part of a Traffic Operating Point (Tikkurila) | 17+109 | | Vantaa | | | |
| Tikkurila asema | Dickursby | Tkl | | Part of a Traffic Operating Point (Tikkurila) | 15+861 | | Vantaa | K | | K |
| Tohmajärvi | | Toh | | Traffic operating point | 571+752 | Niirala-raja-Säkäniemi | Tohmajärvi | K | K | K |
| Toijala | | TL | | Traffic operating point | 147+339 | Toijala-Turku, Riihimäki-Tampere, Toijala-Valkeakoski | Akaa | K | K | K |
| Toivala | | Toi | | Traffic operating point | 479+162 | Pieksämäki-Kontiomäki | Siilinjärvi | K | | K |
| Tolsa | Tolls | Tol | | Stopping point | 35+634 | Helsinki-Turku satama | Kirkkonummi | | | |
| Tommola | | Tom | | Traffic operating point | 117+197 | Riihimäki-Kouvola | Hollola | K | | |
| Torkkeli | | Trk | | Traffic operating point | 240+154 | Tampere-Jyväskylä | Orivesi | K | | |
| TORNIO | | Trn | | Divided Traffic Operating Point | – | Tornio-Röyttä, Tornio-Kolari, Laurila-Tornio-raja | | K | | |
| Tornio asema | Torneå | Tor | Tornio | Part of a Traffic Operating Point (Tornio) | 884+656 | | Tornio | K | K | K |
| Tornio-raja | Torneå gränsen | Trr | | Part of a Traffic Operating Point (Tornio) | 887+190 | | Tornio | | | |
| Tornio-Itäinen | Torneå Östra | Tri | | Stopping point | 883+307 | Laurila-Tornio-raja | Tornio | | | |
| Tuomarila | Domsby | Trl | | Stopping point | 19+022 | Helsinki-Turku satama | Espoo | | | |
| Tuomioja | | Tja | | Part of a Traffic Operating Point | 698+504 | Seinäjoki-Oulu, Tuomioja-Raahe | Siikajoki | K | | K |
| Turenki | | Tu | | Part of a Traffic Operating Point | 93+771 | Riihimäki-Tampere | Janakkala | K | K | K |
| TURKU | | Tur | | Divided Traffic Operating Point | – | Helsinki-Turku satama, Toijala-Turku, Turku-Uusikaupunki | Turku | K | | |
| Kupittaa | Kuppis | Kut | | Part of a Traffic Operating Point (Turku) | 196+372 | | Turku | | | |
| Turku asema | Åbo | Tku | Turku päärautatieasema | Part of a Traffic Operating Point (Turku) | 199+674 | | Turku | | K | K |
| Turku tavara | | Tkut | | Part of a Traffic Operating Point (Turku) | 200+460 | | Turku | | K | K |
| Turku satama | Åbo hamn | Tus | | Part of a Traffic Operating Point (Turku) | 202+510 | | Turku | | K | |
| Tuupovaara | | Tpv | | Traffic operating point | 668+672 | Joensuu-Ilomantsi | Joensuu | | | K |
| Tuuri | | Tuu | | Stopping point | 366+962 | Orivesi-Seinäjoki | Alavus | | | K |
| Törmä | | Tör | | Traffic operating point | 878+075 | Laurila-Kemijärvi | Keminmaa | K | | |
| Törölä | | Trä | | Traffic operating point | 264+972 | Kouvola-Joensuu | Lappeenranta | K | | |
| Uimaharju | | Uim | | Traffic operating point | 674+451 | Joensuu-Nurmes | Joensuu | K | K | K |
| Urkala | | Ur | | Traffic operating point | 165+588 | Toijala-Turku | Urkala | K | | K |
| Utajärvi | | Uti | | Traffic operating point | 810+502 | Oulu-Kontiomäki | Utajärvi | K | | K |
| Utti | | Uti | | Switch on a track line | 204+085 | Kouvola-Joensuu | Kouvola | | | K |
| Uusikaupunki | Nystad | Ukp | | Traffic operating point | 264+795 | Uusikaupunki-Hangonsaari, Turku-Uusikaupunki | Uusikaupunki | K | K | K |
| Uusikylä | | Ukä | | Traffic operating point | 150+722 | Riihimäki-Kouvola | Nastola | K | | K |
| Vaajakoski | | Vko | | Traffic operating point | 384+866 | Jyväskylä-Pieksämäki | Jyväskylä | K | | K |
| Vaala | | Vaa | | Traffic operating point | 844+671 | Oulu-Kontiomäki | Vaala | K | | K |
| Vaarala | | Vra | | Switch on a track line | 981+481 | Laurila-Kemijärvi | Rovaniemi | | | K |
| Vaasa | Vasa | Vs | | Traffic operating point | 492+588 | Seinäjoki-Vaasa, Vaasa-Vaskiluoto | Vaasa | K | K | K |
| Vahojärvi | | Vjr | | Traffic operating point | 244+926 | Tampere-Seinäjoki | Parkano | K | | |
| VAINIKKALA | | Vai | | Divided Traffic Operating Point | – | Luumäki-Vainikkala-raja | | M | | |

| Nimi | Toinen nimi | Lyhenne | Kaupallinen nimi | Tyyppi | Km Hki | Rataosuus | Kunta | Liikenteenohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|-------------------------|--------------|-------------|-------------------|--|---------|--|-----------------|------------------|---------------------------|------------------------|
| Namn | Annat namn | Förkortning | Kommersiellt namn | Typ | Km Hki | Banavsnitt | Kommun | Trafikledning | Privata spår-anläggningar | Möjlighet till växling |
| Name | Another name | Abbr. | Commercial name | Type | Km Hki | Section | Municipality | Traffic control | Private sidings | Shunting |
| Vainikkala tavara | | Vnat | | Part of a Traffic Operating Point (Vainikkala) | 281+700 | | Lappeenranta | | K | K |
| Vainikkala asema | | Vna | Vainikkala | Part of a Traffic Operating Point (Vainikkala) | 282+784 | | Lappeenranta | | K | K |
| Vainikkala-raja | | Vnar | | Traffic operating point | 284+862 | | Lappeenranta | | | |
| Valimo | Gjuteriet | Vmo | | Stopping point | 7+480 | Helsinki-Turku satama | Helsinki | | | |
| Valkeakoski | | Vi | | Traffic operating point | 164+952 | Toijala-Valkeakoski | Valkeakoski | M | K | K |
| Valkeasu | | Vso | | Switch on a track line | 583+976 | Niirala-raja-Säkäniemi | Tohmajärvi | | | K |
| Valtimo | | Vlm | | Traffic operating point | 808+636 | Nurmes-Kontiomäki | Valtimo | M | | K |
| Vammala | | Vma | | Traffic operating point | 245+885 | Lielähti-Kokemäki | Sastamala | K | | K |
| Vanattara | | Vtr | | Traffic operating point | 172+340 | Riihimäki-Tampere | Lempäälä | K | | |
| Vantaankoski | Vandaforsen | Vks | | Traffic operating point | 14+907 | Huopalahti-Vantaankoski | Vantaa | K | | |
| Varkaus | | Var | | Traffic operating point | 424+685 | Pieksämäki-Joensuu, Varkaus-Kommila | Varkaus | K | K | K |
| Vartius | | Vus | | Traffic operating point | 753+755 | Kontiomäki-Vartius-raja | Kuhmo | M | | K |
| Vartius-raja | | Vur | | Traffic operating point | 755+856 | Kontiomäki-Vartius-raja | Kuhmo | | | |
| Vasikkahaka | | Vkh | | Traffic operating point | 31+175 | Helsinki-Turku satama | Kirkkonummi | K | | |
| Vaskiluoto | Vasklot | Vsk | | Traffic operating point | 496+463 | Vaasa-Vaskiluoto | Vaasa | | K | K |
| Venetmäki | | Vki | | Traffic operating point | 433+164 | Jyväskylä-Pieksämäki | Pieksämäki | K | | |
| Vesanka | | Vn | | Traffic operating point | 364+469 | Haapamäki-Jyväskylä | Jyväskylä | K | | |
| Vieki | | Vk | | Switch on a track line | 753+979 | Joensuu-Nurmes | Lieksa | | | K |
| Vierumäki | | Vrm | | Switch on a track line | 153+801 | Lahti-Heinola | Heinola | | | K |
| Vihanti | | Vti | | Traffic operating point | 684+573 | Seinäjoki-Oulu | Raahe | K | K | K |
| Vihtari | | Vih | | Traffic operating point | 489+889 | Pieksämäki-Joensuu | Heinävesi | K | | K |
| Viala | | Via | | Traffic operating point | 154+288 | Riihimäki-Tampere | Akaa | K | | K |
| Viinijärvi | | Vnj | | Traffic operating point | 656+569 | Siilinjärvi-Viinijärvi, Pieksämäki-Joensuu | Liperi | K | | K |
| Villähde | | Vlh | | Traffic operating point | 140+442 | Riihimäki-Kouvola | Nastola | K | | |
| Vilppula | | Vlp | | Traffic operating point | 274+760 | Orivesi-Seinäjoki, Vilppula-Mänttä | Mänttä-Vilppula | K | K | K |
| Vinnilä | | Vin | | Traffic operating point | 131+243 | Riihimäki-Tampere | Hämeenlinna | K | | |
| Voltti | | Vt | | Traffic operating point | 479+402 | Seinäjoki-Oulu | Kauhava | K | | K |
| Vuohijärvi | | Vhj | | Traffic operating point | 221+308 | Kouvola-Pieksämäki | Kouvola | K | | K |
| Vuojoki | | Vjo | | Traffic operating point | 318+501 | Kokemäki-Rauma | Eurajoki | K | | |
| Vuokatti | | Vkt | | Traffic operating point | 868+838 | Nurmes-Kontiomäki, Vuokatti-Lahnaslampi | Sotkamo | M | K | K |
| Vuonilahti | | Vsl | | Traffic operating point | 705+240 | Joensuu-Nurmes | Lieksa | K | | |
| Vuonos | | Vns | | Traffic operating point | 588+808 | Sysmäjärvi-Vuonos | Outokumpu | | | K |
| Vuorten-Vuori | | Vv | | Switch on a track line | 576+687 | Äänekoski-Haapajärvi | Haapajärvi | | | |
| Vuosaari | | Vsa | | Traffic operating point | 50+184 | Kerava-Vuosaari | Helsinki | K | K | K |
| YKSPIHLAJA | | Yks | | Divided Traffic Operating Point | - | Kokkola-Ykspihlaja | | | | |
| Ykspihlaja tavara | | Ykst | | Part of a Traffic Operating Point (Ykspihlaja) | 553+900 | | Kokkola | | K | K |
| Ykspihlaja väitratapiha | | Yksv | | Part of a Traffic Operating Point (Ykspihlaja) | 555+511 | | Kokkola | | K | K |
| Ylistaro | | Yst | | Stopping point | 439+558 | Seinäjoki-Vaasa | Seinäjoki | | | |
| Ylitornio | | Ytr | | Stopping point | 946+139 | Tornio-Kolari | Ylitornio | | | |
| Ylivalli | | Ytv | | Traffic operating point | 302+016 | Tampere-Seinäjoki | Jalasjärvi | K | K | K |
| Ylivieska | | Yv | | Traffic operating point | 630+343 | Iisalmi-Ylivieska, Seinäjoki-Oulu | Ylivieska | M | K | K |
| Yläkoski | | Ylk | | Switch on a track line | 416+849 | Suonenjoki-Iisvesi | Suonenjoki | | K | K |
| Ylämylly | | Yly | | Traffic operating point | 639+019 | Pieksämäki-Joensuu | Liperi | K | | K |
| Ylöjärvi | | Ylö | | Traffic operating point | 200+753 | Tampere-Seinäjoki | Ylöjärvi | K | | K |

| Nimi | Toinen nimi | Lyhenne | Kaupallinen nimi | Tyyppi | Km Hki | Rataosuus | Kunta | Liikenteenohjaus | Yksityisraiteita | Vaihtotyö- mahdollisuus |
|-------------|--------------|-------------|-------------------|-------------------------|---------|---|--------------|------------------|-------------------------------|----------------------------|
| Namn | Annat namn | Förkortning | Kommersiellt namn | Typ | Km Hki | Banavsnitt | Kommun | Trafikledning | Privata spår- anläggningar | Möjlighet till växlning |
| Name | Another name | Abbr. | Commercial name | Type | Km Hki | Section | Municipality | Traffic control | Private sidings | Shunting |
| Ypykkävaara | Etseri | Ypy | | Traffic operating point | 729+780 | Kontiomäki-Vartius-raja | Kuhmo | K | | K |
| Äetsä | | Äs | | Traffic operating point | 258+280 | Lielahdi-Kokemäki | Sastamala | K | | K |
| Ähtäri | | Äht | | Traffic operating point | 346+067 | Orivesi-Seinäjoki | Ähtäri | K | | K |
| Ämmänsaari | | Äm | | Traffic operating point | 750+448 | Kontiomäki-Ämmänsaari | Suomussalmi | M | | K |
| Äänekoski | | Äki | | Traffic operating point | 424+515 | Jyväskylä-Äänekoski, Äänekoski-Haapajärvi | Äänekoski | K | K | K |

[illegible]

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri-korkeus | Laituriraitteiden lukumäärä | Mitoittava raidepituus (tavara-liikenne) | Sähkö-virran saanti | Sivulaituri, suurin pituus | Pääty-laituri | Kuormaus-kenttä | Nosturi | Polttoaine | Henkilö-liiken-nettä | Tavara-liikennettä | Kääntöpöytiä |
|------------------------------|----------------------------|---------------------------|------------------|---------------------------------|--|---------------------|------------------------------|----------------------------|------------------------|----------|------------|----------------------|--------------------|--------------|
| Namn | Kortaste plattform-längden | Längsta plattform-längden | Plattform-höjden | Antal spår med plattform | Dimensionerande spårlängd (godstrafik) | Tillgång på elström | Sidoplattform | Plattform i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person-traffic | Godstrafik | Vändskivor |
| Name | Min. platform length | Max. platform length | Platform height | Number of tracks with platforms | Design train length (freight traffic) | Power supply | Side loading platform length | End loading platform | Loading site | Crane | Fuel | Passenger traffic | Freight traffic | Turntables |
| | [m] | [m] | [mm] | | [m] | [400 V, A] | [m] | | | [t] | | | | |
| Haukipudas | | | | 0 | 833 | — | 11 | — | K | — | — | — | — | — |
| Haukivuori | 199 | 200 | 265 | 2 | 894 | — | — | — | K | — | — | H | T | — |
| HAUSJÄRVI | | | | | | | | | | | | | | — |
| <i>Hausjärvi tavara</i> | | | | 0 | 656 | — | — | — | K | Y | — | — | — | — |
| <i>Oitti</i> | 102 | 102 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Haviseva | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Havukoski | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Heikkilä | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Heinola | | (107) | (265) | (1) | 950 | — | 15 | — | K | — | — | — | T | — |
| Heinoo | | | | 0 | 734 | — | — | — | — | — | — | — | — | — |
| Heinävaara | | | | 0 | — | — | — | — | K | — | — | — | T | — |
| Heinävesi | 100 | 206 | 265 | 2 | 570 | — | 9 | — | K | — | — | H | T | — |
| HELSINKI | | | | | | | | | | | | | | |
| <i>Helsinki asema</i> | 265 | 477 | 550 | 19 | 455 | — | — | — | — | — | — | H | — | — |
| <i>Pasila asema</i> | 319 | 432 | 550 | 10 | — | — | — | — | — | — | — | H | — | 22 |
| <i>Pasila autojuna-asema</i> | 450 | 450 | 550 | 2 | — | 63 A | — | K | — | — | — | H | — | — |
| <i>Ilmala asema</i> | 270 | 270 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| <i>Helsinki Kivihaka</i> | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| <i>Pasila tavara</i> | | | | 0 | 727 | 63 A | 230 | K | K Y | Y | — | — | T | — |
| <i>Ilmala ratapiha</i> | | | | 0 | — | 1500 V, 63 A | 29 | — | — | — | Y | — | — | — |
| <i>Käpylä</i> | (278) | 336 | 550 (265) | 2 (2) | 141 | — | — | — | — | — | — | H | — | — |
| <i>Oulunkylä</i> | 266 | 266 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Herrala | 110 | 110 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Hiirola | | | | 0 | 760 | — | — | — | — | — | — | — | — | — |
| Hikiä | 120 | 120 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Hillosensalmi | | (165) | (550) | (1) | 800 | — | — | — | — | — | — | — | — | — |
| Hinthaara | (55) | (65) | (265) | (3) | — | — | — | — | — | — | — | — | — | — |
| Hirvineva | | | | 0 | 753 | — | — | — | — | — | — | — | — | — |
| Humppila | 249 | 430 | 550 | 3 | 756 | 25 A | 29 | — | Y | — | — | H | T | — |
| Huopalahti | 270 | 270 | 550 | 4 | 287 | — | — | — | — | — | — | H | — | — |
| Huutokoski | | | | 0 | 659 | — | — | — | — | — | — | — | — | — |
| Hyrynsalmi | | (100) | (265) | (1) | 732 | 25 A | 12 | — | K | — | — | — | T | — |
| Hyvinkää | 104 | 332 | 550 (265) | 3 (1) | 814 | 25 A | 20 | — | — | — | — | H | T | 20 |
| Hämeenlinna | 257 | 450 | 550 | 3 | 1038 | 25 A | 34 | K | K | — | — | H | T | — |
| Härmä | | - | | 0 | 808 | — | — | — | K | — | — | — | T | — |
| Höljää | | 92 | 265 | 1 | — | — | — | — | K Y | — | — | H | T | — |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri-korkeus | Laituriraitteiden lukumäärä | Mitoittava raidepituus (tavara-liikenne) | Sähkö-virran saanti | Sivulaituri, suurin pituus | Pääty-laituri | Kuormaus-kenttä | Nosturi | Polttoaine | Henkilö-liiken-nettä | Tavara-liikennettä | Kääntöpöytiä |
|----------------------------|----------------------------|---------------------------|------------------|---------------------------------|--|---------------------|------------------------------|----------------------------|------------------------|----------|------------|----------------------|--------------------|--------------|
| Namn | Kortaste plattform-längden | Längsta plattform-längden | Plattform-höjden | Antal spår med plattform | Dimensionerande spårlängd (godstrafik) | Tillgång på elström | Sidoplattform | Plattform i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person-traffic | Godstrafik | Vändskivor |
| Name | Min. platform length | Max. platform length | Platform height | Number of tracks with platforms | Design train length (freight traffic) | Power supply | Side loading platform length | End loading platform | Loading site | Crane | Fuel | Passenger traffic | Freight traffic | Turntables |
| | [m] | [m] | [mm] | | [m] | [400 V, A] | [m] | | | [t] | | | | |
| Ii | | (92) | (265) | (1) | 687 | — | — | — | K | — | — | — | — | — |
| Iisalmen teollisuusraiteet | | | | 0 | — | — | — | — | Y | — | — | — | T | — |
| Iisalmi | 162 | 396 | 265 | 3 | 742 | 1500 V, 63 A | 58 | K | Y | — | Y | H | T | Y |
| Iisvesi | | | | 0 | — | — | — | — | K | — | — | — | T | — |
| Iittala | 170 | 170 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Ilomantsi | | | | 0 | 771 | 25 A | — | — | K | — | — | — | T | — |
| IMATRA | | | | | | | | | | | | | | |
| Imatra asema | | 450 | 265 | 1 | — | — | — | — | — | — | — | H | — | — |
| Imatra tavara | | (218) | (265) | (1) | 889 | 1500 V, 63 A | — | — | K Y | — | Y | — | T | Y |
| Imatrankoski | | | | 0 | 1209 | — | 18 | — | K | — | — | — | T | — |
| Pelkola | | | | 0 | 1373 | — | — | — | — | — | — | — | T | — |
| Imatrankoski-raja | | | | 0 | — | — | — | — | — | — | — | — | T | — |
| Inha | | (99) | (265) | (1) | — | — | 42 | — | K | — | — | — | T | — |
| Inkeroinen | 120 | 172 | 265 | 3 | 796 | — | 21 | — | K | — | — | H | T | — |
| Inkoo | 100 | 170 | 550 | 2 | 243 | 25 A | 14 | — | — | — | — | H | — | — |
| Isokangas | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Isokylä | | | | 0 | 576 | — | 14 | — | K | — | — | — | T | — |
| Isokyrö | 110 | 150 | 550, 265 | 2 | 509 | — | — | — | K | — | — | H | T | — |
| Jalasjärvi | | (51) | (550) | (1) | 764 | — | 28 | — | K | — | — | — | T | — |
| Jepua | | | | 0 | 825 | — | 16 | — | K | — | — | — | — | — |
| JOENSUU | | | | | | | | | | | | | | |
| Joensuu asema | 239 | 329 | 265 | 3 | 561 | 1500 V, 63 A | 46 | — | K | — | Y | H | T | 20, Y |
| Joensuu Peltola | | | | 0 | 666 | — | — | — | K Y | Y | — | — | T | — |
| Joensuu Sulkulahti | | | | 0 | 692 | — | — | — | — | — | — | — | T | — |
| Jokela | 320 | 338 | 550 | 3 | 821 | — | — | — | — | — | — | H | — | — |
| Joroinen | | | | 0 | — | — | — | — | — | — | — | — | T | — |
| Jorvas | 97 | 124 | 265 | 2 | — | — | — | — | — | — | — | H | — | — |
| Joutseno | 460 | 460 | 550 | 2 | 814 | — | — | — | K | — | — | H | T | — |
| Juankoski | | | | 0 | 583 | 25 A | 13 | — | — | — | — | — | T | — |
| Jutila | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Juupajoki | | 80 | 550 | 1 | — | — | — | — | — | — | — | H | — | — |
| Juurikorpi | | | | 0 | 789 | — | — | — | — | — | — | — | — | — |
| Jyväskylä | 160 | 449 | 550 | 4 | 796 | 1500 V, 63 A | 89 | K | Y | Y | Y | H | T | — |
| Jämsä | 391 | 391 | 550 | 2 | 770 | 25 A | — | — | K | — | — | H | T | — |
| Jämsänkoski | | | | 0 | 873 | 25 A | — | — | — | — | — | — | T | 20 |
| Järvelä | 122 | 122 | 550 | 3 | 630 | — | 12 | — | K | — | — | H | T | — |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri-korkeus | Laituriraitteiden lukumäärä | Mitoittava raidepituus (tavara-liikenne) | Sähkö-virran saanti | Sivulaituri, suurin pituus | Pääty-laituri | Kuormaus-kenttä | Nosturi | Polttoaine | Henkilö-liiken-nettä | Tavara-liikennettä | Kääntöpöytiä |
|------------------|----------------------------|---------------------------|------------------|---------------------------------|--|---------------------|------------------------------|----------------------------|------------------------|----------|------------|----------------------|--------------------|--------------|
| Namn | Kortaste plattform-längden | Längsta plattform-längden | Plattform-höjden | Antal spår med plattform | Dimensionerande spårlängd (godstrafik) | Tillgång på elström | Sidoplattform | Plattform i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person-traffic | Godstrafik | Vändskivor |
| Name | Min. platform length | Max. platform length | Platform height | Number of tracks with platforms | Design train length (freight traffic) | Power supply | Side loading platform length | End loading platform | Loading site | Crane | Fuel | Passenger traffic | Freight traffic | Turntables |
| | [m] | [m] | [mm] | | [m] | [400 V, A] | [m] | | | [t] | | | | |
| JÄRVENPÄÄ | | | | | | | | | | | | | | — |
| Järvenpää asema | 345 | 393 | 550 | 3 | — | — | 29 | K | — | — | — | H | T | — |
| Saunakallio | 180 | 275 | 550, 265 | 4 | 614 | — | — | — | — | — | — | H | T | — |
| Purola | 270 | 270 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Kaipiainen | | | | 0 | 770 | — | 19 | — | Y | — | — | — | T | — |
| Kaipola | | | | 0 | — | — | — | — | — | — | — | — | T | — |
| Kairoskoski | | | | 0 | — | — | 16 | — | K | — | — | — | T | — |
| Kaitjärvi | | | | 0 | 1109 | — | — | — | — | — | — | — | — | — |
| Kajaani | 352 | 411 | 265 | 2 | 845 | 1500 V, 63 A | 122 | — | K | — | — | H | T | — |
| Kaleton | | | | 0 | — | — | 27 | — | K | — | — | — | — | — |
| Kalkku | | | | 0 | — | — | 100 | — | Y | — | — | — | T | — |
| Kalliovarasto | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Kallistahti | | | | 0 | — | — | — | — | K | — | — | — | T | — |
| Kalvitsa | | | | 0 | 867 | — | — | — | K | — | — | — | T | — |
| Kangas | | | | 0 | 782 | 25 A | — | — | K | — | — | — | — | — |
| Kannelmäki | 226 | 226 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Kannonkoski | | | | 0 | — | — | 13 | — | K | — | — | — | T | — |
| Kannus | 339 | 420 | 265 | 2 | 818 | 25 A | 19 | — | K | — | — | H | — | — |
| Karhejärvi | | | | 0 | 778 | 25A | 4 | — | K | — | — | — | — | — |
| Karhukangas | | | | 0 | 840 | — | — | — | — | — | — | — | — | — |
| Karjaa | 248 | 352 | 550 | 4 | 765 | 63 A | — | — | K | — | Y | H | T | 20 |
| Karkku | | 250 | 550 | 1 | 852 | — | — | — | — | — | — | H | — | — |
| Karviainen | | | | 0 | 745 | — | — | — | — | — | — | — | — | — |
| Kaskinen | | | | 0 | 843 | — | — | — | Y | — | — | — | T | Y |
| Kattilaharju | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Kauhajoki | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Kauhava | | 450 | 550 | 1 | 803 | — | — | — | K | — | — | H | T | — |
| KAUKLAHTI | | | | | | | | | | | | | | — |
| Kauklahti asema | 270 | 270 | 550 | 3 | 447 | — | — | — | — | — | — | H | — | — |
| Mankki | 126 | 136 | 265 | 2 | — | — | — | — | — | — | — | H | — | — |
| Kautlinranta | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Kauniainen | 194 | 204 | 265 | 3 | 269 | — | — | — | — | — | — | H | T | — |
| Kauppihanmäki | | | | 0 | 634 | — | — | — | K | — | — | — | T | — |
| Kausala | 120 | 120 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Keiteleporja | | | | 0 | — | — | — | — | K | — | — | — | T | — |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri-korkeus | Laituriraiteiden lukumäärä | Mitoittava raidepituus (tavara-liikenne) | Sähkö-virran saanti | Sivulaituri, suurin pituus | Pääty-laituri | Kuormaus-kenttä | Nosturi | Polttoaine | Henkilö-liiken-nettä | Tavara-liikennettä | Kääntöpöytiä |
|---------------------|----------------------------|---------------------------|------------------|---------------------------------|--|---------------------|------------------------------|----------------------------|------------------------|----------|------------|----------------------|--------------------|--------------|
| Namn | Kortaste plattform-längden | Längsta plattform-längden | Plattform-höjden | Antal spår med plattform | Dimensionerande spårlängd (godstrafik) | Tillgång på elström | Sidoplattform | Plattform i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person-traffic | Godstrafik | Vändskivor |
| Name | Min. platform length | Max. platform length | Platform height | Number of tracks with platforms | Design train length (freight traffic) | Power supply | Side loading platform length | End loading platform | Loading site | Crane | Fuel | Passenger traffic | Freight traffic | Turntables |
| | [m] | [m] | [mm] | | [m] | [400 V, A] | [m] | | | [t] | | | | |
| Kekomäki | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Kelkkämäki | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Kemi | 450 | 450 | 550 | 3 | 949 | 63 A | 148 | — | K | — | Y | H | T | Y |
| Kemijärvi | | 352 | 265 | 1 | 547 | 1500 V, 63 A | 6 | K | K Y | — | — | H | T | Y |
| Kempele | | (119) | (265) | (1) | 762 | 25 A | 9 | — | K | — | — | — | — | — |
| Kera | 216 | 224 | 265 | 2 | — | — | — | — | — | — | — | H | — | — |
| KERAVA | | | | | | | | | | | | | | |
| <i>Kerava asema</i> | 270 | 392 | 550 | 4 | 789 | 25 A | — | — | — | — | Y | H | — | 20 |
| <i>Kytömaa</i> | | | | 0 | 790 | — | — | — | — | — | — | — | — | — |
| Kerimäki | | 108 | 265 | 1 | 398 | — | — | — | K | — | — | H | T | — |
| Kesälahti | | 322 | 265 | 1 | 671 | — | — | — | — | — | — | H | T | — |
| Keuruu | | 111 | 550 | 1 | 678 | — | — | — | K | — | — | H | T | — |
| Kihniö | | | | 0 | 646 | — | 11 | — | K | — | — | — | T | — |
| Kiiala | | | | 0 | — | — | — | — | — | — | — | H | — | — |
| Kilo | 270 | 270 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Kilpua | | | | 0 | 750 | 25 A | — | — | — | — | — | — | — | — |
| Kinahmi | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Kinni | | | | 0 | 776 | — | — | — | — | — | — | — | — | — |
| Kirjola | | | | 0 | — | — | — | — | Y | Y | — | — | — | — |
| Kirkkonummi | 316 | 322 | 550 | 3 | 606 | — | — | — | K | — | — | H | — | — |
| Kirkniemi | | | | 0 | 585 | — | — | — | — | — | — | — | T | — |
| Kitee | | 355 | 265 | 1 | 660 | 25 A | 18 | — | K Y | — | — | H | T | — |
| Kiukainen | | | | 0 | 764 | — | 14 | — | K | — | — | — | — | — |
| Kiuruvesi | | 126 | 265 | 1 | 675 | 25 A | 80 | — | K Y | — | — | H | T | — |
| Kivesjärvi | | (54) | (265) | (1) | 1118 | — | — | — | — | — | — | — | — | — |
| Kohtavaara | | 56 | 265 | 1 | — | — | — | — | — | — | — | H | — | — |
| Koivu | | (40) | (265) | (1) | 617 | — | 32 | — | K | — | — | — | T | — |
| Koivuhovi | 278 | 278 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Koivukylä | 270 | 270 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Kokemäki | 249 | 249 | 550 | 3 | 762 | 25 A | 29 | — | K | — | — | H | T | — |
| Kokkola | 150 | 482 | 265 | 4 | 829 | 1500 V, 63 A | 40 | — | Y | — | Y | H | T | Y |
| Kolari | | 451 | 550 | 1 | 792 | 63 A | 22 | K | K Y | — | — | H | T | — |
| Kolho | | 80 | 550 | 0 | — | — | — | — | Y | — | — | H | T | — |
| Kolppi | | | | 0 | 765 | — | — | — | — | — | — | — | — | — |
| Kommila | | | | 0 | 748 | 25 A | — | — | Y | — | — | — | T | — |
| Komu | | | | 0 | — | — | — | — | Y | — | — | — | — | — |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri-korkeus | Laituriraiteiden lukumäärä | Mitoittava raidepituus (tavara-liikenne) | Sähkö-virran saanti | Sivulaituri, suurin pituus | Pääty-laituri | Kuormaus-kenttä | Nosturi | Polttoaine | Henkilö-liiken-nettä | Tavara-liikennettä | Kääntöpöytiä |
|-------------------|----------------------------|---------------------------|------------------|---------------------------------|--|---------------------|------------------------------|----------------------------|------------------------|----------|------------|----------------------|--------------------|--------------|
| Namn | Kortaste plattform-längden | Längsta plattform-längden | Plattform-höjden | Antal spår med plattform | Dimensionerande spårlängd (godstrafik) | Tillgång på elström | Sidoplattform | Plattform i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person-traffic | Godstrafik | Vändskivor |
| Name | Min. platform length | Max. platform length | Platform height | Number of tracks with platforms | Design train length (freight traffic) | Power supply | Side loading platform length | End loading platform | Loading site | Crane | Fuel | Passenger traffic | Freight traffic | Turntables |
| | [m] | [m] | [mm] | | [m] | [400 V, A] | [m] | | | [t] | | | | |
| Kontiolahti | | (96) | (265) | (1) | 577 | 25 A | — | K | K | — | — | — | T | — |
| Kontiomäki | 350 | 350 | 265 | 3 | 893 | 63A | 31 | K | K | — | Y | H | T | Y |
| Koria | 120 | 120 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Korkeakoski | | (72) | (265) | (1) | 747 | — | — | K | K | — | — | — | T | — |
| Korso | 270 | 270 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Korvensuo | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Koskenkorva | | | | 0 | — | — | — | — | — | — | — | — | T | — |
| KOTKA | | | | | | | | | | | | | | |
| Kotka Hovinsaari | | | | 0 | 865 | 63 A | 85 | — | — | — | — | — | T | — |
| Kotka tavara | | | | 0 | — | — | — | — | — | — | — | — | T | — |
| Paimenportti | | 53 | 265 | 1 | — | — | — | — | — | — | — | H | — | — |
| Kotka asema | | 193 | 265 | 1 | 270 | 63 A | — | — | — | — | — | H | — | Y |
| Kotkan satama | | 110 | 265 | 1 | 539 | 63 A | 280 | — | K | — | Y | H | T | — |
| Kotolahti | | | | 0 | 1176 | — | — | — | — | — | — | — | T | — |
| Kotka Mussalo | | | | 0 | 1005 | — | 25 | — | Y | — | — | — | T | — |
| KOUVOLA | | | | | | | | | | | | | | |
| Kouvola asema | 230 | 480 | 550 | 7 | 600 | 1500 V, 63 A | — | — | K | — | Y | H | — | Y |
| Kouvola lajittelu | | | | 0 | 865 | 25 A | 175 | K | — | — | — | — | T | — |
| Kouvola Oikoraide | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Kouvola tavara | | | | 0 | 903 | — | 11 | — | — | — | — | — | T | — |
| Kullasvaara | | | | 0 | 1364 | — | — | — | — | — | — | — | T | — |
| Kovjoki | | | | 0 | 757 | — | — | — | — | — | — | — | — | — |
| Kruunupyy | | | | 0 | 747 | 25 A | 49 | — | K | — | — | — | T | — |
| Kuivasjärvi | | | | 0 | 781 | — | — | — | K | — | — | — | — | — |
| KUOPIO | | | | | | | | | | | | | | |
| Kuopio asema | 90 | 387 | 265 | 4 | 370 | 63 A | 130 | K | Y | — | — | H | — | — |
| Kuopio tavara | | | | 0 | 766 | 1500 V, 63 A | 100 | — | Y | — | Y | — | T | Y |
| Kurkimäki | | | | 0 | 776 | — | — | — | K | — | — | — | T | — |
| Kuurila | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Kuusankoski | | | | 0 | 803 | 63 A | — | — | Y | — | — | — | T | — |
| Kylänlahti | | 57 | 265 | 1 | — | — | — | — | — | — | — | H | — | — |
| Kymi | 32 | 66 | 265 | 2 | 744 | — | — | — | — | — | — | H | — | — |
| Kyminlinna | | 55 | 265 | 1 | — | — | — | — | — | — | — | H | — | — |
| Kyrö | | | | 0 | 739 | — | — | — | K | — | — | — | T | — |
| Kyrölä | 270 | 270 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Kälviä | | | | 0 | 1040 | 25 A | 18 | — | K | — | — | — | — | — |

[illegible]

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri-korkeus | Laituriraiteiden lukumäärä | Mitoittava raidepituus (tavara-liikenne) | Sähkö-virran saanti | Sivulaituri, suurin pituus | Pääty-laituri | Kuormaus-kenttä | Nosturi | Polttoaine | Henkilö-liiken-nettä | Tavara-liikennettä | Kääntöpöytiä |
|-----------------|----------------------------|---------------------------|------------------|---------------------------------|--|---------------------|------------------------------|----------------------------|------------------------|----------|------------|----------------------|--------------------|--------------|
| Namn | Kortaste plattform-längden | Längsta plattform-längden | Plattform-höjden | Antal spår med plattform | Dimensionerande spårlängd (godstrafik) | Tillgång på elström | Sidoplattform | Plattform i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person-traffic | Godstrafik | Vändskivor |
| Name | Min. platform length | Max. platform length | Platform height | Number of tracks with platforms | Design train length (freight traffic) | Power supply | Side loading platform length | End loading platform | Loading site | Crane | Fuel | Passenger traffic | Freight traffic | Turntables |
| | [m] | [m] | [mm] | | [m] | [400 V, A] | [m] | | | [t] | | | | |
| Loukolampi | | | | 0 | 886 | — | — | — | — | — | — | — | — | — |
| Loviisan satama | | | | 0 | 681 | 25 A | 28 | — | K Y | Y | — | — | T | — |
| Luikonlahti | | | | 0 | 890 | — | — | — | K Y | — | — | — | T | — |
| Luoma | 216 | 216 | 265 | 2 | — | — | — | — | — | — | — | H | — | — |
| Lusto | | 124 | 265 | 1 | — | — | — | — | — | — | — | H | — | — |
| Luumäki | | | | 0 | 1234 | — | 14 | — | Y | — | — | — | T | — |
| Lähdemäki | | | | 0 | 998 | — | — | — | — | — | — | — | — | — |
| Länkipohja | | | | 0 | 802 | — | — | — | — | — | — | — | — | — |
| Maanselkä | | | | 0 | — | — | — | — | K | — | — | — | — | — |
| Maaria | | | | 0 | 743 | — | — | — | — | — | — | — | — | — |
| Madesjärvi | | | | 0 | 777 | 25 A | 8 | — | K | — | — | — | T | — |
| Majajärvi | | | | 0 | 717 | — | — | — | — | — | — | — | — | — |
| Malmi | (280) | 348 | 550 (265) | 2 (2) | — | — | — | — | — | — | — | H | — | — |
| Malminkartano | 284 | 284 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Mankala | | | | 0 | 0 | — | — | — | — | — | — | — | — | — |
| Markkala | | | | 0 | 747 | — | — | — | — | — | — | — | — | — |
| Martinlaakso | 236 | 236 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Masala | 267 | 267 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Matkaneva | | | | 0 | 845 | — | — | — | — | — | — | — | — | — |
| Mattila | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Meltola | | | | 0 | — | — | 10 | — | — | — | — | — | T | — |
| Metsäkansa | | | | 0 | — | — | 13 | — | K | — | — | — | T | — |
| Mikkeli | 352 | 452 | 550 | 3 | 760 | 25 A | 5 | — | K Y | — | Y | H | T | Y |
| Misi | | 352 | 265 | 1 | 760 | 63 A | 52 | K | K | — | — | H | T | — |
| Mommila | 120 | 120 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Muhos | 151 | 212 | 265 | 2 | 670 | 25 A | 24 | — | K | — | — | H | — | — |
| Mukkula | | | | 0 | — | — | — | — | K | — | — | — | T | — |
| Murtomäki | | | | 0 | — | — | — | — | K | — | — | — | T | — |
| Mustio | | | | 0 | — | — | 55 | — | K | — | — | — | T | — |
| Mustolan satama | | | | 0 | — | — | — | — | Y | Y | — | — | T | — |
| Muukko | | | | 0 | 787 | — | — | — | — | — | — | — | — | — |
| Muurame | | | | 0 | 838 | 25 A | — | — | — | — | — | — | — | — |
| Muurola | 316 | 317 | 265 | 2 | 724 | — | — | — | — | — | — | H | — | — |
| Myllykangas | | | | 0 | 851 | — | — | — | — | — | — | — | — | — |
| Myllykoski | 110 | 110 | 265 | 2 | — | — | — | — | — | — | — | H | — | — |
| Myllymäki | | 216 | 265 | 1 | — | — | — | — | K | — | — | H | T | — |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri-korkeus | Laituriraiteiden lukumäärä | Mitoittava raidepituus (tavara-liikenne) | Sähkö-virran saanti | Sivulaituri, suurin pituus | Pääty-laituri | Kuormaus-kenttä | Nosturi | Polttoaine | Henkilö-liiken-nettä | Tavara-liikennettä | Kääntöpöytiä |
|------------------|----------------------------|---------------------------|------------------|---------------------------------|--|---------------------|------------------------------|----------------------------|------------------------|----------|------------|----------------------|--------------------|--------------|
| Namn | Kortaste plattform-längden | Längsta plattform-längden | Plattform-höjden | Antal spår med plattform | Dimensionerande spårlängd (godstrafik) | Tillgång på elström | Sidoplattform | Plattform i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person-traffic | Godstrafik | Vändskivor |
| Name | Min. platform length | Max. platform length | Platform height | Number of tracks with platforms | Design train length (freight traffic) | Power supply | Side loading platform length | End loading platform | Loading site | Crane | Fuel | Passenger traffic | Freight traffic | Turntables |
| | [m] | [m] | [mm] | | [m] | [400 V, A] | [m] | | | [t] | | | | |
| Myllyoja | | | | 0 | — | — | — | — | — | — | — | — | T | — |
| Mynttilä | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Mynämäki | | (124) | (265) | (1) | 495 | — | — | — | — | — | — | — | — | — |
| Myyrmäki | 232 | 232 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Mäkkylä | 270 | 288 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Mäntsälä | 220 | 220 | 550 | 2 | 999 | — | — | — | — | — | — | H | — | — |
| Mänttä | | | | 0 | 553 | — | — | — | K | — | — | — | T | — |
| Mäntyharju | 457 | 457 | 550 | 2 | 992 | — | 159 | — | K | — | — | H | T | — |
| Mäntyluoto | | | | 0 | 779 | — | — | — | Y | Y | — | — | T | — |
| Naantali | | | | 0 | 393 | — | 20 | — | — | — | — | — | T | — |
| Naarajärvi | | | | 0 | 770 | — | — | — | K | — | — | — | T | — |
| Nakkila | | | | 0 | 733 | — | — | — | — | — | — | — | — | — |
| Nastola | 120 | 120 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Niemenpää | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Niinimaa | | | | 0 | — | — | — | — | K | — | — | — | — | — |
| Niinimäki | | | | 0 | 1090 | — | — | — | — | — | — | — | — | — |
| Niinisalo | | | | 0 | — | 63 A | 22 | K | K | — | — | — | T | — |
| Niirala | | (42) | (265) | (1) | 929 | 25 A | — | — | K | — | — | — | T | — |
| Niirala-raja | | | | 0 | — | — | — | — | — | — | — | — | T | — |
| Niittylahti | | | | 0 | 695 | — | — | — | — | — | — | — | — | — |
| Nikkilä | | (30) | (265) | (1) | — | — | — | — | — | — | — | — | — | — |
| Nivala | | 97 | 265 | 1 | 825 | 25 A | — | — | K | — | — | H | T | — |
| Nokia | | 250 | 550 | 1 | 865 | — | 120 | — | K | — | — | H | T | — |
| Nummela | | | | 0 | 328 | — | — | — | K | — | — | — | T | — |
| Nuppulinna | 210 | 240 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Nurmes | 73 | 205 | 265 | 2 | 851 | 25 A | 50 | K | — | — | — | H | T | 18 |
| Närpiö | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Ohenmäki | | | | 0 | — | — | — | — | K | — | — | — | — | — |
| Olli | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Onttola | | | | 0 | — | — | — | — | — | — | — | — | T | — |
| Orimattila | | | | 0 | — | — | 12 | — | K | — | — | — | T | — |
| Orivesi | 297 | 380 | 550 | 3 | 765 | 25 A | — | — | K | — | — | H | T | 13,7 |
| Orivesi keskusta | | 80 | 550 | 1 | — | — | — | — | — | — | — | H | — | — |
| Otanmäki | | | | 0 | — | — | — | — | K | — | — | — | T | — |
| Otava | | (152) | (265) | (1) | 735 | — | — | — | K | — | — | — | T | — |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri-korkeus | Laituriraiteiden lukumäärä | Mitoittava raidepituus (tavara-liikenne) | Sähkö-virran saanti | Sivulaituri, suurin pituus | Pääty-laituri | Kuormaus-kenttä | Nosturi | Polttoaine | Henkilö-liiken-nettä | Tavara-liikennettä | Kääntöpöytiä |
|-----------------------------|----------------------------|---------------------------|------------------|---------------------------------|--|---------------------|------------------------------|----------------------------|------------------------|----------|------------|----------------------|--------------------|--------------|
| Namn | Kortaste plattform-längden | Längsta plattform-längden | Plattform-höjden | Antal spår med plattform | Dimensionerande spårlängd (godstrafik) | Tillgång på elström | Sidoplattform | Plattform i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person-traffic | Godstrafik | Vändskivor |
| Name | Min. platform length | Max. platform length | Platform height | Number of tracks with platforms | Design train length (freight traffic) | Power supply | Side loading platform length | End loading platform | Loading site | Crane | Fuel | Passenger traffic | Freight traffic | Turntables |
| | [m] | [m] | [mm] | | [m] | [400 V, A] | [m] | | | [t] | | | | |
| Otavan satama | | | | 0 | — | — | — | — | — | — | — | — | T | — |
| Oulainen | 427 | 428 | 265 | 3 | 929 | 25 A | 80 | — | K | — | — | H | T | — |
| OULU | | | | | | | | | | | | | | |
| <i>Oulu Nokela</i> | | | | 0 | 990 | 63 A | — | — | — | — | Y | — | T | — |
| <i>Oulu Oritkari</i> | | | | 0 | — | 63 A | 200 | — | Y | Y | — | — | T | — |
| <i>Oulu tavara</i> | | | | 0 | 761 | 25 A | 6 | — | — | — | — | — | T | Y |
| <i>Oulu asema</i> | 366 | 458 | 550, 265 | 3 | 475 | 1500 V, 63 | — | K | — | — | — | H | — | — |
| <i>Oulu Tuira</i> | | | | 0 | 759 | — | 66 | — | K | — | — | — | T | — |
| Paimio | | | | 0 | 763 | — | — | — | — | — | — | — | — | — |
| Palopuro | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Paltamo | | 230 | 265 | 1 | 664 | 25 A | — | — | K | — | — | H | T | — |
| Pankakoski | | | | 0 | — | — | — | — | K Y | — | — | — | T | — |
| Parikkala | 210 | 379 | 265 | 3 | 705 | 25 A | 30 | K | — | — | — | H | — | — |
| Parkano | 600 | 600 | 550 | 3 | 943 | 25 A | 10 | — | K Y | — | — | H | T | — |
| Parola | 192 | 196 | 550 | 2 | 920 | — | 31 | Y | K | Y | — | H | T | — |
| Pello | | 454 | 265 | 1 | 585 | 25 A | 35 | — | Y | — | — | H | T | — |
| Peltosalmi | | | | 0 | — | 25 A | — | — | K | Y | — | — | T | — |
| Peräseinäjoki | | | | 0 | 762 | — | 16 | — | K | — | — | — | T | — |
| Pesiökylä | | (74) | (265) | (1) | — | — | — | — | — | — | — | — | — | — |
| Petäjävesi | | 142 | 265 | 1 | 762 | — | — | — | K | — | — | H | T | — |
| PIEKSÄMÄKI | | | | | | | | | | | | | | |
| <i>Pieksämäki asema</i> | 332 | 611 | 265 | 4 | 499 | 1500 V, 63 A | 5 | — | Y | — | — | H | — | — |
| <i>Pieksämäki Ternu</i> | | | | 0 | 947 | 63 A | — | — | K Y | — | Y | — | — | — |
| <i>Pieksämäki lajittelu</i> | | | | 0 | 954 | — | — | — | — | — | — | — | T | — |
| <i>Pieksämäki tavara</i> | | | | 0 | 752 | — | — | — | — | — | — | — | T | — |
| Pietarsaari | | | | 0 | 766 | 25 A | — | — | — | — | — | — | T | — |
| Pihlajavesi | 99 | 120 | 550, 265 | 2 | 546 | — | — | — | — | — | — | H | — | — |
| Pihtipudas | | | | 0 | — | — | — | — | K | — | — | — | T | 9 |
| Piikkiö | | | | 0 | 303 | — | — | — | K | — | — | — | T | — |
| Pikkarala | | | | 0 | 759 | — | — | — | — | — | — | — | — | — |
| Pitäjänmäki | 270 | 306 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Pohjankuru | | | | 0 | 301 | — | — | — | K | Y | — | — | T | — |
| Pohjois-Haaga | 240 | 240 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Pohjois-Louko | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Poikkeus | | | | 0 | 715 | — | — | — | — | — | — | — | — | — |
| Poiksilta | | | | 0 | — | — | — | — | K | — | — | — | T | — |

[illegible]

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri-korkeus | Laituriraitteiden lukumäärä | Mitoittava raidepituus (tavara-liikenne) | Sähkö-virran saanti | Sivulaituri, suurin pituus | Pääty-laituri | Kuormaus-kenttä | Nosturi | Polttoaine | Henkilö-liiken-nettä | Tavara-liikennettä | Kääntöpöytiä |
|---------------------------|----------------------------|---------------------------|------------------|---------------------------------|--|---------------------|------------------------------|----------------------------|------------------------|----------|------------|----------------------|--------------------|--------------|
| Namn | Kortaste plattform-längden | Längsta plattform-längden | Plattform-höjden | Antal spår med plattform | Dimensionerande spårlängd (godstrafik) | Tillgång på elström | Sidoplattform | Plattform i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person-traffic | Godstrafik | Vändskivor |
| Name | Min. platform length | Max. platform length | Platform height | Number of tracks with platforms | Design train length (freight traffic) | Power supply | Side loading platform length | End loading platform | Loading site | Crane | Fuel | Passenger traffic | Freight traffic | Turntables |
| | [m] | [m] | [mm] | | [m] | [400 V, A] | [m] | | | [t] | | | | |
| Sköldvik | | | | 0 | 929 | 25 A | — | — | — | — | — | — | T | — |
| Soinlahti | | | | 0 | — | — | — | — | K | — | — | — | T | — |
| Sorsasalo | | | | 0 | — | — | — | — | — | — | — | — | T | — |
| Sukeva | 182 | 239 | 550, 265 | 2 | 624 | 25 A | — | — | K | — | — | H | T | — |
| Suolahti | (80) | (147) | (265) | (2) | 682 | 25 A | — | — | K | — | — | — | T | Y |
| Suonenjoki | 250 | 341 | 265 | 3 | 825 | 25 A | — | — | K | — | — | H | T | 20 |
| Suoniemi | | | | 0 | 743 | — | — | — | — | — | — | — | — | — |
| Syrjä | | | | 0 | — | — | 5 | — | — | — | — | — | — | — |
| Syrjämäki | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Sysmäjärvi | | | | 0 | — | — | — | — | K | — | — | — | T | — |
| Säkäniemi | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Sänkimäki | | | | 0 | — | — | — | — | K | — | — | — | T | — |
| Sääksjärvi | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Taavetti | | | | 0 | 723 | — | 18 | — | — | — | — | — | T | — |
| Tahkoluoto | | | | 0 | — | — | — | — | Y | — | — | — | T | — |
| Taipale | | | | 0 | 829 | — | — | — | — | — | — | — | — | — |
| Talviainen | | | | 0 | 732 | 25 A | — | — | — | — | — | — | — | — |
| Talvivaara | | | | 0 | 614 | — | — | — | — | — | — | — | T | — |
| Tammisaari | | 80 | 550 | 1 | — | — | — | — | — | — | — | H | — | — |
| TAMPERE | | | | | | | | | | | | | | |
| <i>Tampere tavara</i> | | | | 0 | 767 | 1500 V, 63 A | 15 | — | — | Y | Y | — | T | 22 |
| <i>Tampere Viinikka</i> | | | | 0 | 966 | 25 A | 134 | K | Y | Y | — | — | T | — |
| <i>Tampere asema</i> | 500 | 500 | 550 | 5 | 693 | 1500 V, 63 A | — | K | — | — | — | H | — | — |
| <i>Tampere Järvensivu</i> | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Tapanila | 272 | 272 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Tapavainola | | | | 0 | 748 | — | — | — | — | — | — | — | — | — |
| Tavastila | | 47 | 265 | 1 | — | — | — | — | — | — | — | H | — | — |
| Tervajoki | | 171 | 265 | 1 | — | — | — | — | — | — | — | H | — | — |
| Tervola | 231 | 301 | 265 | 2 | 709 | 25 A | 11 | — | K | — | — | H | — | — |
| Teuva | | | | 0 | — | 25 A | — | — | K | — | — | — | T | — |
| Tikkala | | | | 0 | 1029 | — | — | — | — | — | — | — | — | — |
| Tikkaperä | | | | 0 | 926 | — | — | — | — | — | — | — | — | — |
| TIKKURILA | | | | | | | | | | | | | | |
| <i>Havukoski</i> | | | | 0 | 0 | — | — | — | — | — | — | — | — | — |
| <i>Hiekkaharju</i> | 257 | 526 | 550 | 3 | — | — | — | — | — | — | — | H | — | — |
| <i>Tikkurila asema</i> | 320 | 445 | 550 | 6 | 413 | — | 30 | — | K | — | — | H | T | — |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri-korkeus | Laituriraitteiden lukumäärä | Mitoittava raidepituus (tavara-liikenne) | Sähkö-virran saanti | Sivulaituri, suurin pituus | Pääty-laituri | Kuormaus-kenttä | Nosturi | Polttoaine | Henkilö-liiken-nettä | Tavara-liikennettä | Kääntöpöytiä |
|--------------------------|----------------------------|---------------------------|------------------|---------------------------------|--|---------------------|------------------------------|----------------------------|------------------------|----------|------------|----------------------|--------------------|--------------|
| Namn | Kortaste plattform-längden | Längsta plattform-längden | Plattform-höjden | Antal spår med plattform | Dimensionerande spårlängd (godstrafik) | Tillgång på elström | Sidoplattform | Plattform i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person-traffic | Godstrafik | Vändskivor |
| Name | Min. platform length | Max. platform length | Platform height | Number of tracks with platforms | Design train length (freight traffic) | Power supply | Side loading platform length | End loading platform | Loading site | Crane | Fuel | Passenger traffic | Freight traffic | Turntables |
| | [m] | [m] | [mm] | | [m] | [400 V, A] | [m] | | | [t] | | | | |
| Tohmajärvi | | | | 0 | 735 | — | — | — | K | — | — | — | T | — |
| Toijala | 450 | 450 | 550 | 4 | 690 | 25 A | — | — | K | Y | Y | H | T | Y |
| Toivala | | | | 0 | 749 | 25 A | — | — | K | — | — | — | T | — |
| Tolsa | 109 | 109 | 265 | 2 | — | — | — | — | — | — | — | H | — | — |
| Tommola | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Torkkeli | | | | 0 | 788 | — | — | — | — | — | — | — | — | — |
| TORNIO | | | | | | | | | | | | | | |
| <i>Tornio asema</i> | (101) | (157) | (265) | (2) | 434 | 63 A | 24 | K | K | Y | — | — | T | — |
| <i>Tornio-raja</i> | | | | 0 | — | — | — | — | — | — | — | — | T | — |
| Tornio-Itäinen | | 297 | 550 | 1 | — | — | — | — | — | — | — | H | — | — |
| Tuomarila | 220 | 222 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Tuomioja | | | | 0 | 644 | 25 A | — | — | — | — | — | — | — | — |
| Turenki | 170 | 170 | 550 | 2 | 1212 | — | — | — | K | — | — | H | T | — |
| TURKU | | | | | | | | | | | | | | |
| <i>Kupittaa</i> | 420 | 420 | 550 | 2 | 633 | — | — | — | — | — | — | H | — | — |
| <i>Turku asema</i> | 315 | 466 | 550 | 6 | 756 | 1500 V, 63 A | — | K | — | — | Y | H | T | Y |
| <i>Turku tavara</i> | | (200) | (265) | (1) | 382 | 25 A | 10 | — | K Y | Y | — | — | T | — |
| <i>Turku satama</i> | 300 | 304 | 550 | 2 | 421 | 63 A | — | — | — | — | — | H | — | — |
| Tuupovaara | | | | 0 | — | — | 14 | — | K | — | — | — | T | — |
| Tuuri | | 66 | 550 | 1 | — | — | — | — | K | — | — | H | — | — |
| Törmä | | | | 0 | 856 | — | — | — | — | — | — | — | — | — |
| Törölä | | | | 0 | 756 | — | — | — | — | — | — | — | — | — |
| Uimaharju | | 98 | 550 | 1 | 805 | 25 A | — | — | K Y | — | — | H | T | — |
| Ujala | | | | 0 | 732 | — | 8 | — | — | — | — | — | — | — |
| Utajärvi | 163 | 174 | 265 | 2 | 715 | — | 25 | — | K | — | — | H | T | — |
| Utti | | | | 0 | — | — | 101 | — | — | — | — | — | T | — |
| Uusikaupunki | | (66) | (265) | (1) | 680 | — | — | — | — | — | — | — | T | — |
| Uusikylä | 120 | 120 | 550 | 2 | 1382 | — | 6 | — | K | Y | — | — | T | — |
| Vaajakoski | | | | 0 | 725 | — | 14 | — | K | — | — | — | T | — |
| Vaala | 183 | 236 | 265 | 2 | 1022 | 25 A | 25 | — | K | — | — | H | — | — |
| Vaarala | | | | 0 | — | — | — | — | K | — | — | — | T | — |
| Vaasa | | 290 | 550 | 1 | 450 | 1500 V, 63 A | — | — | — | — | — | H | T | — |
| Vahojärvi | | | | 0 | 716 | — | — | — | — | — | — | — | — | — |
| VAINIKKALA | | | | | | | | | | | | | | |
| <i>Vainikkala tavara</i> | | | | 0 | 1083 | 25 A | 50 | K | Y | Y | Y | — | T | — |
| <i>Vainikkala asema</i> | 482 | 484 | 550, 265 | 3 | 952 | — | — | — | K | — | — | H | T | — |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri-korkeus | Laituriraiteiden lukumäärä | Mitoittava raidepituus (tavara-liikenne) | Sähkö-virran saanti | Sivulaituri, suurin pituus | Pääty-laituri | Kuormaus-kenttä | Nosturi | Polttoaine | Henkilö-liiken-nettä | Tavara-liikennettä | Kääntöpöytiä |
|-------------------------|----------------------------|---------------------------|------------------|---------------------------------|--|---------------------|------------------------------|----------------------------|------------------------|----------|------------|----------------------|--------------------|--------------|
| Namn | Kortaste plattform-längden | Längsta plattform-längden | Plattform-höjden | Antal spår med plattform | Dimensionerande spårlängd (godstrafik) | Tillgång på elström | Sidoplattform | Plattform i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person-traffic | Godstrafik | Vändskivor |
| Name | Min. platform length | Max. platform length | Platform height | Number of tracks with platforms | Design train length (freight traffic) | Power supply | Side loading platform length | End loading platform | Loading site | Crane | Fuel | Passenger traffic | Freight traffic | Turntables |
| | [m] | [m] | [mm] | | [m] | [400 V, A] | [m] | | | [t] | | | | |
| Vainikkala-raja | | | | 0 | — | — | — | — | — | — | — | — | T | — |
| Valimo | 270 | 270 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Valkeakoski | | (44) | (265) | (1) | — | — | 54 | — | K | — | — | — | T | — |
| Valkeasuo | | | | 0 | — | — | — | — | K | — | — | — | — | — |
| Valtimo | | | | 0 | 756 | — | — | — | K | — | — | — | T | — |
| Vammala | 251 | 251 | 550 | 3 | 843 | — | 128 | — | Y | — | — | H | T | — |
| Vanattara | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Vantaankoski | 230 | 230 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Varkaus | 180 | 213 | 265 | 2 | 728 | 63 A | 124 | K | K Y | — | — | H | T | — |
| Vartius | | | | 0 | 1097 | 25 A | — | — | K | — | — | — | T | — |
| Vartius-raja | | | | 0 | — | — | — | — | — | — | — | — | T | — |
| Vasikkahaka | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Vaskiluoto | | | | 0 | — | — | — | — | K Y | — | — | — | T | — |
| Venetmäki | | | | 0 | 838 | — | — | — | — | — | — | — | — | — |
| Vesanka | | | | 0 | — | — | 5 | — | K | — | — | — | — | — |
| Viekki | | | | 0 | — | — | — | — | K | — | — | — | — | — |
| Vierumäki | | | | 0 | — | — | 92 | — | K | — | — | — | T | — |
| Vihanti | 450 | 450 | 550 | 2 | 803 | 25 A | — | — | K | — | — | H | T | — |
| Vihtari | 58 | 103 | 265 | 2 | 551 | 25 A | 134 | — | K | — | — | H | T | — |
| Viiala | 170 | 170 | 550 | 2 | — | — | — | — | — | — | — | H | — | — |
| Viinijärvi | 136 | 211 | 265 | 2 | 641 | 25 A | — | — | — | — | — | H | T | — |
| Villähde | 120 | 120 | 550 | 2 | — | — | — | — | — | — | — | — | — | — |
| Vilppula | | 110 | 550 | 1 | 694 | 25 A | — | — | K | — | — | H | T | — |
| Vinnilä | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Voltti | | | | 0 | 761 | — | — | — | — | — | — | — | — | — |
| Vuohijärvi | | | | 0 | 713 | — | 15 | K | — | — | — | — | T | — |
| Vuojoki | | | | 0 | 760 | — | — | — | — | — | — | — | — | — |
| Vuokatti | (110) | (141) | (265) | (2) | 627 | 25 A | — | — | K Y | — | — | — | T | — |
| Vuonislahti | | 94 | 265 | 1 | — | — | — | — | — | — | — | H | — | — |
| Vuonos | | | | 0 | — | — | 16 | — | — | Y | — | — | T | — |
| Vuorten-Vuori | | | | 0 | — | — | — | — | — | — | — | — | — | — |
| Vuosaari | | | | 0 | 927 | — | — | — | — | — | — | — | T | — |
| YKSPIHLAJA | | | | | | | | | | | | | | |
| Ykspihlaja tavara | | | | 0 | 767 | — | — | — | K Y | Y | — | — | T | — |
| Ykspihlaja väliratapiha | | | | 0 | 939 | 63 A | — | — | K Y | Y | — | — | T | — |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri-korkeus | Laituriraiteiden lukumäärä | Mitoittava raidepituus (tavara-liikenne) | Sähkö-virran saanti | Sivulaituri, suurin pituus | Pääty-laituri | Kuormaus-kenttä | Nosturi | Polttoaine | Henkilö-liiken-nettä | Tavara-liikennettä | Kääntöpöytiä |
|-------------|----------------------------|---------------------------|------------------|---------------------------------|--|---------------------|------------------------------|----------------------------|------------------------|----------|------------|----------------------|--------------------|--------------|
| Namn | Kortaste plattform-längden | Längsta plattform-längden | Plattform-höjden | Antal spår med plattform | Dimensionerande spårlängd (godstrafik) | Tillgång på elström | Sidoplattform | Plattform i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person-traffic | Godstrafik | Vändskivor |
| Name | Min. platform length | Max. platform length | Platform height | Number of tracks with platforms | Design train length (freight traffic) | Power supply | Side loading platform length | End loading platform | Loading site | Crane | Fuel | Passenger traffic | Freight traffic | Turntables |
| | [m] | [m] | [mm] | | [m] | [400 V, A] | [m] | | | [t] | | | | |
| Ylistaro | | 176 | 265 | 1 | — | — | — | — | — | — | — | H | — | — |
| Ylitornio | | 167 | 265 | 1 | — | 25 A | — | — | — | — | Y | H | — | — |
| Ylivalli | | | | 0 | 1014 | — | — | — | Y | — | — | — | — | — |
| Ylivieska | 315 | 482 | 265 | 3 | 767 | 63 A | 113 | — | K Y | Y | Y | H | T | 20 |
| Yläkoski | | | | 0 | — | — | — | — | Y | — | — | — | T | — |
| Ylämylly | | | | 0 | — | — | 77 | — | K | — | — | — | T | — |
| Ylöjärvi | | | | 0 | 714 | — | 62 | — | K | — | — | — | T | — |
| Ypykkävaara | | | | 0 | 753 | — | — | — | K | — | — | — | T | — |
| Äetsä | | | | 0 | 924 | — | — | — | K | — | — | — | — | — |
| Ähtäri | 85 | 225 | 265 | 2 | 614 | — | — | — | — | — | — | H | — | — |
| Ämmänsaari | | | | 0 | 633 | 25 A | — | — | K | — | — | — | T | — |
| Äänekoski | (35) | (75) | (265) | (2) | 860 | 25 A | 14 | — | K | — | — | — | T | — |

| Nimi | Toinen nimi | Lyhenne | Kaupallinen nimi | Tyyppi | Km Hki | Rataosuus | Kunta | Kauko-ohjaus/ manuaalinen | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|----------------|-----------------|-------------|-------------------|--------|---------|-------------------------|--------------|------------------------------|-------------------------------|------------------------------|
| Namn | Namn på svenska | Förkortning | Kommersiellt namn | Typ | Km Hki | Banavsnitt | Kommun | Trafikledning | Privata spår- anläggningar | Möjlighet till växlarbete |
| Name | Another name | Abbr. | Commercial name | Type | Km Hki | Section | Municipality | Traffic control | Private sidings | Shunting |
| Ahonpää | | Aho | | | 690+503 | Seinäjoki–Oulu | Siikajoki | K | | |
| Asola *) | | Aso | | | 31+527 | Vantaankoski–Havukoski | Vantaa | K | | |
| Aviapolis *) | | Avp | | | 25+135 | Vantaankoski–Havukoski | Vantaa | K | | |
| Haimoo | | Hmo | | | 87+700 | Hyvinkää–Karjaa | Vihti | K | | |
| Jäniskorpi | | Jnk | | | 586+419 | Seinäjoki–Oulu | Kannus | K | | |
| Kiilinkangas | | Kkg | | | 299+490 | Kouvola–Joensuu | Lappeenranta | K | | |
| Kivistö *) | | Ktö | | | 18+300 | Vantaankoski–Havukoski | Vantaa | K | | |
| Kuninkaanmäki | | Knm | | | 38+500 | Kerava–Vuosaari | Vantaa | K | | |
| Laajavuori *) | | Lav | | | 14+428 | Huopalahti–Vantaankoski | Vantaa | K | | |
| Lapinkylä | | Lpk | | | 19+900 | Vantaankoski–Havukoski | Vantaa | K | | |
| Leinelä) | Lejle | Lnä | | | 31+146 | Vantaankoski–Havukoski | Vantaa | K | | |
| Lentoasema *) | Flygplatsen | Len | | | 26+575 | Vantaankoski–Havukoski | Vantaa | K | | |
| Liminpuro | | Lmp | | | 864+750 | Oulu–Kontiomäki | Vaala | K | | |
| Niska | | Nsk | | | 826+880 | Oulu–Kontiomäki | Utajärvi | K | | |
| Pappilankangas | | Pkg | | | 308+633 | Kouvola–Joensuu | Lappeenranta | K | | |
| Petas | | Pet | | | 17+170 | Vantaankoski–Havukoski | Vantaa | K | | |
| Puikkokoski | | Pui | | | 665+680 | Kontiomäki–Vartius-raja | Paltamo | K | | |
| Puolukkasuo *) | | Puo | | | 23+510 | Vantaankoski–Havukoski | Vantaa | K | | |
| Ruoneva | | Rnv | | | | Seinäjoki–Oulu | Siikajoki | K | | |
| Ruskeasanta *) | Rödsand | Rs | | | 28+760 | Vantaankoski–Havukoski | Vantaa | K | | |
| Ruusumäki *) | | Rsm | | | 20+300 | Vantaankoski–Havukoski | Vantaa | K | | |
| Saarela | | Srl | | | 594+018 | Seinäjoki–Oulu | Kannus | K | | |
| Salmenmäki | | Sal | | | | Seinäjoki–Oulu | | K | | |
| Temmesjoki | | Tmj | | | | Seinäjoki–Oulu | Liminka | K | | |
| Tuomaanvaara | | Tva | | | 682+300 | Kontiomäki–Vartius-raja | Ristijärvi | K | | |
| Tupavuori | | Tvu | | | 260+100 | Kouvola–Joensuu | Lappeenranta | K | | |
| Tupos | | Tup | | | 736+500 | Seinäjoki–Oulu | Kempele | K | | |
| Vehkala *) | Veckal | Veh | | | 16+000 | Vantaankoski–Havukoski | Vantaa | K | | |
| Viinikkala | Vinikby | Vkl | | | 22+590 | Vantaankoski–Havukoski | Vantaa | K | | |
| Virkamies *) | | Vms | | | 25+931 | Vantaankoski–Havukoski | Vantaa | K | | |
| Yllikkälä | | Yll | | | 268+500 | Kouvola–Joensuu | Lappeenranta | K | | |

*) in use from 1.7.2015

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri-korkeus | Laituriraiteiden lukumäärä | Mitoittava raidepituus (tavara-liikenne) | Sähkö-virran saanti | Sivulaituri, suurin pituus | Pääty-laituri | Kuormaus-kenttä | Nosturi | Poltto-aine | Henkilö-liiken-nettä | Tavara-liikennettä |
|--|--|--|--|--|--|---------------------|------------------------------|----------------------------|------------------------|----------|-------------|--|--------------------|
| Namn | Kortaste plattformslängden | Längsta plattformslängden | Plattformshöjden | Antal spår med plattform | Dimensionerande spårlängd (godstrafik) | Tillgång på elström | Sidoplattform | Plattform i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person-traffic | Godstrafik |
| Name | Min. platform length | Max. platform length | Platform height | Number of tracks with platforms | Design train length (freight traffic) | Power supply | Side loading platform length | End loading platform | Loading site | Crane | Fuel | Passenger traffic | Freight traffic |
| | [m] | [m] | [mm] | | [m] | [400 V, A] | [m] | | | [t] | | | |
| Ahonpää Asola (in use from 1.7.2015) Aviapolis (in use from 1.7.2015) Haimoo Jäniskorpi Kiilinkangas Kivistö (in use from 1.7.2015) Kuninkaanmäki Laajavuori (in use from 1.7.2015) Lapinkylä Leinelä (in use from 1.7.2015) Lentoasema (in use from 1.7.2015) Liminpuro Niska Pappilankangas Petas | 230 230 230 230 | 230 230 230 230 | 550 550 550 550 | 2 2 2 2 | | | | | | | | K K K K | |

| Nimi | Toinen nimi | Lyhenne | Kaupallinen nimi | Tyyppi | Km Hki | Rataosuus | Kunta | Kauko-ohjaus/ manuaalinen | Yksityisraiteita | Vaihtotyö- mahdollisuus |
|-------------|-----------------|-------------|-------------------|--------|---------|---|--------------|------------------------------|-------------------------------|-------------------------------|
| Namn | Namn på svenska | Förkortning | Kommersiellt namn | Typ | Km Hki | Banavsnitt | Kommun | Trafikledning | Privata spår- anläggningar | Möjlighet till växelarbeta |
| Name | Another name | Abbr. | Commercial name | Type | Km Hki | Section | Municipality | Traffic control | Private sidings | Shunting |
| Buslovskaja | | Bsl | | | 288+000 | Vainikkala raja – Viipuri | [m) | K | | |
| Haaparanta | Haparanda | Hpa | | | 888+130 | Tornio–raja – Boden | Haparanda | K | | |
| Kivijärvi | | Kiv | | | 759+800 | Vartius–raja – Kostamus | | K | | |
| Svetogorsk | | Stg | | | 338+200 | Imatrankoski–raja – Kamennogorsk (Antrea) | | K | | |
| Värtsilä | | Vrs | | | 553+300 | Niirala–raja – Matkaselkä | | K | | |

Transport Operating Regulations for Cross-Border Movements on the Line Section Tornio-Haaparanta

INTRODUCTION

Appendix 3 has expired. It is based on an agreement between the previous Finnish Rail Administration (now the Finnish Transport Agency) and the previous Swedish Rail Administration (now the Swedish Transport Administration), which has not been renewed at the time of printing this Network Statement. Appendix 3 will be completely updated as soon as the agreement has been renewed. Some terms have been brought up to date in this appendix.

The original regulations were laid down in cooperation between the Swedish Rail Administration's Northern Rail Region and the Finnish Rail Administration. The present administrations (the Swedish Transport Administration and the Finnish Transport Agency) will follow these regulations until a new agreement and new regulations enter into force.

At the national border the area between signals HP 6/3 and T 832 is called as a "Common zone", which is jointly reserved by the Swedish and Finnish traffic control operators.

In principle, only one train movement is allowed at a time within the common zone, with the exception of irregular situations, such as engine failure or accident.

SCOPE

The regulations are applicable to cross-border movements between Tornio and Haaparanta, and within the common zone.

REFERENCE DOCUMENTS

Sweden

| | |
|--------------|--|
| JvSFS 2008:7 | Transportstyrelsen/Handbok JTF/10-Växling Transportstyrelsen/Handbok JTF/3 H – Signaler, system H |
|--------------|--|

Finland

| | |
|-------------------|--|
| RVI/363/412/2008 | Junan jarrutuskyky sekä jarrujen tarkastus ja koettelu |
| RVI/301/412/2008 | Liikennöinti ilman JKV-veturilaitetta |
| RVI/1092/412/2009 | Liikennöinti ja ratatyö rautatiejärjestelmässä |
| RVI/295/411/2008 | Museoliikenne |
| RVI/1091/412/2009 | Rautatiejärjestelmän opasteista, opastimista ja liikennöintiin liittyvistä merkeistä |
| RVI/1090/412/2009 | Viestintä rautatiejärjestelmässä |
| RVI/725/412/2008 | Tavaravaunujen suurimmasta sallitusta kuormasta, junapainosta ja junan kokoonpanosta |

DEFINITIONS

| | |
|-------------------------------|---|
| Common zone Finnish | The area to be jointly reserved by the Swedish and traffic control operators and limited on the Swedish side by the 6/3 intermediate signal and on the Finnish side by the T 832 ground signal. |
| Cross-border movement | Movements entirely or partly operated within the common zone. |
| Movement | Refers to railway work and shunting. |
| Permission | Refers to permission to allow movement to begin. |
| Swedish movement | Shunting or railway work started in Sweden. |
| Finnish movement | Shunting or railway work started in Finland. |

GENERAL

The regulations are drafted in Swedish and Finnish with an identical content.

No movement is allowed within the common zone without the Swedish and Finnish traffic control operators having reserved the relevant section of line.

More than one movement is allowed in the common zone only in irregular situations, such as engine failure or accident. In such cases, the work of several movements shall be agreed at the time.

TORNIO-HAAPARANTA CROSS-BORDER MOVEMENTS

General

Movements are operated as specified in the Finnish RVI/1092/412/2009, as "shunting" operations, and as specified in the Swedish JvSFS 2008:7 JTF/10, as "shunting" or "small-wagon shunting" operations.

Messages and message transmission

The Finnish staff shall be in contact with the Finnish traffic control operators, who will deliver message to the Swedish traffic control operators.

The Swedish staff shall be in contact with the Swedish traffic control operators, who will deliver the message to the Finnish traffic control operators.

Haaparanta-Tornio

Prior to the commencement of a Swedish cross-border shunting operation Haaparanta-Tornio direction, permission by the traffic control operators in Haaparanta is required.

Prior to the commencement of a Finnish cross-border shunting operation Haaparanta–Tornio direction, permission by the traffic control operators in Tornio is required.

The traffic control unit that granted a permission shall be notified of the completion of the movement.

Tornio-Haaparanta

Prior to the commencement of a Finnish cross-border shunting operation Tornio-Haaparanta direction, permission by the traffic control operators in Tornio is required.

Prior to the commencement of a Swedish cross-border shunting operation Tornio-Haaparanta direction, permission by the traffic control operators in Haaparanta is required.

The traffic control unit that granted permission shall be notified of the completion of the movement.

RAILWAY WORK WITHIN THE COMMON ZONE

General

The Finnish staff shall be in contact with the Finnish traffic control operators transmitting possible messages to and from the Swedish traffic control operators.

The Swedish staff shall be in contact with the Swedish traffic control operators transmitting possible messages to and from the Finnish traffic control operators.

Swedish staff

The permission of the Haaparanta traffic control operators is required for work carried out by the Swedish staff within the common zone.

Prior to the granting permission, the Haaparanta and Tornio traffic control operators shall reserve the common zone.

The Haaparanta traffic control operators shall be notified of the completion of the work.

Finnish staff

The permission of the Tornio traffic control operators is required for work carried out by the Finnish staff within the common zone.

Prior to granting permission, the Tornio and Haaparanta traffic control operators shall reserve common zone.

The Tornio traffic control operators shall be notified of the completion of the work.

SAFETY CALLS AND DOCUMENTATION

Safety calls

The safety calls between the Swedish and Finnish traffic control operators shall be conducted either in Swedish or in Finnish.

There is a word list with translations in section 1.5, while section 1.6 includes examples of phrases to be used.

The safety calls shall be repeated.

Train Log

A train log shall be used according to the instructions and regulations of the traffic control.

RESERVATION OF COMMON ZONE

The reservation of the common zone shall be operated jointly by the Swedish and Finnish traffic control operators.

The clearance of the occupancy of the common zone shall be operated jointly by the Swedish and Finnish traffic control operators.

MAXIMUM PERMITTED SPEED

The maximum permitted speeds are specified in the speed signs, which are described in section 1.2.

ACCIDENTS

Any accident or risk of accident shall be reported to traffic control operators.

1.1 SIGNALS AND SIGNAL ASPECTS

The signals are applicable in conformity with the regulations of the country concerned.

Manual Signalling

The Swedish shunting staff shall implement manual signalling as specified in JvSFS 2008:7/10, irrespective of whether the activity takes place on the Swedish or Finnish side of the border.

The Finnish shunting staff shall implement manual signalling as specified in RVI/1091/412/2009, irrespective of whether the activity takes place on the Finnish or Swedish side of the border.

A "stop" signal shall always be followed, irrespective of whether it is operated in conformity with the Swedish or Finnish regulations.

Haaparanta – Tornio direction

From Finnish track, intermediate signal (main ground signal) 1/6, km 1310.845.



"Stop"



"Proceed"



"Proceed –
check clearance"



"Proceed
check
turnouts and
clearance"

From Swedish tracks, intermediate signal 5/6, km 1310.697.



"Stop"



"Proceed – check turnouts and clearance"

Swedish and Finnish tracks, intermediate signal 6/8, km 1311.006.



"Stop"



"Proceed"

Common track, Tornio T 832, km 886.8



"Stop"



"Proceed with caution"

Tornio – Haaparanta direction

No optical signals are used in Tornio for movements towards Sweden.

Intermediate signal 6/3, km 1311.012.




"Stop"



"Proceed –
check turnouts and clearance"

1.2 SPEED SIGNS

In **conformity** with RVI/1092/412/2009



*Maximum admissible speed
(example displaying max. 30 km/h)*


In **conformity** with JvSFS 2008:7/JTF/3 H



*Maximum admissible speed
(example displaying max. 30 km/h)*


1.3 STOP SIGNALLING

In **conformity** with JvSFS 2008:7/JTF/3 H




Read: Stop

In **conformity** with RVI/1092/412/2009




Read: Stop



Read: Danger (emergency stop)

1.4 DRAWING ON HAAPARANTA – TORNIO AREA



1.5 TRANSLATION TABLE

Should any language problems arise, the below table may be implemented.

Table 1. Translation table

| Swedish | Finnish | English |
|----------------------|-----------------------|------------------------|
| Växling | Vaihtotyö | Shunting work |
| Arbete | Työ | Work |
| Reserverad zon | Varaus | Reserved / Occupied |
| Upphävande | Peruuttaminen | Clearance of occupancy |
| Tågklarare | Junasuorittaja | Dispatcher |
| Trafikledning | Liikenteenohjaus | Traffic control |
| Station | Asema | Station |
| Fara | Vaara | Danger |
| Stoppsignal | Seis-opaste | Stop aspect |
| Passage av en signal | Opastimen ohittaminen | Passing of signal |
| Signal | Opastin/Opaste | Signal / Signal aspect |
| Repetera | Toistaa | Repeat |
| Rätt uppfattat | Oikein ymmärretty | Correctly read |

1.6 EXAMPLE PHRASES

Zone reservation request for shunting work

Swe: *Tågklareraren _____, reserverad zon Haparanda – Torneå, växling.*

Fin: Liikenteenohjaus _____, varaus Haaparanta – Tornio välille, vaihtotyö.

Eng: Traffic control _____, reservation Haaparanta – Tornio, shunting.

Zone reservation request for railway work

Swe: *Tågklareraren _____, reserverad zon Haparanda – Torneå, arbete.*

Fin: Liikenteenohjaus _____, varaus välille Haaparanta – Tornio, työ.

Eng: Traffic control _____, reservation Haaparanta – Tornio, work.

Clearance of occupied zone

Swe: *Tågklareraren _____, upphävande reserverad zon _____ - _____*

Fin: Liikenteenohjaus _____, varauksen peruuttaminen välille _____ - _____

Eng: Traffic control _____, clearance of occupied zone _____ - _____

Request for reservation in dangerous situation

Swe: *Tågklareraren _____, Fara Haparanda-Torneå.*

Fin: Liikenteenohjaus _____, vaara Haaparanta-Tornio.

Eng: Traffic control _____, danger Haaparanta-Tornio.

Permission to pass stop signal aspect, Haaparanta

Swe: *Tågklareraren Haparanda, medgivande att passera signal (ett-sex) och/eller (åtta-tre) och/eller (sex-åtta)*

Fin: Liikenteenohjaus Haaparanta, lupa ohittaa opastin (yksi-kuusi) ja/tai (kahdeksan-kolme) ja/tai (kuusi-kahdeksan)

Eng: Traffic control Haaparanta, permission to pass signal (one-six) and/or (eight/three) and/or (six-eight).

Permission to pass stop signal aspect, Tornio

Swe: *Tågklareraren Torneå, växling, medgivande att passera signal (T åtta-tre-två)*

Fin: Liikenteenohjaus Tornio, vaihtotyö, lupa ohittaa opastin (T kahdeksan-kolme-kaksi)

Eng: Traffic control Tornio, shunting, permission to pass signal (T eight—three-two).

Correctly read

Swe: *Rätt uppfattat*

Fin: Oikein ymmärretty

Eng: Correctly read.

Repeat

Swe: *Repetera*

Fin: Toista.

Eng: Repeat

The loading gauge (KU) refers to the space inside which the load on an open wagon shall remain, when the wagon is in the centre position on a straight, even track.




Figure 1. Principal dimensions of the loading gauge.

Use of the Loading Gauge

The loading gauge is valid on the whole rail network with the exceptions mentioned below.

The loading gauge may be used for wagons in which the wheelbase or the distance between bogie centres is max. 17.5 m and the length of the loading area of the wagon outside the wheelbase or the distance between bogie centres max. 0.2 times the length of the wheelbase or the distance between bogie centres. In other cases, loading shall be examined separately.

If there is a risk that the load may be displaced laterally outside the loading gauge during transportation, the width of the load shall be reduced correspondingly. If the displacement of the load may increase the height of some parts of the load so that they extend outside the loading gauge, the height of the load shall be reduced correspondingly.

If the load extends below the floor level of the wagon, the regulations concerning the vehicle gauge (LKU) are applied or the load is carried as a special transport.

Loading Gauge Restrictions

The bridges on the line section Helsinki (passenger railway yard) - Pasila (passenger railway yard) – Ilmala (depot) restrict the loading gauge. The loading gauge valid on these bridges is marked with dashed line (-----) on the loading gauge drawing (Figure 1).

On several industrial and other sidings, there are loading gauge restrictions, which shall be taken into account in local traffic operating.

Transports Exceeding the Loading Gauge

Lorries, lorry trailers and containers exceeding the loading gauge may be transported on separately specified line sections on the conditions laid down in the transport permit. Transports exceeding the loading gauge can be transported on the sections of line mentioned in the network description, according to the conditions based on the Finnish Transport Safety Agency's regulations.

Other transports exceeding the loading gauge are transported as special transports.

Structure Gauge

No fixed installations or equipment must be placed within the structure gauge envelope.

The form and dimensions of the structure gauge (ATU) on a straight track, on open line and in the railway yard are shown in Figure 1. The space required for the mounting of the catenary structure and for the passage of the pantograph on electrified lines is marked by the broken line D-E-F-G-H-L. The widths of the structure gauge in curves, restrictions and more detailed instructions are presented in the Ratatekniset ohjeet (RATO) publication, part 2 "Radan geometria" (Track geometry).




Figure 1. Principal dimensions of the structure gauge.

Effective Passing Clearance

The structure gauge is used as a guideline for building and mounting new structures and installations in the vicinity of the track. The structure gauge or the deviations from it constitute the so-called effective available structure gauge, i.e. the passing clearance, for special consignments. Information on the passing clearance is collected for each line section and continuously updated by the track maintainers.

Superstructure categories, EN categories derived from the superstructure categories and permitted speeds for different axle loads

Division of Lines into Line Categories

The lines are divided into line categories according to the superstructure as follows:

Table 1. Division of lines into line categories.

| Superstructure category | | Superstructure | | |
|---|--------------|------------------------|------------------------------|----------------------|
| Finnish Transport Infrastructure Agency | SFS-EN 15528 | Rails | Sleepers | Ballast |
| A | C4 | K30, K33 | wooden | gravel or equivalent |
| B ₁ | D4 | K43, 54 E1, K60, 60 E1 | wooden | gravel or equivalent |
| B ₂ | D4 | K43, K60 | wooden, concrete | railway ballast |
| C ₁ | D4 /E4 | 54 E1 | wooden, concrete before 1987 | railway ballast |
| C ₂ | D4/E4 | 54 E1 | concrete 1987 and after | railway ballast |
| D | D4/E4 | 60 E1 | concrete | railway ballast |

The border of the line category is marked in the middle of the station building in the traffic operating point, unless another point is indicated by the kilometre marking.

The line categories for sections of lines are also presented in Figure 1.

Responsibility of Track Maintainer

Track maintainer has the right to restrict the permitted axle load and speed depending on the condition of the track superstructure.

Table 2. Superstructure Categories and EN Categories derived from the superstructure categories of the main lines and permitted speeds for different axle loads.

| Section of line | Category | | Passenger trains | | Freight trains | | | |
|--|--------------------------|--------------|--------------------|------------|----------------|--------|--------|--------|
| | Finnish Transport Agency | SFS-EN 15528 | loco-motive hauled | motor cars | 160 kN | 200 kN | 225 kN | 250 kN |
| Helsinki–Riihimäki | | | | | | | | |
| Helsinki asema–Pasila asema | D | D4 | 80 | 80 | 80 | 80 | 80 | – |
| Pasila asema–Tikkurila asema läntisin raide | D | E4 | 160 | 160 | 120 | 120 | 100 | 100 |
| Pasila asema–Tikkurila asema läntinen keskiraide | D | E4 | 160 | 160 | 120 | 120 | 100 | 100 |
| Pasila asema–Tikkurila asema itäinen keskiraide | D | E4 | 120 | 120 | 120 | 120 | 100 | 100 |
| Pasila asema–Tikkurila asema itäisin raide | D | E4 | 120 | 120 | 120 | 120 | 100 | 100 |
| Tikkurila asema–Kerava asema läntisin raide | D | E4 | 200 | 200 | 120 | 120 | 100 | 100 |
| Tikkurila asema–Kerava asema läntinen keskiraide | D | E4 | 200 | 200 | 120 | 120 | 100 | 100 |
| Tikkurila asema–Kerava asema itäinen keskiraide ¹ | D | E4 | 120 | 120 | 120 | 120 | 100 | 100 |
| Tikkurila asema–Kerava asema itäisin raide ¹ | D | E4 | 120 | 120 | 120 | 120 | 100 | 100 |
| Kerava asema–Kytömaa läntisin raide | D | E4 | 120 | 120 | 120 | 120 | 100 | 100 |
| Kerava asema–Kytömaa läntinen keskiraide | D | E4 | 200 | 200 | 120 | 120 | 100 | 100 |
| Kerava asema–Kytömaa itäinen keskiraide | D | E4 | 200 | 200 | 120 | 120 | 100 | 100 |
| Kerava asema–Kytömaa itäisin raide | D | E4 | 120 | 120 | 120 | 120 | 100 | 100 |
| Kytömaa–Kyrölä | D | E4 | 200 | 200 | 120 | 120 | 100 | 100 |
| Kyrölä–Purola läntinen raide | D | E4 | 200 | 200 | 120 | 120 | 100 | 100 |
| Kyrölä–Purola keskiraide | D | E4 | 200 | 200 | 120 | 120 | 100 | 100 |
| Kyrölä–Purola itäinen raide | D | E4 | 120 | 120 | 120 | 120 | 100 | 100 |
| Purola–Riihimäki asema | D | E4 | 200 | 200 | 120 | 120 | 100 | 100 |

¹ From 1.7.2015 Tikkurila–Havukoski 80 km/h

| Section of line | Category | | Passenger trains | | Freight trains | | | |
|--|--------------------------|--------------|--------------------|------------|----------------|--------|--------|--------|
| | Finnish Transport Agency | SFS-EN 15528 | loco-motive hauled | motor cars | 160 kN | 200 kN | 225 kN | 250 kN |
| Riihimäki–Tampere | | | | | | | | |
| Riihimäki asema–Sääksjärvi | D | E4 | 200 | 200 | 120 | 120 | 100 | 100 |
| Sääksjärvi–Tampere tavara läntinen raide | D | E4 | 200 | 200 | 120 | 120 | 100 | 100 |
| Sääksjärvi–Tampere tavara keskiraide | D | E4 | 200 | 200 | 120 | 120 | 100 | 100 |
| Sääksjärvi–Tampere tavara itäinen raide | D | E4 | 100 | 100 | 100 | 100 | 100 | 100 |
| Tampere tavara–Tampere asema | D | E4 | 200 | 200 | 120 | 120 | 100 | 100 |
| Kerava–Sköldvik | | | | | | | | |
| Kytömaa–Sköldvik | D | D4 | 80 | 80 | 80 | 80 | 80 | – |
| Olli–Porvoo² | A | C4 | 35 | 50 | 35 | 20 | – | – |
| Kerava–Vuosaari | | | | | | | | |
| Kerava asema–Vuosaari | D | D4 | – | – | 80 | 80 | 80 | 80 |
| Helsinki–Turku satama | | | | | | | | |
| Helsinki asema–km 25,2 | D | D4 | 120 | 120 | 120 | 120 | 100 | – |
| km 25,2–km 29,0 | C ₁ | D4 | 120 | 120 | 120 | 120 | 100 | – |
| km 29,0–Kirkkonummi | D | D4 | 120 | 120 | 120 | 120 | 100 | – |
| Kirkkonummi–km 41,4 | D | D4 | 160 | 180 | 120 | 120 | 100 | – |
| km 41,4–Siuntio | C ₁ | D4 | 160 | 180 | 120 | 120 | 100 | – |
| Siuntio–km 55,8 | D | D4 | 160 | 180 | 120 | 120 | 100 | – |

² Museum line, Finnish Rail Agency regulation/museum traffic 295/411/2008

| Section of line | Category | | Passenger trains | | Freight trains | | | |
|--|--------------------------|--------------|--------------------|------------|----------------|--------|--------|--------|
| | Finnish Transport Agency | SFS-EN 15528 | loco-motive hauled | motor cars | 160 kN | 200 kN | 225 kN | 250 kN |
| km 55,8–km 59,2 | C ₁ | D4 | 160 | 180 | 120 | 120 | 100 | – |
| km 59,2–km 75,4 | D | D4 | 160 | 180 | 120 | 120 | 100 | – |
| km 75,4–km 80,4 | C ₁ | D4 | 160 | 180 | 120 | 120 | 100 | – |
| km 80,4–Karjaa | D | D4 | 160 | 180 | 120 | 120 | 100 | – |
| Karjaa–km 96,6 | D | D4 | 160 | 200 | 120 | 120 | 100 | – |
| km 96,6–km 103,6 | C ₁ | D4 | 160 | 180 | 120 | 120 | 100 | – |
| km 103,6–km 119,2 | C ₂ | D4 | 160 | 200 | 120 | 120 | 100 | – |
| km 119,2–km 121,3 | D | D4 | 160 | 200 | 120 | 120 | 100 | – |
| km 121,3–km 126,0 | C ₁ | D4 | 160 | 180 | 120 | 120 | 100 | – |
| km 126,0–km 130,8 | D | D4 | 160 | 180 | 120 | 120 | 100 | – |
| km 130,8–km 152,0 | D | D4 | 160 | 200 | 120 | 120 | 100 | – |
| km 152,0–km 158,0 | C ₁ | D4 | 160 | 200 | 120 | 120 | 100 | – |
| km 158,0–km 193,4 | C ₁ | D4 | 160 | 180 | 120 | 120 | 100 | – |
| km 193,4–Turku asema | D | D4 | 160 | 180 | 120 | 120 | 100 | – |
| Turku asema–Turku satama | C ₁ | D4 | 40 | 40 | 40 | 40 | 40 | – |
| Huopalahti–Vantaankoski³ | D | D4 | – | 120 | – | – | – | – |
| Turku–Uusikaupunki | | | | | | | | |
| Turku asema–Raisio (km 207,4) | C ₁ | D4 | 60 | 60 | 60 | 60 | 60 | – |
| Raisio (km 207,4)–Uusikaupunki | B ₁ | D4 | 60 | 60 | 60 | 60 | 50 | – |

³ From 1.7.2015 Huopalahti–Havukoski

| Section of line | Category | | Passenger trains | | Freight trains | | | |
|---------------------------------|--------------------------|--------------|--------------------|------------|-----------------|-----------------|-----------------|--------|
| | Finnish Transport Agency | SFS-EN 15528 | loco-motive hauled | motor cars | 160 kN | 200 kN | 225 kN | 250 kN |
| Raisio–Naantali | B ₁ | D4 | 50 | 50 | 50 | 50 | 50 | – |
| Uusikaupunki–Hangonsaari | | | | | | | | |
| Uusikaupunki–km 269,0 | C ₁ | D4 | – | – | 30 ⁴ | 30 ⁴ | 30 ⁴ | – |
| km 269,0–Hangonsaari | B ₁ | D4 | – | – | 30 ⁴ | 30 ⁴ | 30 ⁴ | – |
| Hyvinkää–Karjaa | | | | | | | | |
| Hyvinkää–km 133,1 | C ₁ | D4 | 80 | 80 | 80 | 80 | 80 | – |
| km 133,1–Kirkniemi | D | D4 | 80 | 80 | 80 | 80 | 80 | – |
| Kirkniemi–km 152,2 | D | E4 | 80 | 80 | 80 | 80 | 80 | 80 |
| km 152,2–Karjaa | C ₁ | E4 | 80 | 80 | 80 | 80 | 80 | 60 |
| Karjaa–Hanko | | | | | | | | |
| Karjaa–km 205,7 | D | E4 | 120 | 120 | 120 | 120 | 100 | 100 |
| km 205,7–Hanko-Pohjoinen | C ₁ | E4 | 60 | 60 | 60 | 60 | 60 | 60 |
| Hanko-Pohjoinen–Hanko asema | B ₁ | D4 | 35 | 35 | 35 | 35 | 35 | 35 |
| Toijala–Turku | | | | | | | | |
| Toijala–km 264,7 | D | D4 | 140 | 140 | 120 | 120 | 100 | – |
| km 264,7–Turku asema | D | D4 | 120 | 120 | 120 | 120 | 100 | – |
| Toijala–Valkeakoski | C ₁ | D4 | 50 | 50 | 50 | 50 | 50 | – |

⁴ Shunting traffic only.

| Section of line | Category | | Passenger trains | | Freight trains | | | |
|--|--------------------------|--------------|--------------------|------------|-----------------|-----------------|-----------------|--------|
| | Finnish Transport Agency | SFS-EN 15528 | loco-motive hauled | motor cars | 160 kN | 200 kN | 225 kN | 250 kN |
| Lielähti-Kokemäki | D | D4 | 140 | 140 | 120 | 120 | 100 | 100 |
| Kokemäki-Pori | | | | | | | | |
| Kokemäki-Harjavalta | D | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Harjavalta-Pori | D | E4 | 140 | 140 | 120 | 120 | 100 | 100 |
| Pori-Mäntyluoto | C ₁ | E4 | 70 | 70 | 70 | 70 | 70 | 50 |
| Mäntyluoto-Tahkoluoto | B ₂ | D4 | — | — | 50 ⁵ | 50 ⁵ | 50 ⁵ | — |
| Pori-Ruosniemi | B ₁ | D4 | — | — | 20 ⁵ | 20 ⁵ | 20 ⁵ | — |
| Kokemäki-Rauma | D | E4 | 100 | 100 | 100 | 100 | 100 | 80 |
| Tampere-Seinäjoki | | | | | | | | |
| Tampere asema-Lielähti | D | E4 | 120 | 120 | 120 | 120 | 100 | 80 |
| Lielähti-Pohjois-Louko | D | D4 | 200 | 200 | 120 | 120 | 100 | — |
| Pohjois-Louko-Seinäjoki asema läntinen raide | D | D4 | 200 | 200 | 120 | 120 | 100 | — |
| Pohjois-Louko-km 343,2 itäinen raide | D | D4 | 160 | 160 | 120 | 120 | 100 | — |
| km 343,2-Seinäjoki asema läntinen raide | D | D4 | 130 | 160 | 120 | 120 | 100 | — |
| Niinisalo-Parkano-Kihniö | | | | | | | | |

⁵ Shunting traffic only.

| Section of line | Category | | Passenger trains | | Freight trains | | | |
|---|--------------------------|--------------|--------------------|------------|-----------------|-----------------|-----------------|-----------------|
| | Finnish Transport Agency | SFS-EN 15528 | loco-motive hauled | motor cars | 160 kN | 200 kN | 225 kN | 250 kN |
| Niinisalo–Parkano | A | C4 | 30 | 30 | 30 | 30 | – | – |
| Parkano–Kihniö | A | C4 | 30 | 30 | 30 | 30 | – | – |
| Tampere–Jyväskylä | | | | | | | | |
| Tampere Järvensivu–Orivesi pohjoinen raide | D | E4 | 140 | 140 | 120 | 120 | 100 | 100 |
| Tampere Järvensivu–km 205,0 eteläinen raide | C ₂ | E4 | 140 | 140 | 120 | 120 | 100 | 100 |
| km 205,0–208,0 eteläinen raide | D | E4 | 140 | 140 | 120 | 120 | 100 | 100 |
| km 208,0–Orivesi eteläinen raide | C ₂ | E4 | 140 | 140 | 120 | 120 | 100 | 100 |
| Orivesi–km 287,4 | D | E4 | 120 | 140 | 120 | 120 | 100 | 80 |
| km 287,4–Jämsänkoski | D | E4 | 160 | 160 | 120 | 120 | 100 | 80 |
| Jämsänkoski–km 308,2 | D | D4 | 160 | 160 | 120 | 120 | 100 | – |
| km 308,2–km 312,6 | C ₁ | D4 | 160 | 160 | 120 | 120 | 100 | – |
| km 312,6–km 329,7 | D | D4 | 160 | 160 | 120 | 120 | 100 | – |
| km 329,7–km 332,8 | C ₁ | D4 | 160 | 160 | 120 | 120 | 100 | – |
| km 332,8–Jyväskylä km 340,0 | D | D4 | 160 | 160 | 120 | 120 | 100 | – |
| Jämsä–Kaipola | | | | | | | | |
| | B ₁ | E4 | – | – | 50 ⁶ | 50 ⁶ | 50 ⁶ | 50 ⁶ |
| Jyväskylä–Pieksämäki | | | | | | | | |
| Jyväskylä–Pieksämäki asema | C ₁ | D4 | 140 | 140 | 120 | 120 | 100 | – |
| Orivesi–Seinäjoki | | | | | | | | |
| Orivesi–Haapamäki | B ₁ | D4 | 100 | 100 | 100 | 70 | 50 | – |

⁶ Shunting traffic only.

| Section of line | Category | | Passenger trains | | Freight trains | | | |
|---------------------------|-----------------------------|--------------|--------------------|------------|-----------------|-----------------|-----------------|--------|
| | Finnish Transport Agency | SFS-EN 15528 | loco-motive hauled | motor cars | 160 kN | 200 kN | 225 kN | 250 kN |
| Haapamäki –Pihlajavesi | C ₂ | D4 | 100 | 100 | 100 | 100 | 100 | – |
| Pihlajavesi–Seinäjoki | B ₁ | D4 | 100 | 100 | 100 | 60 | 50 | – |
| Vilppula–Mänttä | B ₁ | D4 | 50 | 50 | 50 | 50 | 50 | – |
| Seinäjoki–Kaskinen | | | | | | | | |
| Seinäjoki–km 452,0 | B ₁ ⁷ | D4 | 80 | 80 | 80 | 60 | 50 | – |
| km 452,0–km 513,8 | B ₁ ⁷ | D4 | 60 | 60 | 60 | 50 | 40 | – |
| km 513,8–km 514,6 | B ₁ ⁷ | D4 | 30 | 30 | 30 | 30 | 30 | – |
| km 514,6–Kaskinen | B ₁ ⁷ | D4 | 80 | 80 | 80 | 60 | 50 | – |
| Seinäjoki–Vaasa | C ₂ | D4 | 120 | 120 | 120 | 120 | 100 | – |
| Vaasa–Vaskiluoto | A | C4 | – | – | 30 ⁸ | 30 ⁸ | 30 ⁸ | – |
| Seinäjoki–Oulu | | | | | | | | |
| Seinäjoki asema–km 431,5 | D | D4 | 140 | 140 | 120 | 120 | 100 | — |
| km 431,5–Lapua | C ₂ | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Lapua–km 459,0 | D | D4 | 160 | 200 | 120 | 120 | 100 | — |
| km 459,0–km 467,5 | D | D4 | 200 | 200 | 120 | 120 | 100 | — |
| km 467,5–km 482,8 | D | D4 | 190 | 200 | 120 | 120 | 100 | — |
| km 482,8–km 507,8 | D | D4 | 200 | 200 | 120 | 120 | 100 | — |

⁷ Bridge restriction, see Appendix 12

⁸ Shunting traffic only.

| Section of line | Category | | Passenger trains | | Freight trains | | | |
|--|--------------------------|--------------|--------------------|------------|-----------------|-----------------|-----------------|--------|
| | Finnish Transport Agency | SFS-EN 15528 | loco-motive hauled | motor cars | 160 kN | 200 kN | 225 kN | 250 kN |
| km 507,8–km 519,2 | D | D4 | 180 | 200 | 120 | 120 | 100 | — |
| km 519,2–km 524,6 | D | D4 | 190 | 200 | 120 | 120 | 100 | — |
| km 524,6–km 529,3 | D | D4 | 200 | 200 | 120 | 120 | 100 | — |
| km 529,3–km 550,5 | D | D4 | 170 | 200 | 120 | 120 | 100 | — |
| km 551,0–km 553,1 | C ₂ | D4 | 70 | 70 | 70 | 70 | 70 | — |
| km 553,1–Oulu asema | D | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Pännäinen–Pietarsaari | C ₂ | D4 | 60 | 60 | 60 | 60 | 60 | – |
| Pietarsaari–Alholma | C ₂ | D4 | – | – | 35 ⁹ | 35 ⁹ | 35 ⁹ | – |
| Kokkola–Ykspihlaja Kokkola–Ykspihlaja väliratapiha | B ₁ | D4 | 35 | 35 | 35 | 35 | 35 | – |
| Tuomioja–Raahe | C ₂ | D4 | 80 | 80 | 80 | 80 | 80 | – |
| Raahe–Rautaruukki | C ₂ | D4 | – | – | 35 ⁹ | 35 ⁹ | 35 ⁹ | – |
| Oulu–Laurila Oulu asema–Laurila | C ₂ | D4 | 140 | 140 | 120 | 120 | 100 | – |
| Kemi–Ajos | | | | | | | | |

⁹ Shunting traffic only.

| Section of line | Category | | Passenger trains | | Freight trains | | | |
|----------------------------|--------------------------|--------------|--------------------|------------|------------------|------------------|------------------|--------|
| | Finnish Transport Agency | SFS-EN 15528 | loco-motive hauled | motor cars | 160 kN | 200 kN | 225 kN | 250 kN |
| Kemi–Ajos km 861,8 | B ₁ | D4 | – | – | 50 ¹⁰ | 50 ¹⁰ | 50 ¹⁰ | – |
| Ajos km 861,8–km 863,5 | C ₂ | D4 | – | – | 50 ¹⁰ | 50 ¹⁰ | 50 ¹⁰ | – |
| Ajos km 863,5–867,1 | B ₁ | D4 | – | – | 50 ¹⁰ | 50 ¹⁰ | 50 ¹⁰ | – |
| Laurila–Kemijärvi | | | | | | | | |
| Laurila–Koivu | D | D4 | 140 | 140 | 120 | 120 | 100 | – |
| Koivu–Rovaniemi | D | D4 | 120 | 120 | 120 | 120 | 100 | – |
| Rovaniemi–Misi | C ₂ | D4 | 100 | 100 | 100 | 100 | 100 | – |
| Misi–km 1037,1 | C ₁ | D4 | 100 | 100 | 100 | 100 | 100 | – |
| km 1037,1–Kemijärvi | B ₁ | D4 | 100 | 100 | 100 | 60 | 50 | – |
| Kemijärvi–Isokylä | | | | | | | | |
| | B ₁ | D4 | 50 | 50 | 50 | 50 | 50 | – |
| Laurila–Tornio-raja | | | | | | | | |
| Laurila–Tornio asema | C ₂ | D4 | 120 | 120 | 120 | 120 | 100 | – |
| Tornio asema–Tornio-raja | C ₁ | D4 | 40 | 40 | 40 | 40 | 40 | – |
| Tornio–Röyttä | | | | | | | | |
| | B ₁ | D4 | – | – | 50 ¹⁰ | 50 ¹⁰ | 50 ¹⁰ | – |
| Tornio–Kolari | | | | | | | | |
| Tornio asema–km 885,6 | B ₂ | D4 | 80 | 80 | 80 | 80 | 80 | – |

¹⁰ Shunting traffic only

| Section of line | Category | | Passenger trains | | Freight trains | | | |
|------------------------------|--------------------------|--------------|--------------------|------------|------------------|------------------|------------------|--------|
| | Finnish Transport Agency | SFS-EN 15528 | loco-motive hauled | motor cars | 160 kN | 200 kN | 225 kN | 250 kN |
| km 885,6–Kolari | D | D4 | 100 | 100 | 80 | 80 | 80 | – |
| Kerava–Hakosilta | | | | | | | | |
| Kytömaa–Hakosilta | D | E4 | 200 | 220 | 120 | 120 | 100 | 100 |
| Riihimäki–Kouvola | | | | | | | | |
| Riihimäki asema–Hakosilta | D | D4 | 140 | 140 | 120 | 120 | 100 | – |
| Hakosilta–Lahti | D | E4 | 160 | 200 | 120 | 120 | 100 | 80 |
| Lahti–Kouvola asema | D | E4 | 200 | 200 | 120 | 120 | 100 | 100 |
| Lahti–Heinola | B ₁ | D4 | 60 | 60 | 60 | 60 | 50 | – |
| Lahti–Mukkula | B ₁ | D4 | – | – | 35 ¹¹ | 35 ¹¹ | 35 ¹¹ | – |
| Lahti–Loviisan satama | B ₁ | D4 | 60 | 60 | 60 | 60 | 50 | – |
| Kouvola–Pieksämäki | | | | | | | | |
| Kouvola asema–km 245,9 | D | D4 | 140 | 140 | 120 | 120 | 100 | – |
| km 245,9–Otava | D | D4 | 160 | 200 | 120 | 120 | 100 | – |
| Otava–Pieksämäki asema | D | D4 | 140 | 140 | 120 | 120 | 100 | – |

¹¹ Shunting traffic only.

| Section of line | Category | | Passenger trains | | Freight trains | | | |
|----------------------------------|--------------------------|--------------|--------------------|------------|------------------|------------------|------------------|--------|
| | Finnish Transport Agency | SFS-EN 15528 | loco-motive hauled | motor cars | 160 kN | 200 kN | 225 kN | 250 kN |
| Mynttilä–Ristiina | A | C4 | 50 | 50 | 50 | 35 | 20 | – |
| Otava–Otavan satama | B ₁ | D4 | – | – | 35 ¹² | 35 ¹² | 35 ¹² | – |
| Pieksämäki–Kontiomäki | | | | | | | | |
| Pieksämäki asema–Kuopio km 466,0 | D | D4 | 140 | 140 | 120 | 120 | 100 | – |
| Kuopio km 466,0–Toivala | D | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Toivala–Iisalmi | D | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Iisalmi–Murtomäki | C ₂ | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Murtomäki–Kajaani | C ₁ | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Kajaani–Kontiomäki | C ₁ | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Kajaani–Lamminniemi | B ₁ | D4 | – | – | 35 ¹² | 35 ¹² | 35 ¹² | – |
| Suonenjoki–Iisvesi | B ₁ | D4 | – | – | 35 ¹² | 35 ¹² | 35 ¹² | – |
| Murtomäki–Otanmäki | A | C4 | – | – | 50 ¹² | 40 ¹² | – | – |

¹² Shunting traffic only.

| Section of line | Category | | Passenger trains | | Freight trains | | | |
|---|--------------------------|--------------|--------------------|------------|------------------|------------------|------------------|--------|
| | Finnish Transport Agency | SFS-EN 15528 | loco-motive hauled | motor cars | 160 kN | 200 kN | 225 kN | 250 kN |
| Murtomäki–Talvivaara | C ₂ | D4 | 80 | 80 | 80 | 80 | 80 | – |
| Kouvola–Kuusankoski Kouvola asema–Kuusankoski | C ₁ | D4 | 50 | 50 | 50 | 50 | 50 | – |
| Iisalmi–Ylivieska Iisalmi–km 555,8 | C ₁ | D4 | 120 | 120 | 120 | 120 | 100 | – |
| km 555,8–km 613,1 | D | D4 | 120 | 120 | 120 | 120 | 100 | – |
| km 613,1–km 699,0 | C ₂ | D4 | 120 | 120 | 120 | 120 | 100 | – |
| km 699,0–Ylivieska | D | D4 | 120 | 120 | 120 | 120 | 100 | – |
| Pyhäkumpu erk. vh–Pyhäkumpu | B ₁ | D4 | 35 | 35 | 35 | 35 | 35 | – |
| Kontiomäki–Vartius Kontiomäki–km 662,2 | C ₁ | D4 | 80 | 80 | 80 | 80 | 80 | – |
| km 662,2–Vartius-raja | C ₂ | D4 | 80 | 80 | 80 | 80 | 80 | – |
| Kontiomäki–Ämmänsaari | A | C4 | 50 | 50 | 50 | 40 | – | – |
| Siilinjärvi–Viinijärvi | C ₂ | D4 | 100 | 100 | 100 | 100 | 100 | – |
| Sysmäjärvi–Vuonos | B ₂ | D4 | – | – | 35 ¹³ | 35 ¹³ | 35 ¹³ | – |

¹³ Shunting traffic only.

| Section of line | Category | | Passenger trains | | Freight trains | | | |
|--|--------------------------|--------------|--------------------|------------|----------------|--------|--------|--------|
| | Finnish Transport Agency | SFS-EN 15528 | loco-motive hauled | motor cars | 160 kN | 200 kN | 225 kN | 250 kN |
| Haapamäki–Jyväskylä | B ₁ | D4 | 100 | 100 | 100 | 70 | 50 | – |
| Jyväskylä–Äänekoski | C ₁ | D4 | 100 | 100 | 100 | 100 | 100 | – |
| Äänekoski–Haapajärvi | | | | | | | | |
| Äänekoski–Saarijärvi | C ₂ | D4 | 80 | 80 | 80 | 80 | 80 | – |
| Saarijärvi–Haapajärvi | A | C4 | 60 | 60 | 60 | 40 | – | – |
| Kouvola–Kotka | | | | | | | | |
| Kouvola tavara–Juurikorpi läntinen raide | D | D4 | 120 | 120 | 120 | 120 | 100 | – |
| Kouvola Oikoraide–Inkeroinen itäinen raide | C ₁ | D4 | 120 | 120 | 120 | 120 | 100 | – |
| Inkeroinen–Juurikorpi itäinen raide | D | D4 | 120 | 120 | 120 | 120 | 100 | – |
| Juurikorpi–Paimenportti | D | D4 | 120 | 120 | 120 | 120 | 100 | – |
| Paimenportti–Kotka asema | C ₁ | D4 | 80 | 80 | 80 | 80 | 80 | – |
| Kotka asema–Kotkan satama | C ₁ | D4 | 35 | 35 | 35 | 35 | 35 | – |
| Kotka Hovinsaari–Kotka Mussalo | C ₁ | D4 | 50 | 50 | 50 | 50 | 50 | – |
| Juurikorpi–Hamina | C ₁ | D4 | 100 | 100 | 100 | 100 | 100 | – |
| Luumäki–Vainikkala | | | | | | | | |
| Luumäki–Vainikkala asema | D | E4 | 120 | 140 | 120 | 120 | 100 | 80 |
| Vainikkala asema–Vainikkala-raja | D | E4 | 50 | 50 | 50 | 50 | 50 | 50 |

| Section of line | Category | | Passenger trains | | Freight trains | | | |
|--|--------------------------|--------------|--------------------|------------|------------------|------------------|------------------|--------|
| | Finnish Transport Agency | SFS-EN 15528 | loco-motive hauled | motor cars | 160 kN | 200 kN | 225 kN | 250 kN |
| Lappeenranta–Mustolan satama | C ₁ | D4 | – | – | 50 ¹⁴ | 50 ¹⁴ | 50 ¹⁴ | – |
| Imatra tavara–Imatrankoski-raja | D | D4 | 50 | 50 | 50 | 50 | 50 | – |
| Kouvola–Joensuu | | | | | | | | |
| Kouvola asema–Luumäki | D | E4 | 200 | 200 | 120 | 120 | 100 | 100 |
| Luumäki–km 395,5 | D | D4 | 140 | 140 | 120 | 120 | 100 | – |
| km 395,5–Säkäniemi | C ₂ | D4 | 140 | 140 | 120 | 120 | 100 | – |
| Säkäniemi–Joensuu Sulkulahti | D | D4 | 140 | 140 | 120 | 120 | 100 | – |
| Joensuu Sulkulahti–Joensuu asema | C ₁ | D4 | 90 | 90 | 90 | 90 | 90 | – |
| Niirala–Säkäniemi | | | | | | | | |
| Niirala raja–Säkäniemi | D | D4 | 100 | 100 | 100 | 100 | 100 | – |
| Joensuu–Ilomantsi | | | | | | | | |
| Joensuu Sulkulahti–Heinävaara | B ₂ | D4 | 60 | 60 | 60 | 60 | 60 | – |
| Heinävaara–km 660,4 | A | C4 | 50 | 50 | 50 | 40 | – | – |
| km 660,4–km 664,1 | B ₁ | D4 | 50 | 50 | 50 | 40 | – | – |
| km 664,1–km 678,4 | A | C4 | 50 | 50 | 50 | 40 | – | – |
| km 678,4–km 683,8 | B ₁ | D4 | 50 | 50 | 50 | 40 | – | – |
| km 683,8–km 687,9 | A | C4 | 50 | 50 | 50 | 40 | – | – |

¹⁴ Shunting traffic only.

| Section of line | Category | | Passenger trains | | Freight trains | | | |
|------------------------------|------------------------------|--------------|--------------------|------------|------------------|------------------|------------------|--------|
| | Finnish Transport Agency | SFS-EN 15528 | loco-motive hauled | motor cars | 160 kN | 200 kN | 225 kN | 250 kN |
| km 687,9–km 692,5 | B ₁ | D4 | 50 | 50 | 50 | 40 | – | – |
| km 692,5–Ilomantsi | A | C4 | 50 | 50 | 50 | 40 | – | – |
| Pieksämäki–Joensuu | C ₂ | D4 | 120 | 120 | 120 | 120 | 100 | – |
| Varkaus–Kommila | B ₂ | D4 | 50 | 50 | 50 | 50 | 50 | – |
| Huutokoski–Savonlinna | | | | | | | | |
| Huutokoski–Savonlinna asema | C ₂ | D4 | 80 | 80 | 80 | 80 | 80 | – |
| Savonlinna–Parikkala | | | | | | | | |
| Savonlinna asema–Parikkala | B ₂ ¹⁵ | D4 | 110 | 110 | 110 | 90 | 80 | – |
| Joensuu–Nurmes | | | | | | | | |
| Joensuu asema–Uimaharju | C ₂ | D4 | 120 | 120 | 120 | 120 | 100 | – |
| Uimaharju–Liekksa | C ₂ | D4 | 100 | 100 | 100 | 100 | 100 | – |
| Liekksa–Nurmes | B ₂ | D4 | 110 | 110 | 110 | 90 | 80 | – |
| Liekksa–Pankakoski | A | C4 | – | – | 30 ¹⁶ | 30 ¹⁶ | 20 ¹⁶ | – |

¹⁵ Bridge restriction, see Appendix 12

¹⁶ Shunting traffic only.

| Section of line | Category | | Passenger trains | | Freight trains | | | |
|------------------------------|--------------------------|--------------|--------------------|------------|------------------|------------------|------------------|--------|
| | Finnish Transport Agency | SFS-EN 15528 | loco-motive hauled | motor cars | 160 kN | 200 kN | 225 kN | 250 kN |
| Nurmes–Kontiomäki | | | | | | | | |
| Nurmes–Porokylä (km 787,9) | B ₂ | D4 | 80 | 80 | 80 | 80 | 80 | — |
| Porokylä (km 787,9)–km 807,5 | C ₂ | D4 | 80 | 80 | 80 | 80 | 80 | — |
| km 807,5–km 809,2 | C ₂ | D4 | 60 | 60 | 60 | 60 | 60 | — |
| km 809,2–km 810,2 | B ₂ | D4 | 60 | 60 | 60 | 60 | 60 | — |
| km 810,2–km 813,7 | C ₂ | D4 | 60 | 60 | 60 | 60 | 60 | — |
| km 813,7–Vuokatti | C ₂ | D4 | 80 | 80 | 80 | 80 | 80 | — |
| Vuokatti–Kontiomäki | B ₁ | D4 | 80 | 80 | 80 | 60 | 50 | — |
| Vuokatti–Lahnaslampi | B ₂ | D4 | — | — | 50 ¹⁷ | 50 ¹⁷ | 50 ¹⁷ | — |
| Oulu–Kontiomäki | | | | | | | | |
| Oulu Nokela–km 775,9 | C ₁ | D4 | 120 | 120 | 120 | 120 | 100 | — |
| km 775,9–km 787,4 | C ₁ | D4 | 140 | 140 | 120 | 120 | 100 | — |
| km 787,4–km 794,5 | C ₁ | D4 | 120 | 120 | 120 | 120 | 100 | — |
| km 794,5–km 809,3 | C ₁ | D4 | 130 | 130 | 120 | 120 | 100 | — |
| km 809,3–Utajärvi | C ₁ | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Utajärvi–km 878,2 | C ₁ | D4 | 140 | 140 | 120 | 120 | 100 | — |
| km 878,2–km 879,6 | C ₁ | D4 | 120 | 120 | 120 | 120 | 100 | — |
| km 879,6–km 893,7 | C ₁ | D4 | 140 | 140 | 120 | 120 | 100 | — |

¹⁷ Shunting traffic only.

| Section of line | Category | | Passenger trains | | Freight trains | | | |
|--------------------|--------------------------|--------------|--------------------|------------|----------------|--------|--------|--------|
| | Finnish Transport Agency | SFS-EN 15528 | loco-motive hauled | motor cars | 160 kN | 200 kN | 225 kN | 250 kN |
| km 893,7–Paltamo | C ₁ | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Paltamo–Kontiomäki | C ₁ | D4 | 140 | 140 | 120 | 120 | 100 | — |

Permitted Speed on Points and Track Crossings

Table 2. Permitted speed on points and track crossings

| | Superstructure category | | | | | |
|--|-------------------------|------------------|------------------|------------------|------------------|------------------|
| | A | B ₁ | B ₂ | C ₁ | C ₂ | D |
| Straight track | | | | | | |
| Single points, 60 E 1, short | 70 | 100 | 110 | 180 | 200 | 200 |
| Single points, 60 E 1, long | — | 100 | 110 | 180 | 200 | 220 |
| Single points, 54 E 1, long | 70 | 100 | 110 | 140 | 140 | 140 |
| Single points, other | 70 | 100 | 110 | 160 | 160 | 160 |
| Three-throw points | 70 | 100 | 110 | 120 | 120 | 120 |
| Diamond crossings | 35 | 90 | 90 | 90 | 90 | 90 |
| Track crossings | 35 ¹⁸ | 90 ¹⁸ | 90 ¹⁸ | 90 ¹⁸ | 90 ¹⁸ | 90 ¹⁸ |
| Deflecting section | | | | | | |
| Short points R = 165 m | 20 ¹⁸ | 20 ¹⁸ | 20 ¹⁸ | 20 ¹⁸ | 20 ¹⁸ | 20 ¹⁸ |
| Short points | 35 | 35 | 35 | 35 | 35 | 35 |
| Short points when axle load is over 225 kN | — | 10 | 20 | 20 | 20 | 35 |
| Long points | | | | | | |
| R = 500 m | — | — | — | 60 | 60 | 60 |
| R = 530 m | 70 | 70 | 70 | — | — | — |
| R = 900 m, when axle load max. 225 kN | — | 80 | 80 | 80 | 80 | 80 |
| R = 900 m, when axle load over 225 kN | — | — | — | 60 | 60 | 60 |
| R = 1600 m | — | — | — | 110 | 110 | 110 |
| R = 2500 m | — | — | — | 140 | 140 | 140 |
| R = 3000 m | — | — | — | — | — | 160 |
| Non-interlockeg points | | | | | | |
| Straight track and deflecting section | 30 ¹⁸ | 30 ¹⁸ | 30 ¹⁸ | 30 ¹⁸ | 30 ¹⁸ | 30 ¹⁸ |

¹⁸ Indicated with a speed board

| Päällysrakenneluokka Överbyggnadklass Superstructure Category | ei sähköistetty ikke-elektrifierad non-electrified | sähköistetty elektrifierad electrified | kiskotus rälser rails | pölkkyt sliprar sleepers | tukikerros ballast ballast |
|---|--|--|----------------------------------|--|--|
| A | — | | K30, K33 | puu trä wooden | raidesora tai vastaava ballastgrus eller motsvarande gravel or equivalent |
| B ₁ | — | — | K43, K60, K54 E1, 60 E1 | puu trä wooden | raidesora tai vastaava ballastgrus eller motsvarande gravel or equivalent |
| B ₂ | — | — | K43, K60 | puu, betoni trä, betong wooden, concrete | raidesepeli makadamballast railway ballast |
| C ₁ | — | — | 54 E1 | puu, betoni trä, betong wooden, concrete < 1987 | raidesepeli makadamballast railway ballast |
| C ₂ | — | — | 54 E1 | betoni betong concrete > 1987 | raidesepeli makadamballast railway ballast |
| D | — | — | 60 E1 | betoni betong concrete | raidesepeli makadamballast railway ballast |

..... Ei liikennöintiä
Trafikeras inte
No traffic

— — — — — Rakenteilla
Under byggnad
Under construction





Figure 1. Line categories and electrification.

Maintenance level on main lines

The maintenance levels on main lines used as the basis for railway maintenance are illustrated in figure 2.




Figure 2. Maintenance levels on main lines.

Electrification

Electrified railway lines

Helsinki asema-Turku satama
Huopalahti-Vantaankoski
Helsinki asema-Riihimäki asema
Kytömaa-Hakosilta
Kerava-Sköldvik
Riihimäki asema-Tampere asema
Toijala-Turku tavara
Tampere asema-Seinäjoki asema
Lielehti-Kokemäki
Kokemäki-Pori
Kokemäki-Rauma
Seinäjoki asema-Oulu asema
Oulu Nokela-Oulu Oritkari
Tuomioja-Raahe
Raahe-Rautaruukki
Riihimäki asema-Kouvola asema
Kouvola asema-Kuusankoski
Kouvola-Kotkan satama
Kotka Hovinsaari-Kotka Mussalo
Juurikorpi-Hamina
Kouvola asema-Joensuu asema
Luumäki-Vainikkala raja
Kouvola asema-Pieksämäki asema
Pieksämäki asema-Kontiomäki

Tampere-Jyväskylä
Jyväskylä-Pieksämäki asema
Oulu asema-Laurila
Laurila-Rovaniemi
Oulu Nokela-Kontiomäki
Kontiomäki-Vartius
Kerava-Vuosaari
Murtomäki-Talvivaara
Kokkola-Ykspihlaja
Seinäjoki-Vaasa
Rovaniemi-Kemijärvi (under construction)

The electrified railway lines are also illustrated in figure 1.




Figure 1. Electrified railway lines.

Signalling systems

The signalling systems used on the lines are represented in the figures in this appendix.

Lines with a section blocking system

Helsinki asema–Turku satama
Huopalahti–Vantaankoski
Hyvinkää–Hanko
Helsinki asema–Riihimäki asema
Kytömaa–Hakosilta
Kerava–Sköldvik
Riihimäki asema–Tampere asema
Toijala–Turku tavara
Tampere asema–Seinäjoki asema
Lielähti–Kokemäki
Kokemäki–Mäntyluoto
Kokemäki–Rauma
Seinäjoki asema–Oulu asema
Tuomioja–Raahe tracks 001 and 002
Riihimäki asema–Kouvola asema
Kouvola–Kymi track 001–(Kotka)
Juurikorpi–(Hamina)
Kouvola–Imatra tavara tracks 601-613– (Joensuu)
Luumäki–Vainikkala
Kouvola asema–Pieksämäki asema
Pieksämäki asema–Kuopio asema–Iisalmi
Tampere Järvensivu–Jyväskylä
Jyväskylä–Pieksämäki asema
Oulu asema–Laurila
Laurila–Tornio tracks 721, 722, 732, 741 and 742
Oulu Nokela–(Kontiomäki)
Säkäniemi–(Niirala)
Turku asema–Uusikaupunki
Kerava–Vuosaari
Vantaankoski–Havukoski (under construction, operational from 1 July 2015)

Double-track or multi-track railway lines with section blocking systems in both directions

Huopalahti–Vantaankoski

Kytömaa-Hakosilta

Pohjois-Louko-Ruha

Riihimäki asema–Luumäki

Tampere Järvensivu–Orivesi

system is under construction, are illustrated in figure 1.




Figure 1. Lines with a section blocking system.

Reporting use of the left-hand track

Usage of the left-hand track on the railway sections below must be reported in an advance report to the driver or in a report to the traffic control. The report to the driver must always include information about to what point the moving train is allowed to use the left-hand track.

Kouvola–Juurikorpi

Lines with a centralised traffic control system

Helsinki–Turku satama

Huopalahti–Vantaankoski

Hyvinkää–(Hanko)

Helsinki–Riihimäki

Kytömaa–Hakosilta

Kerava–Sköldvik

Riihimäki–(Tampere)

Toijala–Turku

(Tampere)–(Seinäjoki)

Lielähti–Kokemäki

Kokemäki–Mäntyluoto

Kokemäki–Rauma

(Seinäjoki)–(Ylivieska)–(Oulu)

Tuomioja–Raahe

Riihimäki–(Kouvola)

(Kouvola)–Kymi track 002–(Kotka)

Juurikorpi–(Hamina)

(Kouvola)–Luumäki

Luumäki–(Joensuu)

Luumäki–(Vainikkala)

(Kouvola)–Pieksämäki

Pieksämäki–(Kuopio)–Siilinjärvi tracks 001 and 002–(Iisalmi)

Siilinjärvi–Kemira

(Tampere)–Jyväskylä

Jyväskylä–Pieksämäki

(Oulu)–Laurila

Laurila–Tornio

(Oulu)–(Kontiomäki)

Säkäniemi–(Niirala)

Turku–Uusikaupunki

Kerava–Vuosaari

(Murtomäki)–Talvivaara

Vantaankoski–Havukoski (under construction, operational from 1 July 2015)

The centralised controlled railway sections and railway sections where centralised control is under construction are illustrated in figure 2.




Figure 2. Lines with a centralized traffic control system.

Lines with ATP

ATP is a class B system "ATP-VR/RHK-Junankulunvalvonta (JKV)" according to appendix B to the technical specification for interoperability relating to the control-command and signalling subsystem of the trans-European conventional rail system of 28 March 2006.

The following railway lines are equipped with ATP:

Helsinki asema–Turku satama
 Huopalahti–Vantaankoski
 Hyvinkää–Hanko asema
 Helsinki asema–Riihimäki asema
 Kytömaa–Hakosilta
 Kerava–Sköldvik
 Riihimäki asema–Tampere asema
 Toija–Turku tavara
 Tampere asema–Seinäjoki asema
 Lielähti–Kokemäki
 Kokemäki–Mäntyluoto
 Kokemäki–Rauma
 Seinäjoki asema–Vaasa
 Seinäjoki asema–Oulu asema
 Tuomioja–(Raahe)
 Riihimäki asema–Kouvola asema
 Paimenportti–(Kotka Mussalo)
 Juurikorpi–(Hamina)
 Kouvola asema–Joensuu asema
 Luumäki–(Vainikkala)
 Joensuu asema–Nurmes
 Kouvola asema–Pieksämäki asema
 Pieksämäki asema–Kontiomäki
 Pieksämäki–Joensuu asema
 Huutokoski–Parikkala
 Siilinjärvi–Viinijärvi
 Tampere–Jyväskylä
 Orivesi–Seinäjoki
 Haapamäki–Jyväskylä
 Jyväskylä–Pieksämäki asema
 Jyväskylä–Äänekoski
 Iisalmi–Ylivieska
 Oulu asema–Laurila
 Laurila–Tornio
 Tornio–Kolari
 Laurila–Kemijärvi
 Oulu Nokela–Kontiomäki
 Kontiomäki–Vartius
 Säkäniemi–(Niirala)

Turku–Uusikaupunki
 Kerava–Vuosaari
 Seinäjoki asema–Kaskinen
 Murtomäki–Talvivaara
 Vantaankoski–Havukoski (under construction, operational from 1 July 2015)

The railway lines with ATP and the lines where ATP is under construction are illustrated in figure 3.



(Seinäjäjoki)–Vaasa
(Joensuu)–Nurmes
(Iisalmi)–Kontiomäki
(Pieksämäki)–(Joensuu)
Huutokoski–(Parikkala)
(Siilinjärvi)–Viinijärvi
(Orivesi)–(Seinäjäjoki)
Haapamäki–(Jyväskylä)
(Jyväskylä)–Äänekoski
(Iisalmi)–(Ylivieska)
(Tornio)–Kolari
(Laurila)–Kemijärvi
Kontiomäki–Vartius
(Seinäjäjoki)–Kaskinen

The lines with a radio-controlled traffic system are illustrated in figure 4.




Figure 4. Lines with a radio-controlled traffic system.

Vibration-related speed restrictions

Table 1. Vibration-related speed restrictions.

| Operating Point | Operating Point | Km-stretch | Speed restriction |
|--------------------|-----------------|-----------------|-----------------------------------|
| Helsinki–Riihimäki | Jokela | 47+950–49+950 | ≥ 3000 ton trains 40 km/h |
| Kerava–Sköldvik | Kerava | 30+700–31+650 | ≥ 3000 ton trains 40 km/h |
| Kerava–Sköldvik | Nikkilä | 38+850–40+160 | all trains 40 km/h |
| Toijala–Turku | Loimaa | 208+000–210+600 | ≥ 3000 ton trains 40 km/h |
| Toijala–Turku | Turku | 271+900–273+700 | ≥ 3000 ton trains 40 km/h |
| Seinäjäki–Kaskinen | Kurikka | 450+500–452+000 | all trains 40 km/h |
| Seinäjäki–Oulu | Liminka | 726+900–729+200 | ≥ 3000 ton trains 50 km/h |
| Seinäjäki–Oulu | Kempele | 740+600–741+700 | ≥ 3000 ton trains 50 km/h |
| Riihimäki–Kouvola | Hollola | 116+200–118+500 | ≥ 3000 ton trains 40 km/h |
| Riihimäki–Kouvola | Lahti | 125+000–125+400 | ≥ 3000 ton trains 40 km/h |
| Riihimäki–Kouvola | Koria | 182+900–186+400 | ≥ 3000 ton trains 30 km/h |
| Kouvola–Kotka | Myllykoski | 201+500–203+100 | ≥ 3000 ton trains 40 km/h |
| Kouvola–Kotka | Keltakangas | 207+300–207+700 | <u>all freight trains 60 km/h</u> |
| Oulu–Kontiomäki | Oulu | 762+800–763+800 | ≥ 3000 ton trains 45 km/h |
| Oulu–Kontiomäki | Muhos | 786+000–790+000 | ≥ 3000 ton trains 60 km/h |
| Kerava–Lahti | Järvenpää | 35+800–36+200 | ≥ 3000 ton freight trains 40 km/h |
| Joensuu–Viinijärvi | Joensuu | 631+100–631+700 | ≥ 3000 ton freight trains 40 km/h |

Speed Limits due to Track Conditions

The information in table 1 for 2015 will be updated on 12 December 2014

[illegible]

Maximum Train Speeds in Tunnels

This table presents the tunnels with a speed limit. The speed limit of the track section in question is applied for all other tunnels.

Table 1. In the following tunnels there are operational restrictions due to the piston effect, when a train has one or more cars similar to those mentioned in the table.

| Tunnel | Km-location | Maximum speed [km/h] | | |
|-------------------|-----------------|----------------------|-------------|------------------|
| | | Single deck | Double deck | Motorised trains |
| Helsinki–Karjaa | | | | |
| Lillgård | 46+790–46+977 | 160 | 120 | 180 |
| Riddarbacken | 47+770–48+043 | 160 | 120 | 180 |
| Karjaa–Salo | | | | |
| Bäljens | 88+924–89+222 | 160 | 140 | 200 |
| Köpskog | 90+492–90+535 | 160 | 140 | 200 |
| Åminne | 92+391–92+492 | 160 | 140 | 200 |
| Högbacka | 94+365–94+565 | 160 | 140 | 200 |
| Kaivosmäki | 113+961–114+060 | 160 | 140 | 200 |
| Haukkamäki | 114+304–114+740 | 160 | 140 | 200 |
| Harmaamäki | 115+150–115+415 | 160 | 140 | 200 |
| Lemunmäki | 125+820–126+595 | 160 | 160 | 180 |
| Märjänmäki | 126+940–128+180 | 160 | 160 | 180 |
| Lavianmäki | 137+720–138+302 | 160 | 160 | 180 |
| Tottola | 139+084–139+615 | 160 | 120 | 180 |
| Salo–Turku | | | | |
| Halikko | 150+207–150+393 | 160 | 140 | 200 |
| Pepallonmäki | 152+420–152+951 | 160 | 140 | 200 |
| Orivesi–Jyväskylä | | | | |
| Keljonkangas II | 335+301–335+526 | 140 | 140 | 140 |

Table 2. Following tunnels have speed limits due to their condition.

| Section | Tunnel | Km-location | Maximum speed [km/h] |
|-----------------------|-------------|---------------------|----------------------|
| Jämsänkoski–Jyväskylä | Lahdenvuori | 308+200–312+700 | 120 |
| Jämsänkoski–Jyväskylä | Paasivuori | 330+100–332+700 | 120 |
| Haapamäki–Jyväskylä | Möykynmäki | 365+900– 366+400 | 50 |

Bridge-Related Restrictions

On the movable bridges mentioned below, axle loads and speed impose restrictions on the running of rail vehicles. The speed restrictions are indicated by speed signs.

Bridges with Weight Restrictions

- 1) Kyrönsalmi bridge on the Parikkala-Savonlinna section of line:
 - Axle load restriction 225 kN
 - Maximum permitted speed on the bridge is 20 km/h
- 2) Seinäjoki, Kyrönjoki, Nenätönjoki, Kainastonjoki, Teuvanjoki, Närpiönjoki and Kaskistensalmi bridges on the Seinäjoki-Kaskinen section of line.
 - Axle load restriction 225 kN
 - Maximum speed on the bridges is 60 km/h, unless a lower speed limit is otherwise ordered.

The axle loads mentioned here shall not be exceeded, and the excess load shall be unloaded at the station where it is discovered.

These regulations do not apply to 6- or 8-axle wagons built according to the Russian standard, which can be carried over the above-mentioned bridges only as special transport on the conditions laid down in the transport permit.

Movable Bridges

Table 1. Restrictions related to movable bridges.

| Bridge | Railway section | Permitted speed [km/h] |
|---------------|------------------------------------|------------------------|
| Pohja | Karjaa–Hanko | 50 |
| Kyrönsalmi | Savonlinna–Parikkala | 20 ¹ |
| Pirttiniemi | Pieksämäki–Joensuu | 40 ² |
| Taipale Canal | Pieksämäki–Joensuu | 30 ² |
| Pielisjoki | Pieksämäki–Joensuu, Joensuu–Nurmes | 50 |
| Tikkalansaari | Pieksämäki–Kontiomäki | 50 |
| Uimasalmi | Joensuu–Nurmes | 60 |
| Tahkoluoto | Mäntyluoto–Tahkoluoto | 50 |

¹ See bridges with weight restrictions.

² The bridge and the rail joints can be locked, in which case the permitted speed is 60 km/h.

Major track work and other track works affecting traffic in 2015

This appendix presents an estimate of the rail maintenance work that will be carried out during the 2015 timetable period and that may affect traffic. The information in the appendices may change once the details of funding and planning become clear. The updated list will be published on the Finnish Transport Agency website at http://portal.liikennevirasto.fi/sivu/www/ff/ammattiliikenteen_palvelut/rataverkolla_liikennointi/liikennesuunnittelu/ratatyot.

Table 1. Track work in 2015.

| Location | Affects traffic | Break description |
|--|-----------------|---|
| SOUTHERN FINLAND | | |
| Pasila: western additional track | x | Weeknight and weekend breaks |
| Pasila-Käpylä: new cross-over | x | Weeknight and weekend breaks |
| Leppävaara-Kirkkonummi station arrangements: Tolsa | x | Only one track in use and weekend breaks. Commuter traffic arrangements |
| Karjaa-Turku: repairs of areas with frost heave damages and soft soils, turnout replacements at Piikkiö and Pohjankuru | x | Weeknight breaks and long weekend breaks. Arrangements in passenger traffic in July |
| Karjaa-Hanko: repairs of areas with frost heave damage and soft soils | x | Weeknight and weekend breaks |
| Riihimäki: building of a triangle line | x | Weekend breaks |
| EASTERN FINLAND | | |
| Kuopio - Pieksämäki improvement, At Suonenjoki: work at traffic operating points | x | Weeknight and weekend breaks |
| Siilinjärvi-Iisalmi: repairs of areas with frost heave damage and soft soils | x | 9 h weekday track possessions |
| Jyväskylä-Pieksämäki: turnout replacements on the main line at Hankasalmi and Naarajärvi | x | 16 h weekend breaks, restrictions on passing track |
| Simpele: rock blasting operations | x | Simpele: track r001 will be closed to train traffic for two weeks |
| Parikkala-Savonlinna: sleeper replacement | x | 7 h track possession at night |
| Lieksa-Porokylä: sleeper replacement, turnout replacements at Nurmes and Höljää | x | 8 h track possession at night |
| Jyväskylä-Äänekoski: superstructure and drainage of Kangasvuori tunnel | x | Breaks for several days in connection with weekends or one continuous total break |

| Location | Affects traffic | Break description |
|---|-----------------|--|
| WESTERN FINLAND | | |
| Turku: building of underpass in Raunistula | x | Turku-Toijala 48 h weekend break |
| Riihimäki-Tampere: replacement of four turnouts at Kuurila | x | Weekend breaks. Only one track in use |
| Jämsä-Jyväskylä: Jämsänjoki railway bridge | x | Weekend break |
| Tampere Central Arena project: deck construction and turnout and track alterations at the southern end of the passenger railway yard | - | No works affecting traffic in 2015 |
| Turnout replacements on the main line between Tampere and Seinäjoki | x | Weekend breaks. Restrictions on passing track |
| Tampere-Seinäjoki: axle load level increased to 25t | x | Weekend breaks |
| Improvement of the service level on the section Seinäjoki-Oulu: double track between Ruha and Lapua and at Lapua traffic operating point | x | Seinäjoki-Kokkola 20 h traffic breaks at weekends in May–October. 24 h Midsummer break. No passenger service will be provided at Lapua traffic operating point for two months. |
| Seinäjoki-Vaasa: improvement of locations with frost heave damages | x | Weeknight breaks |
| Seinäjoki-Haapamäki: rail replacement Niinimaa-Tuuri 16 km | - | - |
| Seinäjoki-Haapamäki-Jyväskylä: Alavus, Inha, Keuruu: turnout replacements | x | 8–16 h track possessions |
| Seinäjoki-Haapamäki-Orivesi: measures to ensure a diversion route for freight traffic during the improvement of the line section Tampere-Jyväskylä | x | - |
| NORTHERN FINLAND | | |
| Improvement of the service level between Seinäjoki and Oulu: double track, work on bridges and safety control devices. Ballast replacement and work at traffic operating points | x | Kokkola-Ylivieska-Oulu: 14.5–20 h traffic breaks at weekends in May–November. 24 h Midsummer break. Ylivieska-Oulu 10 h daily traffic break Mo-Thu for 8 weeks |
| Ylivieska: joining of double track and renewal of railway bridges at Kalajoki. | x | Weekend breaks 14.5-20h. Only one track in use on Kalajoki railway bridge |
| Oulu-Kontiomäki superstructure renewal between Kivesjärvi and Oulu | x | 10-12 h track possessions Mon–Fri for 12 weeks. Weekend breaks. Coordination with the work between Seinäjoki and Oulu. |

| Location | Affects traffic | Break description |
|---|-----------------|--|
| NORTHERN FINLAND (continues) | | |
| Ii: underpass at Kuivajoentie | x | Weekend break |
| Tuomioja-Raahe: axle load level increased to 25t | x | Daily track possessions and weekend breaks |
| Kemijärvi-Isokylä improvement and triangle line | x | - |
| OTHER BREAKS | | |
| Investments to improve punctuality | x | - |
| Level crossing renewals and removals, station arrangements | x | - |
| Bridge, culvert and superstructure repairs | x | - |
| Railway bridges | x | - |
| Renewal and maintenance of the catenary system, droppers, foundations | x | - |
| Investments to promote availability of wood raw material | x | - |
| Maintenance track work and other ad hoc track works (for example snow related track works) | x | - |
| Replacement of individual turnouts at the following railway yards: Helsinki, Kouvola, Kotka, Hamina, Vainikkala, Harakka railway yard at Imatra, Joensuu, Pieksämäki, Tampere, Seinäjoki, Jyväskylä, Turku, Riihimäki, Oulu | x | 8–16 h track possessions |
| Walking inspections on tracks where the maximum allowed speed exceeds 140 km/h | x | - |
| Maintenance tamping of tracks and turnouts | x | - |
| Replacement of single sleepers and worn rails in curves | x | - |
| Rolling stock monitoring equipment | x | - |
| Removal of mandatory signals at sets of tracks | - | - |
| Introduction of the remote control system in Western Finland | - | - |
| Signal boxes on the section Riihimäki–Tampere–Seinäjoki | - | - |
| Kerava–Vuosaari: maintenance of Savio tunnel | x | 8 h track possession on Mondays |
| Helsinki–Riihimäki: catenary maintenance | x | 4 h track possessions on the first night between Monday and Tuesday of the month |

Map of Traffic Planning Areas

Coordination of track work and traffic according to the traffic planning areas shown on the map below.

CONTACTS

Traffic and track work co-ordinators (Finrail Oy)

Helsinki

liikennesuunnittelu.helsinki@vr.fi

Miikkola Reijo 040 866 3840

Lahtinen Hannu 040 866 3751

Hyppänen Pertti 040 862 0926

Tampere

liikennesuunnittelu.tampere@vr.fi

Jalanto Esko 040 863 0570

Kunelius Juha 040 863 1118

Järvinen Antti 040 863 0030

Oulu

liikennesuunnittelu.oulu@vr.fi

Meripaasi Sakari 040 864 5450

Tumelius Tommi 040 864 5446

Kouvola

liikennesuunnittelu.kouvola@vr.fi

Lahtinen Juha 040 863 4271

Lyytikäinen Juha 046 921 4815

Papunen Arto (Joensuu) 040 864 0379

Traffic and track work co-ordination areas

- Helsinki
- Tampere
- Oulu
- Kouvola




Figure 1. Traffic Planning Areas and Contacts (E-mail addresses will be updated in 2014.)

Passenger Information at the Stations of the State-owned Railway Network

The Finnish Transport Agency is responsible for the electronic and fixed passenger information at railway stations and in platform areas. The electronic information is produced in the passenger information and announcement system MIKU. MIKU generally produces information automatically, but in extraordinary situations the personnel of the Information Centre or the Traffic Control enters the data on the screens or give announcements.

The table below includes information about the passenger information at the traffic operating points. All changes to this table are updated on the Finnish Transport Agency's website

http://portal.liikennevirasto.fi/sivu/www/e/professionals/network_statement.

Table 1. Passenger information at operating points.

| Station | Swedish name of Station | No information system | Only an announcement system | Track displays | Main displays | Special displays (bridge and other displays) | LCD monitors | Tunnel displays | TFT displays | Total |
|------------------|-------------------------|-----------------------|-----------------------------|----------------|---------------|--|--------------|-----------------|--------------|------------|
| Total | | 13 | 66 | 425 | 38 | 6 | 46 | 3 | 395 | 992 |
| Alavus | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Dragsvik | | 1 | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Eläinpuiisto-Zoo | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Eno | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Espoo | Esbo | | | 6 | 0 | 0 | 0 | 0 | 18 | 24 |
| Haapajärvi | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Haapamäki | | | | 0 | 0 | 0 | 0 | 0 | 2 | 2 |
| Haarajoki | | | | 4 | 0 | 0 | 0 | 0 | 4 | 8 |
| Hankasalmi | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Hanko | Hangö | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Hanko-Pohjoinen | Hangö Norra | 1 | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Harjavalta | | | | 0 | 0 | 0 | 0 | 0 | 1 | 1 |
| Haukivuori | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Heinävesi | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Helsinki | Helsingfors | | | 19 | 4 | 2 | 10 | 3 | 38 | 76 |
| Herrala | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Hiekkaharju | Sandkulla | | | 4 | 0 | 0 | 0 | 0 | 2 | 6 |
| Hikiä | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Humppila | | | | 3 | 0 | 0 | 0 | 0 | 2 | 5 |
| Huopalahti | Hoplax | | | 8 | 0 | 0 | 4 | 0 | 6 | 18 |
| Hyvinkää | Hyvinge | | | 4 | 0 | 0 | 0 | 0 | 5 | 9 |

| Station | Swedish name of Station | No information system | Only an announcement system | Track displays | Main displays | Special displays (bridge and other displays) | LCD monitors | Tunnel displays | TFT displays | Total |
|-------------|-------------------------|-----------------------|-----------------------------|----------------|---------------|--|--------------|-----------------|--------------|-------|
| Hämeenlinna | Tavastehus | | | 5 | 2 | 0 | 0 | 0 | 4 | 11 |
| Höljääkä | | 1 | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Iisalmi | Idensalmi | | | 2 | 0 | 0 | 0 | 0 | 3 | 5 |
| Iittala | | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Ilmala | | | | 2 | 0 | 0 | 0 | 0 | 2 | 4 |
| Imatra | | | | 2 | 0 | 0 | 0 | 0 | 3 | 5 |
| Inkeroinen | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Inkoo | Ingå | | 1 | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Isokyrö | Storkyro | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Joensuu | | | | 3 | 0 | 0 | 0 | 0 | 6 | 9 |
| Jokela | | | | 3 | 0 | 0 | 0 | 0 | 2 | 5 |
| Jorvas | | | 1 | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Joutseno | | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Juupajoki | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Jyväskylä | | | | 3 | 2 | 0 | 10 | 0 | 0 | 15 |
| Jämsä | | | | 2 | 0 | 0 | 0 | 0 | 1 | 3 |
| Järvelä | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Järvenpää | Träskända | | | 7 | 0 | 0 | 0 | 0 | 4 | 11 |
| Kajaani | Kajana | | | 1 | 0 | 0 | 0 | 0 | 2 | 3 |
| Kannelmäki | Gamlas | | | 2 | 0 | 0 | 0 | 0 | 2 | 4 |
| Kannus | | | | 0 | 0 | 0 | 0 | 0 | 1 | 1 |
| Karjaa | Karis | | | 7 | 0 | 0 | 1 | 0 | 3 | 11 |
| Karkku | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Kauhava | | | | 1 | 0 | 0 | 0 | 0 | 0 | 1 |
| Kausala | | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Kauklahti | Köklax | | | 3 | 0 | 0 | 0 | 0 | 1 | 4 |
| Kauniainen | Grankulla | | | 3 | 0 | 0 | 0 | 0 | 2 | 5 |
| Kausala | | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Kemi | | | | 2 | 0 | 0 | 0 | 0 | 2 | 4 |
| Kemijärvi | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Kera | | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Kerava | Kervo | | | 10 | 0 | 0 | 0 | 0 | 11 | 21 |
| Kerimäki | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Kesälahti | | | | 1 | 0 | 0 | 0 | 0 | 0 | 1 |
| Keuruu | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Kilo | | | | 4 | 0 | 0 | 0 | 0 | 0 | 4 |
| Kirkkonummi | Kyrkslätt | | | 3 | 0 | 0 | 0 | 0 | 6 | 9 |
| Kitee | | | | 1 | 0 | 0 | 0 | 0 | 0 | 1 |
| Kiuruvesi | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Kohtavaara | | 1 | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Koivuhovi | Björkgård | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Koivukylä | Björkby | | | 4 | 0 | 0 | 0 | 0 | 1 | 5 |

| Station | Swedish name of Station | No information system | Only an announcement system | Track displays | Main displays | Special displays (bridge and other displays) | LCD monitors | Tunnel displays | TFT displays | Total |
|---------------|-------------------------|-----------------------|-----------------------------|----------------|---------------|--|--------------|-----------------|--------------|-------|
| Kokemäki | Kumo | | | 0 | 0 | 0 | 0 | 0 | 1 | 1 |
| Kokkola | Karleby | | | 6 | 0 | 0 | 0 | 0 | 2 | 8 |
| Kolari | | | | 0 | 0 | 0 | 0 | 0 | 2 | 2 |
| Kolho | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Kontiomäki | | | | 0 | 0 | 0 | 0 | 0 | 1 | 1 |
| Koria | | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Korso | | | | 4 | 0 | 0 | 0 | 0 | 2 | 6 |
| Kotka | | | | 0 | 0 | 0 | 0 | 0 | 1 | 1 |
| Kotkan satama | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Kouvola | | | | 13 | 2 | 0 | 5 | 0 | 2 | 22 |
| Kuopio | | | | 4 | 0 | 0 | 0 | 0 | 6 | 10 |
| Kupittaa | Kuppis | | | 4 | 0 | 2 | 2 | 0 | 4 | 12 |
| Kylänlahti | | 1 | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Kymi | Kymmene | 1 | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Kyminlinna | | 1 | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Kyrölä | | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Käpylä | Kottby | | | 4 | 0 | 0 | 0 | 0 | 2 | 6 |
| Lahti | Lahtis | | | 12 | 2 | 0 | 0 | 0 | 5 | 19 |
| Laihia | Laihela | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Lapinlahti | | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Lappeenranta | Villmanstrand | | | 3 | 0 | 0 | 6 | 0 | 1 | 10 |
| Lappila | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Lappohja | Lappvik | 1 | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Lapua | Lappo | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Lempäälä | | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Leppävaara | Alberga | | | 8 | 0 | 0 | 1 | 0 | 5 | 14 |
| Liekksa | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Lievestuore | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Loimaa | | | | 1 | 0 | 0 | 0 | 0 | 1 | 2 |
| Louhela | Klippsta | | | 2 | 0 | 0 | 0 | 0 | 2 | 4 |
| Luoma | Bobäck | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Lusto | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Malmi | Malm | | | 4 | 0 | 0 | 0 | 0 | 8 | 12 |
| Malminkartano | Malmgård | | | 2 | 0 | 0 | 0 | 0 | 4 | 6 |
| Mankki | Mankby | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Martinlaakso | Mårtensdal | | | 4 | 0 | 0 | 0 | 0 | 2 | 6 |
| Masala | Masaby | | | 4 | 0 | 0 | 0 | 0 | 0 | 4 |
| Mikkeli | St. Michel | | | 5 | 0 | 2 | 0 | 0 | 7 | 14 |
| Misi | | 1 | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Mommila | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Muhos | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Muurola | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

| Station | Swedish name of Station | No information system | Only an announcement system | Track displays | Main displays | Special displays (bridge and other displays) | LCD monitors | Tunnel displays | TFT displays | Total |
|------------------|-------------------------|-----------------------|-----------------------------|----------------|---------------|--|--------------|-----------------|--------------|-------|
| Myllykoski | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Myllymäki | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Myyrmäki | Myrbacka | | | 2 | 0 | 0 | 0 | 0 | 1 | 3 |
| Mäkkylä | | | | 2 | 0 | 0 | 0 | 0 | 2 | 4 |
| Mäntsälä | | | | 4 | 0 | 0 | 0 | 0 | 4 | 8 |
| Mäntyharju | | | | 4 | 0 | 0 | 0 | 0 | 1 | 5 |
| Nastola | | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Nivala | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Nokia | | | 1 | 0 | 0 | 0 | 0 | 0 | 1 | 1 |
| Nuppulinna | | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Nurmes | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Oitti | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Orivesi | | | | 2 | 0 | 0 | 0 | 0 | 1 | 3 |
| Orivesi keskusta | | | | 0 | 0 | 0 | 0 | 0 | 1 | 1 |
| Oulainen | | | | 3 | 0 | 0 | 0 | 0 | 1 | 4 |
| Oulu | Uleåborg | | | 6 | 2 | 0 | 0 | 0 | 5 | 13 |
| Oulunkylä | Äggelby | | | 4 | 0 | 0 | 0 | 0 | 4 | 8 |
| Paimenportti | | 1 | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Paltamo | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Parikkala | | | | 3 | 0 | 0 | 0 | 0 | 2 | 5 |
| Parkano | | | | 3 | 0 | 0 | 0 | 0 | 2 | 5 |
| Parola | | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Pasila | Böle | | | 38 | 4 | 0 | 1 | 0 | 55 | 98 |
| Pello | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Petäjävesi | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Pieksämäki | | | | 9 | 2 | 0 | 0 | 0 | 3 | 14 |
| Pihlajavesi | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Pitäjänmäki | Sockenbacka | | | 4 | 0 | 0 | 0 | 0 | 4 | 8 |
| Pohjois-Haaga | Norra Haga | | | 2 | 0 | 0 | 0 | 0 | 2 | 4 |
| Pori | Björneborg | | | 0 | 0 | 0 | 0 | 0 | 3 | 3 |
| Puistola | Parkstad | | | 4 | 0 | 0 | 0 | 0 | 4 | 8 |
| Pukinmäki | Bocksbacka | | | 4 | 0 | 0 | 0 | 0 | 3 | 7 |
| Punkaharju | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Purola | | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Pyhäsalmi | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Pännäinen | Bennäs | | | 0 | 0 | 0 | 0 | 0 | 1 | 1 |
| Pääskylahti | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Rekola | Räckhals | | | 2 | 0 | 0 | 1 | 0 | 0 | 3 |
| Retretti | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Riihimäki | | | | 8 | 6 | 0 | 3 | 0 | 11 | 28 |
| Rovaniemi | | | | 3 | 0 | 0 | 0 | 0 | 4 | 7 |
| Runni | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

| Station | Swedish name of Station | No information system | Only an announcement system | Track displays | Main displays | Special displays (bridge and other displays) | LCD monitors | Tunnel displays | TFT displays | Total |
|----------------|-------------------------|-----------------------|-----------------------------|----------------|---------------|--|--------------|-----------------|--------------|-------|
| Ruukki | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Ryttylä | | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Salo | | | | 6 | 0 | 0 | 0 | 0 | 3 | 9 |
| Santala | Sandö | 1 | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Saunakallio | | | | 4 | 0 | 0 | 0 | 0 | 0 | 4 |
| Savio | | | | 4 | 0 | 0 | 0 | 0 | 1 | 5 |
| Savonlinna | Nyslott | | | 0 | 0 | 0 | 0 | 0 | 1 | 1 |
| Seinäjäki | | | | 9 | 2 | 0 | 0 | 0 | 7 | 18 |
| Siilinjärvi | | | | 1 | 0 | 0 | 0 | 0 | 1 | 2 |
| Simpele | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Siuntio | Sjundeå | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Skogby | | 1 | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Sukeva | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Suonenjoki | | | | 0 | 0 | 0 | 0 | 0 | 1 | 1 |
| Tammisaari | Ekenäs | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Tampere | Tammerfors | | | 15 | 2 | 0 | 0 | 0 | 27 | 44 |
| Tapanila | Mosabacka | | | 4 | 0 | 0 | 0 | 0 | 2 | 6 |
| Tavastila | | 1 | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Tervajoki | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Tervola | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Tikkurila | Dickursby | | | 15 | 0 | 0 | 0 | 0 | 26 | 41 |
| Toijala | | | | 4 | 0 | 0 | 0 | 0 | 3 | 7 |
| Tolsa | Tolls | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Tornio-Itäinen | Torneå Östra | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Tuomarila | Domsby | | | 3 | 0 | 0 | 0 | 0 | 0 | 3 |
| Turenki | | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Turku | Åbo | | | 9 | 2 | 0 | 3 | 0 | 3 | 17 |
| Turku satama | Åbo hamn | | | 2 | 0 | 0 | 0 | 0 | 3 | 5 |
| Tuuri | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Uimaharju | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Utajärvi | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Uusikylä | | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Vaala | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Vaasa | Vasa | | | 2 | 2 | 0 | 0 | 0 | 4 | 8 |
| Vainikkala | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Valimo | Gjuteriet | | | 4 | 0 | 0 | 0 | 0 | 1 | 5 |
| Vammala | | | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 |
| Vantaankoski | Vandaforsen | | | 2 | 0 | 0 | 0 | 0 | 2 | 4 |
| Varkaus | | | | 0 | 0 | 0 | 0 | 0 | 3 | 3 |
| Vihanti | | | | 1 | 0 | 0 | 0 | 0 | 1 | 2 |
| Vihtari | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Viiala | | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |

| Station | Swedish name of Station | No information system | Only an announcement system | Track displays | Main displays | Special displays (bridge and other displays) | LCD monitors | Tunnel displays | TFT displays | Total |
|------------|-------------------------|-----------------------|-----------------------------|----------------|---------------|--|--------------|-----------------|--------------|-------|
| Viinijärvi | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Villähde | | | | 2 | 0 | 0 | 0 | 0 | 0 | 2 |
| Vilppula | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Vuonisahti | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Ylistaro | | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Ylitornio | Övertorneå | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Ylivieska | | | | 0 | 0 | 0 | 0 | 0 | 2 | 2 |
| Ähtäri | Etseri | | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

GSM-R (RAILI) Network

The Finnish Transport Agency's GSM-R network, RAILI for short, acts as the railways' integrated communication system, serving primarily traffic controllers, drivers and train guards as well as shunting managers and those responsible for track work. The network covers track and railway yards over a distance of about 5,000 km. More information is available in chapter 3.3.3.4 (Communications Systems) of the Network Statement as well as on the Finnish Transport Agency's website <http://www.liikennevirasto.fi>.




Figure 1. The Finnish GSM-R Network

What to consider when using the RAILI network

External interferences still affect the use of RAILI phones. The base stations for commercial mobile networks which cover the railway area are blocking the RAILI phone receiver by interfering with or even obstructing all communication in the disturbance area.

In traffic safety duties it is best to have a spare phone at hand, the contact information of which is known to the traffic control.

The contact information of the railway operational communication and the emergency contact information of the traffic control can be found on the RAILI list, which is managed by the Finnish Transport Agency on its Extranet site:

http://portal.liikennevirasto.fi/sivu/www/f/urakoitsijat_suunnittelijat/konsultit/Extranet

Rolling Stock Speed in the Railway Network

SPEED DEPENDING ON THE ROLLING STOCK

The rolling stock for which the Finnish Transport Safety Agency has granted a commissioning licence, which is valid until further notice, has been listed in the tables below. As soon as the above mentioned commissioning licence has been granted, the rolling stock type will be entered into the respective table.

Table 1. Maximum speed allowable for locomotives and train sets

| Superstructure category | | | | | | |
|-------------------------|--------------------|----------------|-----------------|------------------|------------------|------------------|
| Series | A ¹ | B ₁ | B ₂ | C ₁ | C ₂ | D |
| Dv12 | 50 ^{2, 3} | 100 | 110 | 125 | 125 | 125 |
| Dv17 9810 6003070-8 | 30 | 40 | 40 | 40 | 40 | 40 |
| Dr14, added weight | – | 50 | 75 ⁴ | 75 ⁴ | 75 ⁴ | 75 ⁴ |
| Dr16 | – | 70 | 110 | 140 ⁵ | 140 ⁵ | 140 ⁵ |
| Dr17 9810 6007001-9 | 30 | 65 | 65 | 65 | 65 | 65 |
| Dr17 9810 6006010-1 | – | 50 | 50 | 50 | 50 | 50 |
| Dr25 9810 8029002-7 | 20 | 25 | 25 | 25 | 25 | 25 |
| Dr25 9810 8129002-6 | 20 | 25 | 25 | 25 | 25 | 25 |
| Dr25 9810 8129003-4 | 20 | 25 | 25 | 25 | 25 | 25 |
| Dr35 9810 8039011-6 | 20 | 60 | 60 | 60 | 60 | 60 |
| Dr35 9810 8139005-7 | – | 30 | 30 | 30 | 30 | 30 |
| Dr35 9810 8139006-5 | – | 30 | 30 | 30 | 30 | 30 |
| Dr35 9810 8039013-2 | 35 | 60 | 60 | 60 | 60 | 60 |
| Dr45 9810 8049001-5 | – | 60 | 60 | 60 | 60 | 60 |
| Sr1 | – | 80 | 100 | 140 | 140 | 140 |
| Sr2 | – | 80 | 100 | 180 ⁶ | 200 | 210 |
| Train sets | | | | | | |
| Sm1, Sm2 | – | 90 | 110 | 120 | 120 | 120 |
| Sm3 | – | 100 | 110 | 180 | 200 | 220 |
| Sm4 | – | 90 | 110 | 160 | 160 | 160 |
| Sm5 | – | 90 | 110 | 160 | 160 | 160 |
| Sm6 | – | 100 | 110 | 180 | 200 | 220 |
| Dm12 | 50 | 100 | 110 | 120 | 120 | 120 |

¹ For tracks belonging to superstructure category A, see USE OF LOCOMOTIVES ON TRACKS BELONGING TO SUPERSTRUCTURE CATEGORY A.

² Max. speed 40 km/h in curves with a radius under 600 m. Max. speed 60 km/h on the line section Äänekoski-Haapajärvi.

³ 20 km/h in the deflecting section of K30 turnouts.

⁴ 80 km/h when hauled

⁵ 135 km/h without wagons, either on its own or with double heading.

⁶ 160 km/h without wagons. 160 km/h with double heading.

SMALL-POWER LOCOMOTIVES AND TRACK MOTOR CARS

(Towing speed in brackets, if it differs from the maximum speed when self-propelled)

| Superstructure category | | | | |
|--|-----------------|----------------------|----------------------|-------------------------------------|
| Series | A ¹ | B ₁ | B ₂ | C ₁ , C ₂ , D |
| Tve1 | 30 (60) | 30 (80) | 30 (80) | 30 (80) |
| Tve2 | 45 (60) | 45 (80) | 45 (80) | 45 (80) |
| Tve4 | 35 | 60 | 80 | 80 |
| Tve5 | 20 (50) | 20 (50) | 20 (50) | 20 (50) |
| Tka3-6 | 60 | 60 (80) | 60 (80) | 60 (80) |
| Tka7, numbers 168-238, 243-247 | 60 | 80 | 80 | 80 |
| Tka7, with snow plough, numbers 168-238 | 35 ⁷ | 60 ⁷ (80) | 60 ⁷ (80) | 60 ⁷ (80) |
| Tka7, numbers 239-242 | 50 | 80 | 80 | 80 |
| Tka7, with snow plough, numbers 239-247 | 35 ⁷ | 60 ⁷ (80) | 60 ⁷ (80) | 60 ⁷ (80) |
| Tka7, with welding container, numbers 168-238, 243-247 | 35 | 60 | 60 | 80 |
| Tka8 | 35 | 60 | 80 | 80 |
| Tka9 numbers 91901 | 20 ⁸ | 50 ⁸ | 70 ⁸ | 70 ⁸ |
| Otso4 numbers 920001 | 20 ⁹ | 45 | 45 | 45 |

MAXIMUM ALLOWABLE SPEED FOR SELF-PROPELLED MACHINERY

(Hauling speed in brackets, if the machine can be coupled to the train and the hauling speed differs from the above mentioned)

| Superstructure category | | | | |
|---------------------------------|------------------|----------------|----------------|-------------------------------------|
| Series | A | B ₁ | B ₂ | C ₁ , C ₂ , D |
| Track inspection cars | | | | |
| Et number 66 | 20 ¹⁰ | 60 | 60 | 100 |
| Ttr1 number 51 | 60 | 80 | 120 | 120 |
| Snow brooms | | | | |
| Tlh number 741 ¹¹ | 50 | 60 | 60 | 60 |
| Snow ploughs | | | | |
| Tla 90109691001-2 | 35 | 60 | 60 | 60 |
| Rail planing machines | | | | |
| Tkh number 894 ¹¹ | 60 | 80 | 80 | 80 |
| Track renewal machines | | | | |
| Trk number 870 | 20 | 20 (50) | 20 (80) | 20 (100) |
| Ballast ploughs | | | | |
| Tsl numbers 880, 882, 884, 885, | 70 | 80 | 80 | 80 |

⁷ The maximum snow-ploughing speed is specified in the machine operator's manual.

⁸ Hauling according to the manufacturer's instructions.

⁹ 20 km/h on sidings which belong to superstructure category A.

¹⁰ Same as the maximum speed on the section in question, as assessed by a railway technology specialist taking the measurements, and a representative of the local maintenance entrepreneur.

¹¹ Wheel diameter max. 790 mm, which necessitates caution in diamond crossings with slips.

| Superstructure category | | | | |
|---|-----------------------|---|-----------------------|-----------------------|
| 890 ¹¹ | | | | |
| Tsl number 883 ¹¹ | 35 | 50 | 60 | 60 |
| Tsl number 888 ¹¹ | 50 | 60 | 60 | 80 |
| Tsl number 889 ¹¹ | 20 | 50 | 80 | 80 |
| Tsl number 91021 | 20 | 70 | 70 | 70 |
| Ballast cleaning machines | | | | |
| Tsp numbers 891, 893 | 20 | 60 | 80 | 80 |
| Tsp number 892 | 50 | 80 | 80 | 80 |
| Multi-purpose machines | | | | |
| Ttm1 number 91101 | 20 ¹² | 50 | 70 | 70 |
| Tamping machines | | | | |
| Ttk1 ¹¹ numbers 801–803, 821, 823, 831, 91042 | 60 | 80 | 80 | 80 |
| Ttk1 ¹¹ number 818–820 | 25 (50) ¹³ | 25 (50) ¹³ Virhe. Kirjanmerkkiä ei ole määritetty. | 25 (50) ¹³ | 25 (50) ¹³ |
| Ttk1 ¹¹ numbers 822, 824–829 | 50 | 50 (80) | 50 (80) | 50 (80) |
| Ttk1 ¹¹ number 830 | 60 | 85 (90) | 85 (90) | 85 (90) |
| Ttk1 ¹¹ numbers 832, 833 | 50 | 80 | 80 | 80 |
| Ttk1 number 834 | 50 ¹⁴ | 80 | 80 | 80 |
| Ttk1 ¹¹ number 91041 | 60 | 60 | 60 | 60 |
| Ttk1 number 91042 | 60 | 70 | 70 | 70 |
| Ttk1 number 9010 9122002-9 | 50 | 80 | 80 | 80 |
| Ttk1 number 9010 9422001-8 | 50 | 80 | 80 | 80 |
| Stabilisation machines | | | | |
| Ttk2 numbers 841, 844, 849 ¹¹ | 60 | 80 | 80 | 80 |
| Ttk2 number 842 ¹¹ | 35 | 60 | 60 | 80 |
| Ttk2 numbers 850, 856 | 20 | 60 | 80 | 90 (100) |
| Ttk2 numbers 851–855 ¹¹ | 50 | 50 (80) | 50 (80) | 50 (80) |
| Ttk2 number 857 | 20 | 60 | 80 | 80 (100) |
| Ttk2 number 858 | – ¹⁴ | 60 | 75 | 90 (100) |
| Ttk2 number 859 | 20 ¹⁴ | 60 | 75 | 90 (100) |
| Ttk2 number 91051 | 15 | 35 | 50 | 70 ¹⁵ |
| Ballast compacting machines | | | | |
| Ttk3 numbers 862, 863 ¹¹ | 60 | 80 | 80 | 80 |
| Tamping machines | | | | |
| Ttk4 number 91501 | 20 | 40 | 40 | 40 |
| Ttk5 numbers 9010 9422001-8 | 50 | 80 | 80 | 80 |
| Service and inspection vehicles on electrified lines | | | | |
| Tta numbers 1, 2 | 30 ¹⁶ | 30 ¹⁶ | 50 ¹⁶ | 50 ¹⁶ |

¹² Max. axle load of trailer vehicle 160 kN (16 t).

¹³ 15 km/h in turnouts.

¹⁴ Max. 20 km/h on sidings which belong to railway category A.

¹⁵ Max. hauling speed 80 km/h.

¹⁶ 5 km/h in diamond crossing with slips, due to the small wheel diameter (440 mm).

| Superstructure category | | | | |
|-------------------------------|------------------|------------------|-----------------------|-----------------------|
| Tta number 3 | 30 ¹⁶ | 50 ¹⁶ | 70 ¹⁶ | 70 ¹⁶ |
| Tte numbers 21–29 | 70 | 100 | 110 | 110 |
| Tte numbers 91201, 91202 | 20 | 60 | 80 | 80 |
| Ttv numbers 6, 9, 12, 15 | 50 | 70 | 70 | 90 |
| Rail-mounted cranes | | | | |
| Tnk4 numbers 982, 983 | 15 (20) | 15 (50) | 15 (60) | 15 (60) |
| Tnk4 number 984 | 15 (50) | 15 (60) | 15 (60) | 15 (60) |
| Tnk4 numbers 985–989 | 15 (60) | 15 (60) | 15 (60) | 15 (60) |
| Tnk4 number 990 | 15 (20) | 15 (50) | 15 (60) ¹⁷ | 15 (60) ¹⁷ |
| Electrification trains | | | | |
| Tnv-sr numbers 911002, 911003 | 40 (40) | 40 (60) | 40 (80) | 40 (100) |

MAXIMUM SPEED FOR MUSEUM LOCOMOTIVES

(Hauling speed in brackets, whether it differs from the maximum speed when self-propelled)

| Superstructure category | | | | |
|-------------------------|------------------|------------------|----------------|-------------------------------------|
| Series | A ¹⁸ | B ₁ | B ₂ | C ₁ , C ₂ , D |
| Dr12 | 20 ¹⁹ | 60 ²⁰ | 90 | 120 |
| Dr13 | 20 ¹⁹ | 100 | 110 | 120 |
| Dv15 | 60 | 75 (80) | 75 (80) | 75 (80) |
| Dv16 | 60 | 85 | 85 | 85 |
| Hr1 | 20 ¹⁹ | 80 | 100 | 110 ²¹ |
| Hv1 | 60 | 80 | 80 | 80 |
| Hv3 | 20 ²² | 70 | 70 | 70 |
| Pr1 | 20 ¹⁹ | 80 | 80 | 80 |
| Tk3 | 60 | 60 | 60 | 60 |
| Tr1 | 20 ¹⁹ | 80 | 80 | 80 |
| Vr1 | 40 ²³ | 40 | 40 | 40 |
| Rau 2 | 70 | 70 | 70 | 70 |
| Dm7 | 70 | 95 | 95 | 95 |
| Dm9 | 50 | 100 | 110 | 120 |

USE OF LOCOMOTIVES ON TRACKS BELONGING TO SUPERSTRUCTURE CATEGORY A

Locomotives of the Dr and Sr series must not operate on tracks belonging to superstructure category A. Locomotives of the Dr and Sr series are allowed to operate at a maximum speed of 20 km/h on sidings when carrying out renewal work. Other types of locomotives may operate at a maximum speed of 50 km/h on tracks belonging to superstructure category A.

¹⁷ Hauling speed 80 km/h, when the balance weight has been moved to the crane trailer.

¹⁸ For tracks belonging to superstructure category A, see USE OF LOCOMOTIVES ON TRACKS BELONGING TO SUPERSTRUCTURE CATEGORY A.

¹⁹ Operation only allowed on sidings.

²⁰ 80 km/h on the line sections Orivesi–Haapamäki and Haapamäki–Jyväskylä.

²¹ 100 km/h without wagons, either on its own or with double heading.

²² Max. speed 20 km/h in the deflecting section of K30 turnouts.

²³ 25 km/h on its own.

TRANSPORT OF OVERWEIGHT WAGONS

A wagon whose axle load exceeds the maximum axle load given for the different line sections in the appendix 6 is overweight for that line section. The terms for transporting wagons with an axle load over 225 kN in eastern transit traffic are listed below.

The load specified in the wagon load table may not be exceeded intentionally. Any excess load must be unloaded at the first possible traffic operating point, if the load exceeds the permitted load by more than 5% when the maximum axle load is 225 kN or by more than 2% when the maximum axle load is 250 kN.

Overweight wagons must be transported in line with the regulations governing exceptional transport. Before transport the wagon's wheel sets and the rest of the bogie structure must be inspected.

Temporary transport of overweight wagons can be considered in case of ad hoc need. Any temporary transport of overweight loads must be notified to the track's maintenance operator with a view to monitoring the condition of the track superstructure.

Transport of overweight wagons in the domestic and western transit traffic

When the maximum axle load of a wagon is 225 kN, individual wagons bearing excess weight may be transported at no more than the following speeds:

| Superstructure category | Maximum axle load kN | Speed km/h |
|-------------------------|----------------------|------------------|
| A | 225 ²⁴ | 20 ²⁴ |
| B1 | 235 | 35 |
| B2 | 235 | 50 |
| C1, C2, D | 235 | 80 |

Transport of wagons with an axle load over 225 kN in the eastern transit traffic and on line sections belonging to superstructure categories C and D, on which it is allowed to operate with a maximum axle load of 250 kN.

Maximum axle load 245 kN.

In the eastern transit traffic, individual wagons with an axle load over 225 kN, but no more than 245 kN, may be transported at the speed limit imposed on axle loads exceeding 225 kN.

Maximum speed 60 km/h.

²⁴ On main lines and secondary tracks belonging to superstructure category A, individual overweight wagons with axle loads exceeding 200 kN, but no more than 225 kN, may only be transported on a temporary basis at a speed of 20 km/h. It is prohibited to operate wagons with an axle load exceeding 225 kN on main lines and secondary tracks.

Transport of wagons with an axle load over 225 kN in the eastern transit traffic and on line sections belonging to superstructure categories C and D, on which it is allowed to operate with a maximum axle load of 225 kN.

- a) Axle load over 225 kN, but no more than 235 kN

Maximum speed 60 km/h.

Maximum axle load 235 kN.

In the eastern transit traffic, individual wagons with an axle load over 225 kN, but no more than 235 kN, may be transported at the speed limit imposed on axle loads exceeding 225 kN.

- b) Axle load over 235 kN

In case the axle load of a wagon in the eastern transit traffic exceeds 235 kN, the Rail Traffic Management Centre at the Finnish Transport Agency grants transport permits up to an axle load of 245 kN on the line sections listed below. For other line sections, permission must be granted by the Infrastructure and Environment Department at the Finnish Transport Agency. The wagons must be transported as abnormal loads at the speed specified in the permit.

Kerava–Sköldvik
Tampere–Seinäjoki
Lielähti–Kokemäki
Kokemäki–Harjavalta
Kokemäki–Rauma
Seinäjoki–Oulu
Kokkola–Ykspihlaja
Tuomioja–Raahe
Raahe–Rautaruukki
Riihimäki–Hakosilta
Kouvola–Kotka
Kotka Hovinsaari–Kotka Mussalo
Juurikorpi–Hamina
Luumäki–Joensuu
Imatra tavara–Imatrankoski-raja
Niirala-raja–Säkäniemi
Joensuu–Uimaharju
Kouvola–Pieksämäki
Pieksämäki–Kontiomäki
Pieksämäki–Joensuu
Siilinjärvi–Viinijärvi
Iisalmi–Ylivieska
Oulu–Laurila
Laurila–Tornio
Tornio–Röyttä
Oulu–Kontiomäki
Kontiomäki–Vartius-raja

Transport of wagons with an axle load over 225 kN in the eastern transit traffic on a line section belonging to superstructure category B.

Individual wagons with axle loads exceeding 235 kN may temporarily be transported as abnormal loads on a line section belonging to superstructure category B1 at a speed of 35 km/h, and at 50 km/h on a line section belonging to superstructure category B2. A permit for this must be granted by the Rail Traffic Management Centre at the Finnish Transport Agency.

Transport of wagons with axle loads over 225 kN in the eastern transit traffic on tracks and in turnouts with K30 and K33 rail profiles.

It is prohibited to operate wagons with an axle load exceeding 225 kN in the eastern transit traffic on tracks and in turnouts with K30 and K33 rail profiles.

TRANSPORT OF WAGONS COMPLYING WITH THE RUSSIAN STANDARD (FOR EASTERN TRANSIT TRAFFIC)

If the train contains at least one goods wagon which complies with the Russian standard, the maximum speed on the sidings between the following traffic operating points or their parts is 20 km/h.

| | |
|--|---|
| Helsinki-Turku satama Kauniainen | Riihimäki-Tampere — |
| Huopalahti-Vantaankoski — | Toijala-Turku — |
| Hyvinkää-Karjaa — | Toijala-Valkeakoski — |
| Karjaa-Hanko Hanko | Tampere-Seinäjoki Ylöjärvi Parkano Ratikylä Peräseinäjoki Seinäjoki asema Seinäjoki tavara |
| Turku-Uusikaupunki — | Lielähti-Kokemäki — |
| Uusikaupunki-Hangonsaari — | Kokemäki-Pori Pori |
| Raisio-Naantali — | Pori-Mäntyluoto Pori Mäntyluoto |
| Helsinki-Riihimäki — | Mäntyluoto-Tahkoluoto Mäntyluoto |
| Kerava-Hakosilta — | Kokemäki-Rauma — |
| Kerava-Sköldvik — | |
| Kerava-Vuosaari — | |

Kiukainen-Säkylä

—

Niinisalo-Parkano-Kihniö
 Parkano

Seinäjoki-Vaasa
 Seinäjoki asema
 Seinäjoki tavara

Seinäjoki-Kaskinen
 Seinäjoki asema
 Seinäjoki tavara
 Kaskinen

Seinäjoki-Oulu
 Seinäjoki asema
 Seinäjoki tavara
 Lapua
 Jepua
 Pännäinen
 Kälviä
 Kannus
 Eskola
 Sievi
 Ylivieska
 Oulainen
 Kilpua
 Vihanti
 Tuomioja
 Oulu tavara

Pännäinen-Pietarsaari
 Pännäinen
 Pietarsaari

Tuomioja-Raahe

—

Riihimäki-Kouvola

—

Kouvola-Kuusankoski
 Kuusankoski

Lahti-Heinola
 Heinola

Lahti-Loviisan satama

—

Kouvola-Kotka
 Kymi

Kotka Hovinsaari-Kotka Mussalo

—

Juurikorpi-Hamina

—

Kouvola-Joensuu
 Joensuu Peltola
 Joensuu asema

Luumäki-Vainikkala-raja

—

Imatra tavara-Imatrankoski-raja

—

Niirala-raja-Säkäniemi
 Tohmajärvi

Joensuu-Ilomantsi
 Joensuu Peltola
 Joensuu asema

Joensuu-Nurmes
 Joensuu Peltola
 Joensuu asema

Nurmes-Kontiomäki
 Valtimo
 Vuokatti

Kouvola-Pieksämäki
 Pieksämäki asema
 Pieksämäki Temu
 Pieksämäki lajittelu
 Pieksämäki tavara

Mynttilä-Ristiina
 Ristiina

Pieksämäki-Kontiomäki
 Pieksämäki asema
 Pieksämäki Temu
 Pieksämäki lajittelu
 Pieksämäki tavara
 Haapakoski
 Markkala
 Suonenjoki
 Salminen
 Kurkimäki
 Kuopio asema
 Kuopio tavara
 Murtomäki

Pieksämäki–Joensuu

Pieksämäki asema
 Pieksämäki Temu
 Pieksämäki lajittelu
 Pieksämäki tavara
 Varkaus
 Heinävesi
 Joensuu asema
 Joensuu Peltola

Murtomäki–Talvivaara

Murtomäki

Varkaus–Kommila

Varkaus
 Kommila

Huutokoski–Savonlinna

—

Savonlinna–Parikkala

Kerimäki
 Punkaharju

Siilinjärvi–Viinijärvi

—

Tampere–Jyväskylä

—

Orivesi–Seinäjoki

Vilppula
 Ähtäri
 Alavus

Vilppula–Mänttä

Vilppula

Haapamäki–Jyväskylä

Keuruu

Jyväskylä–Pieksämäki

Pieksämäki asema
 Pieksämäki Temu
 Pieksämäki lajittelu
 Pieksämäki tavara

Jyväskylä–Äänekoski

—

Äänekoski–Haapajärvi

Haapajärvi

Iisalmi–Ylivieska

Pyhäsalmi
 Haapajärvi

Pyhäkumpu erkanemisvaihte-

Pyhäkumpu

—

Oulu–Laurila

Oulu tavara

Laurila–Tornio-raja

—

Tornio–Kolari

Pello

Laurila–Kemijärvi

Rovaniemi
 Kemijärvi

Kemijärvi–Isokylä

Kemijärvi

Oulu–Kontiomäki

Paltamo
 Oulu tavara

Kontiomäki–Ämmänsaari

Hyrnsalmi
 Pesiökylä
 Ämmänsaari

Kontiomäki–Vartius-raja

Monitoring of Rolling Stock

Rolling stock monitoring equipment

The location of the equipment for monitoring rolling stock in the railway network is illustrated in figure 1.




Figure 1. Rolling stock monitoring equipment.

Matters concerning wheel flats

Each passing train must be monitored to detect wheel defects, overheated bearings or brakes, an uneven or unstable load, or something else potentially alarming. The monitoring should be carried out on both sides of the train, whenever there is sufficient staff. If a defect or deficiency is detected, it should be addressed immediately or the unit detached from the train. The unit with defective wheels should, if possible, be transported in the same train to the nearest depot, unless this causes apparent danger or damage, and the maintainer of the vehicle unit should be notified.

The wheel condition can be monitored both manually and with automatic measuring devices. In the monitoring process the following measures should be taken:

- I. If harmful wheel flats are detected, the length of the notch should be measured at the next stop. Further transport of a unit with a wheel flat is permitted on the following conditions:
 - a) If the length of the notch is less than 45 mm, no direct action is required
 - b) If the length of the notch is 46–60 mm and the outdoor temperature is below -10°C , the maximum speed allowed is 10 km/h. No speed limit when the temperature $\geq -10^{\circ}\text{C}$; the speed range 20–45 km/h should however be avoided. The wheelset must be replaced at the next depot.
 - c) If the length of the notch is 61–80 mm, the maximum speed allowed is 10 km/h. The wheelset must be replaced at the next depot.
 - d) If the length of the notch or the combined notches is more than 80 mm, the wheelset must be replaced at the station where the notch is measured.
 - e) If an overweight wagon has an over 45 mm long notch, the load should be lightened at the nearest station or the wagon should be transported at a maximum speed of 10 km/h to the nearest depot.
- II. The Q_{imp} limit values of the dynamic percussion force of the wheels on the rail have been specified in the table below. This force is usually caused by defects in the running surface of the wheel, such as notches, roughness or ovalisation. The dynamic force f_{dyn} indicates the ratio of wheel force variation for an unloaded wagon.

These forces are measured by wheel-flat detectors. The locations of these detectors are illustrated in figure 1.

| Type of message | Level | Limit | Measures |
|--------------------------------------|-------|----------|---|
| Dynamic force Q_{imp} | Q5 | > 500 kN | Must be detached from the train; max. speed 50 until detached |
| | Q4 | > 450 kN | Max. speed 50 right after the message. The wheelset must be repaired before the next loading. |
| | Q3 | > 350 kN | No speed limit; must be repaired before the next loading. If the same unit causes at least a Q3 alarm after the following loading, the measures required for Q4 must be taken |
| | Q2 | > 300 kN | Must be repaired at the next depot, at the latest. |
| | Q1 | > 250 kN | The maintainer can schedule the repair. |
| | | | |
| Dynamic coefficient f_{dyn} | f3 | > 800 % | Must be repaired before the next loading. If the same unit causes at least an f3 alarm after the following loading, the measures required for Q4 must be taken |
| | f2 | > 600 % | Must be repaired at the next depot, at the latest |
| | f1 | > 400 % | The maintainer can schedule the repair. |
| | | | |



Finnish Transport Agency

ISSN-L 1798-8276
ISSN 1798-8284
ISBN 978-952-255-383-6
www.liikennevirasto.fi
